

Ethernet Switch



Version 3.60 8/2005





Copyright © 2005 by ZyXEL Communications Corporation.

The contents of this publication may not be reproduced in any part or as a whole, transcribed, stored in a retrieval system, translated into any language, or transmitted in any form or by any means, electronic, mechanical, magnetic, optical, chemical, photocopying, manual, or otherwise, without the prior written permission of ZyXEL Communications Corporation.

Published by ZyXEL Communications Corporation. All rights reserved.

Disclaimer

ZyXEL does not assume any liability arising out of the application or use of any products, or software described herein. Neither does it convey any license under its patent rights nor the patent rights of others. ZyXEL further reserves the right to make changes in any products described herein without notice. This publication is subject to change without notice.

Interference Statements and Warnings

FCC Statement

This switch complies with Part 15 of the FCC rules. Operation is subject to the following two conditions:

- 1 This switch may not cause harmful interference.
- **2** This switch must accept any interference received, including interference that may cause undesired operations.

FCC Warning

This equipment has been tested and found to comply with the limits for a Class A digital switch, pursuant to Part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference in a commercial environment. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with the instruction manual, may cause harmful interference to radio communications. Operation of this equipment in a residential area is likely to cause harmful interference in which case the user will be required to correct the interference at his own expense.

CE Mark Warning:

This is a class A product. In a domestic environment this product may cause radio interference in which case the user may be required to take adequate measures.

Taiwanese BSMI (Bureau of Standards, Metrology and Inspection) A Warning:

警告使用者 這是甲類的資訊產品,在居住的環境使用時, 可能造成射頻干擾,在這種情況下, 使用者會被要求採取某些適當的對策.

Notice 1

Changes or modifications not expressly approved by the party responsible for compliance could void the user's authority to operate the equipment.

This Class A digital apparatus complies with Canadian ICES-003.

Cet appareil numérique de la classe A est conforme à la norme NMB-003 du Canada.

Certifications

- **1** Go to www.zyxel.com
- **2** Select your product from the drop-down list box on the ZyXEL home page to go to that product's page.
- **3** Select the certification you wish to view from this page.

Registration

Register your product online for free future product updates and information at www.zyxel.com for global products, or at www.us.zyxel.com for North American products.

Safety Warnings

For your safety, be sure to read and follow all warning notices and instructions.

- To reduce the risk of fire, use only No. 26 AWG (American Wire Gauge) or larger telecommunication line cord.
- Do NOT open the device or unit. Opening or removing covers can expose you to dangerous high voltage points or other risks. ONLY qualified service personnel can service the device. Please contact your vendor for further information.
- Use ONLY the dedicated power supply for your device. Connect the power cord or power adaptor to the right supply voltage (110V AC in North America or 230V AC in Europe).
- Do NOT use the device if the power supply is damaged as it might cause electrocution.
- If the power supply is damaged, remove it from the power outlet.
- Do NOT attempt to repair the power supply. Contact your local vendor to order a new power supply.
- Place connecting cables carefully so that no one will step on them or stumble over them. Do NOT allow anything to rest on the power cord and do NOT locate the product where anyone can walk on the power cord.
- If you wall mount your device, make sure that no electrical, gas or water pipes will be damaged.
- Do NOT install nor use your device during a thunderstorm. There may be a remote risk of electric shock from lightning.
- Do NOT expose your device to dampness, dust or corrosive liquids.
- Do NOT use this product near water, for example, in a wet basement or near a swimming pool.
- Make sure to connect the cables to the correct ports.
- Do NOT obstruct the device ventilation slots, as insufficient airflow may harm your device.
- Do NOT store things on the device.
- Connect ONLY suitable accessories to the device.



ZyXEL Limited Warranty

ZyXEL warrants to the original end user (purchaser) that this product is free from any defects in materials or workmanship for a period of up to two years from the date of purchase. During the warranty period, and upon proof of purchase, should the product have indications of failure due to faulty workmanship and/or materials, ZyXEL will, at its discretion, repair or replace the defective products or components without charge for either parts or labor, and to whatever extent it shall deem necessary to restore the product or components to proper operating condition. Any replacement will consist of a new or re-manufactured functionally equivalent product of equal value, and will be solely at the discretion of ZyXEL. This warranty shall not apply if the product is modified, misused, tampered with, damaged by an act of God, or subjected to abnormal working conditions.

Note

Repair or replacement, as provided under this warranty, is the exclusive remedy of the purchaser. This warranty is in lieu of all other warranties, express or implied, including any implied warranty of merchantability or fitness for a particular use or purpose. ZyXEL shall in no event be held liable for indirect or consequential damages of any kind of character to the purchaser.

To obtain the services of this warranty, contact ZyXEL's Service Center for your Return Material Authorization number (RMA). Products must be returned Postage Prepaid. It is recommended that the unit be insured when shipped. Any returned products without proof of purchase or those with an out-dated warranty will be repaired or replaced (at the discretion of ZyXEL) and the customer will be billed for parts and labor. All repaired or replaced products will be shipped by ZyXEL to the corresponding return address, Postage Paid. This warranty gives you specific legal rights, and you may also have other rights that vary from country to country.

Customer Support

Please have the following information ready when you contact customer support.

- Product model and serial number.
- Warranty Information.
- Date that you received your device.
- Brief description of the problem and the steps you took to solve it..

METHOD	SUPPORT E-MAIL	TELEPHONE*	WEB SITE		
LOCATION	SALES E-MAIL	FAX	FTP SITE	REGULAR MAIL	
CORPORATE HEADQUARTERS	support@zyxel.com.tw	+886-3-578-3942	www.zyxel.com www.europe.zyxel.com	ZyXEL Communications Corp. 6 Innovation Road II Science Park	
(WORLDWIDE)	sales@zyxel.com.tw	+886-3-578-2439	ftp.zyxel.com ftp.europe.zyxel.com	Hsinchu 300 Taiwan	
	info@cz.zyxel.com	+420 241 091 350	www.zyxel.cz	ZyXEL Communications Czech s.r.o.	
CZECH REPUBLIC	info@cz.zyxel.com	+420 241 091 359		Modranská 621 143 01 Praha 4 - Modrany Ceská Republika	
	support@zyxel.dk	+45 39 55 07 00	www.zyxel.dk	ZyXELCommunicationsA/S	
DENMARK	sales@zyxel.dk	+45 39 55 07 07		Columbusvej 5 2860 Soeborg Denmark	
	support@zyxel.fi	+358-9-4780-8411	www.zyxel.fi	ZyXEL Communications Oy Malminkaari 10	
FINLAND	sales@zyxel.fi	+358-9-4780 8448		00700 Helsinki Finland	
	info@zyxel.fr	+33 (0)4 72 52 97 97	www.zyxel.fr	ZyXEL France 1 rue des Vergers	
FRANCE		+33 (0)4 72 52 19 20		Bat. 1 / C 69760 Limonest France	
	support@zyxel.de	+49-2405-6909-0	www.zyxel.de	ZyXEL Deutschland GmbH.	
GERMANY	sales@zyxel.de	+49-2405-6909-99		Adenauerstr. 20/A2 D-52146 Wuerselen Germany	
	support@zyxel.com	+1-800-255-4101 +1-714-632-0882	www.us.zyxel.com	ZyXEL Communications Inc. 1130 N. Miller St.	
NORTH AMERICA	sales@zyxel.com	+1-714-632-0858	ftp.us.zyxel.com	Anaheim CA 92806-2001 U.S.A.	
	support@zyxel.no	+47 22 80 61 80	www.zyxel.no	ZyXELCommunicationsA/S	
NORWAY	sales@zyxel.no	+47 22 80 61 81		Nils Hansens vei 13 0667 Oslo Norway	
	support@zyxel.es	+34 902 195 420	www.zyxel.es	ZyXEL Communications	
SPAIN	sales@zyxel.es	+34 913 005 345		Alejandro Villegas 33 1º, 28043 Madrid Spain	
SWEDEN	support@zyxel.se	+46 31 744 7700	www.zyxel.se	ZyXEL Communications A/S Sjöporten 4, 41764 Göteborg	
	sales@zyxel.se	+46 31 744 7701		Sweden	

METHOD	SUPPORT E-MAIL	TELEPHONE*	WEB SITE	REGULAR MAIL	
LOCATION	SALES E-MAIL	FAX	FTP SITE		
	support@zyxel.co.uk	+44 (0) 1344 303044 08707 555779 (UK only)	www.zyxel.co.uk	ZyXEL Communications UK Ltd.,11 The Courtyard,	
UNITED KINGDOM	sales@zyxel.co.uk	+44 (0) 1344 303034	ftp.zyxel.co.uk	Eastern Road, Bracknell, Berkshire, RG12 2XB, United Kingdom (UK)	

 * "+" is the (prefix) number you enter to make an international telephone call.

Table of Contents

Copyright	1
Interference Statements and Warnings	2
ZyXEL Limited Warranty	4
Customer Support	5
Table of Contents	7
List of Figures	15
List of Tables	19
Preface	21
Chapter 1 Getting to Know Your Switch	23
1.1 Introduction	23
1.2 Software Features	23
1.3 Hardware Features	25
1.4 Applications	25
1.4.1 Backbone Application	25
1.4.2 Bridging Example	
1.4.3 High Performance Switched Example	
1.4.4 IEEE 802.1Q VLAN Application Examples	
1.4.4.1 Tag-based VLAN Example	
1.4.4.2 VLAN Shared Server Example	28
Chapter 2 Hardware Installation and Connection	29
2.1 Freestanding Installation	
2.2 Mounting the Switch on a Rack	
2.2.1 Rack-mounted Installation Requirements	
2.2.1.1 Precautions	
2.2.2 Attaching the Mounting Brackets to the Switch	
2.2.3 Mounting the Switch on a Rack	
Chapter 3 Hardware Overview	33
3.1 Front Panel Connection	

	3.1.1 Console Port	
	3.1.2 Ethernet Ports	
	3.1.2.1 Default Ethernet Settings	
	3.1.3 Mini-GBIC Slots	
	3.1.3.1 Transceiver Installation	
	3.1.3.2 Transceiver Removal	
	3.2 Rear Panel	
	3.2.1 Power Connector	
	3.3 Front Panel LEDs	
Chapt	ter 4	
The W	/eb Configurator	39
	4.1 Introduction	
	4.2 System Login	
	4.3 The Status Screen	
	4.3.1 Change Your Password	
	4.4 Switch Lockout	
	4.5 Resetting the Switch	
	4.5.1 Reload the Factory-default Configuration File	
3.1.2.1 Default Ethernet Settings 3.1.3 Mini-GBIC Slots 3.1.3.1 Transceiver Installation 3.1.3.2 Transceiver Removal 3.2 Rear Panel 3.2.1 Power Connector 3.3 Front Panel LEDs Chapter 4 The Web Configurator 4.1 Introduction 4.2 System Login 4.3 The Status Screen 4.3.1 Change Your Password 4.4 Switch Lockout 4.5 Resetting the Switch 4.5.1 Reload the Factory-default Configuration File 4.6 Logging Out of the Web Configurator 4.7 Help Chapter 5 Initial Setup Example 5.1 Overview 5.1.2 Setting Port VID 5.1.3 Configuring Switch Management IP Address Chapter 6 System Status and Port Statistics 6.1 Overview 6.2.1 Status: Port Details Chapter 7 Basic Setting 7.1 Overview 7.2 System Information 7.3 General Setup 7.4 Introduction to VLANs 7.5 IGMP Snooping		
	4.7 Help	
		47
	5.1 Overview	47
	5.1.1 Creating a VLAN	
	5.1.2 Setting Port VID	
	5.1.3 Configuring Switch Management IP Address	49
	•	
		55
	•	
3.1.2 Ethernet Ports 3.1.3.1 Default Ethernet Settings 3.1.3 Mini-GBIC Slots 3.1.3.1 Transceiver Installation 3.1.3.2 Transceiver Removal 3.2 Rear Panel 3.2.1 Power Connector 3.3 Front Panel LEDs Chapter 4 The Web Configurator 4.1 Introduction 4.2 System Login 4.3 The Status Screen 4.3.1 Change Your Password 4.4 Switch Lockout 4.5 Resetting the Switch 4.5.1 Reload the Factory-default Configuration File 4.6 Logging Out of the Web Configurator 4.7 Help Chapter 5 Initial Setup Example 5.1 Overview 5.1.1 Creating a VLAN 5.1.2 Setting Port VID 5.1.3 Configuring Switch Management IP Address Chapter 6 System Status and Port Statistics 6.1 Overview 6.2 Port Status Summary 6.2.1 Status: Port Details Chapter 7 Basic Setting 7.1 Overview 7.2 System Information 7.3 General Setup 7.4 Introduction to VLANs <t< td=""><td></td></t<>		

7.7 IP Setup	60
7.7.1 Management IP Addresses	60
7.8 Port Setup	62
Chapter 8	
VLAN	65
0.4 Introduction to IEEE 002.40 Taggod V/LAN	05
8.1 Introduction to IEEE 802.1Q Tagged VLAN	
8.1.1 Forwarding Tagged and Untagged Frames	
8.2 Automatic VLAN Registration	
8.2.1 GARP	
8.2.1.1 GARP Timers	
8.2.2 GVRP	
8.3 Port VLAN Trunking	
8.4 Select the VLAN Type	
8.5 Static VLAN	
8.5.1 Static VLAN Status	
8.5.2 Configure a Static VLAN	
8.5.3 Configure VLAN Port Settings	
8.6 Port-based VLAN Setup	
8.6.1 Configure a Port-based VLAN	72
Chapter 9	
Static MAC Forwarding	77
9.1 Overview	77
9.2 Configuring Static MAC Forwarding	
Chapter 10	
Filtering	79
10.1 Overview	79
10.2 Configure a Filtering Rule	79
Chapter 11 Spanning Tree Brotocol	04
Spanning Tree Protocol	01
11.1 Overview	81
11.1.1 STP Terminology	81
11.1.2 How STP Works	82
11.1.3 STP Port States	82
11.2 STP Status	82
11.3 Configure STP	84
Chapter 12	
Chapter 12 Bandwidth Control	87
12.1 Bandwidth Control Setup	87

Chapter 13 Broadcast Storm Control	89
13.1 Overview	
13.2 Broadcast Storm Control Setup	
Chapter 14	
Mirroring	
14.1 Overview	91
14.2 Port Mirroring Setup	91
Chapter 15	
Link Aggregation	
15.1 Overview	
15.2 Dynamic Link Aggregation	
15.2.1 Link Aggregation ID	
15.3 Link Aggregation Status	
15.4 Link Aggregation Setup	
Chapter 16 Port Authentication	
16.1 Overview	
16.1.1 RADIUS	
16.2 Port Authentication Configuration	
16.2.1 Activate IEEE 802.1x Security	100
16.2.2 Configuring RADIUS Server Settings	101
Chapter 17 Port Security	103
17.1 Overview	103
17.2 Port Security Setup	
Chapter 18 Queuing Method	105
18.1 Overview	105
18.1.1 Strict Priority Queuing (SPQ)	
18.1.2 Weighted Round Robin Scheduling (WRR)	
18.2 Configuring Queuing Method	
Chapter 19 Static Route	107
19.1 Configuring Static Route	

Chapter 20 Differentiated Services	109
20.1 Overview	109
20.1.1 DSCP and Per-Hop Behavior	109
20.1.2 DiffServ Network Example	
20.2 Activating DiffServ	
20.3 DSCP-to-IEEE802.1p Priority Mapping	
20.3.1 Configuring DSCP Settings	
Chapter 21 Maintenance	113
21.1 The Maintenance Screen	
21.2 Firmware Upgrade	114
21.3 Restore a Configuration File	
21.4 Backing Up a Configuration File	115
21.5 Load Factory Defaults	115
21.6 Reboot System	116
21.7 FTP Command Line	116
21.7.1 Filename Conventions	116
21.7.1.1 Example FTP Commands	117
21.7.2 FTP Command Line Procedure	
21.7.3 GUI-based FTP Clients	118
21.7.4 FTP over WAN Restrictions	118
Chapter 22	440
Access Control	119
22.1 Overview	119
22.2 The Access Control Main Screen	119
22.3 About SNMP	120
22.3.1 Supported MIBs	121
22.3.2 SNMP Traps	121
22.3.3 Configuring SNMP	121
22.4 Setting Up Login Accounts	122
22.5 SSH Overview	123
22.6 How SSH works	124
22.7 SSH Implementation on the Switch	125
22.7.1 Requirements for Using SSH	125
22.7.2 SSH Login Example	125
22.8 Introduction to HTTPS	
22.9 HTTPS Example	
22.9.1 Internet Explorer Warning Messages	
22.9.2 Netscape Navigator Warning Messages	
22.9.3 The Main Screen	

22.10 Service Port Access Control	131
22.11 Remote Management	131
Chapter 23	
Diagnostic	133
23.1 Diagnostic	133
Chapter 24	
Cluster Management	135
24.1 Overview	135
24.2 Cluster Management Status	136
24.2.1 Cluster Member Switch Management	137
24.2.1.1 Uploading Firmware to a Cluster Member Switch	137
24.3 Configuring Cluster Management	138
Chapter 25	
MAC Table	141
25.1 Overview	
25.2 Viewing the MAC Table	
Chapter 26	
ARP Table	143
26.1 Overview	143
26.1.1 How ARP Works	143
26.2 Viewing the ARP Table	143
Chapter 27	
Introducing the Commands	145
27.1 Overview	
27.1.1 Switch Configuration File	
27.2 Accessing the CLI	145
27.2.1 Access Priority	146
27.2.2 The Console Port	
27.2.2.1 Initial Screen	
27.2.3 Telnet	146
27.2.4 SSH	147
27.3 The Login Screen	147
27.4 Command Syntax Conventions	148
27.5 Getting Help	148
27.5.1 List of Available Commands	148
27.5.2 Detailed Command Information	149
27.6 Command Modes	150
27.7 Using Command History	151

27.8 Saving Your Configuration	151
27.8.1 Logging Out	151
27.9 Command Summary	151
27.9.1 User Mode	
27.9.2 Enable Mode	
27.9.3 General Configuration Mode	
27.9.4 interface port-channel Commands	
27.9.5 config-vlan Commands	
Chanter 29	
Chapter 28 Command Examples	167
28.1 Overview	
28.2 show Commands	
28.2.1 show system-information	
28.2.2 show ip	
28.2.3 show logging	
28.2.4 show interface	
28.2.5 show mac address-table	
28.3 ping	170
28.4 traceroute	170
28.5 Enabling RSTP	171
28.6 Configuration File Maintenance	171
28.6.1 Restarting the Switch	171
28.6.2 Resetting to the Factory Default	172
28.7 no Command Examples	172
28.7.1 no mirror-port	172
28.7.2 no https timeout	173
28.7.3 no trunk	173
28.7.4 no port-access-authenticator	
28.7.5 no ssh	174
28.8 spq	175
28.9 wrr	175
28.10 interface Commands	
28.10.1 interface port-channel	
28.10.2 bmstorm-limit	
28.10.3 bandwidth-limit	177
28.10.4 mirror	177
28.10.5 gvrp	
28.10.6 frame-type	
28.10.7 egress set	
28.10.8 qos priority	
28.10.9 name	
28.10.10 speed-duplex	181

Chapter 29 IEEE 802.1Q Tagged VLAN Commands	183
29.1 IEEE 802.1Q Tagged VLAN Overview	183
29.2 VLAN Databases	183
29.2.1 Static Entries (SVLAN Table)	183
29.2.2 Dynamic Entries (DVLAN Table)	184
29.3 Configuring Tagged VLAN	184
29.4 Global VLAN1Q Tagged VLAN Configuration Commands	185
29.4.1 GARP Status	185
29.4.2 GARP Timer	185
29.4.3 GVRP Timer	186
29.4.4 Enable GVRP	186
29.4.5 Disable GVRP	187
29.4.6 Enable Ingress Checking	187
29.5 Port VLAN Commands	187
29.5.1 Set Port VID	187
29.5.2 Set Acceptable Frame Type	188
29.5.3 Enable or Disable Port GVRP	188
29.5.4 Modify Static VLAN	188
29.5.4.1 Modify a Static VLAN Table Example	189
29.5.4.2 Forwarding Process Example	189
29.5.5 Delete VLAN ID	190
29.6 Enable VLAN	190
29.7 Disable VLAN	191
29.8 Show VLAN Setting	191
Chapter 30 Troubleshooting	193
30.1 Problems Starting Up the Switch	193
30.2 Problems Accessing the Switch	193
30.2.1 Pop-up Windows, JavaScripts and Java Permissions	194
30.2.1.1 Internet Explorer Pop-up Blockers	194
30.2.1.2 JavaScripts	197
30.2.1.3 Java Permissions	199
30.3 Problems with the Password	201
Appendix A Product Specifications	203
Appendix B IP Subnetting	
Index	215

List of Figures

Figure 1 Backbone Application	26
Figure 2 Bridging Application	26
Figure 3 High Performance Switched Application	27
Figure 4 Tag-based VLAN Application	28
Figure 5 Shared Server Using VLAN Example	28
Figure 6 Attaching Rubber Feet	29
Figure 7 Attaching the Mounting Brackets	30
Figure 8 Mounting the Switch on a Rack	31
Figure 9 Front Panel	33
Figure 10 Transceiver Installation Example	35
Figure 11 Installed Transceiver	35
Figure 12 Opening the Transceiver's Latch Example	36
Figure 13 Transceiver Removal Example	36
Figure 14 Rear Panel	36
Figure 15 Web Configurator: Login	39
Figure 16 Web Configurator Home Screen (Status)	40
Figure 17 Change Administrator Login Password	44
Figure 18 Resetting the Switch: Via the Console Port	45
Figure 19 Web Configurator: Logout Screen	46
Figure 20 Initial Setup Network Example: VLAN	
Figure 21 Initial Setup Network Example: Port VID	49
Figure 22 Initial Setup Example: Management IP Address	. 50
Figure 23 Status	51
Figure 24 Status: Port Details	53
Figure 25 System Info	55
Figure 26 General Setup	56
Figure 27 Switch Setup	59
Figure 28 IP Setup	61
Figure 29 Port Setup	63
Figure 30 Port VLAN Trunking	67
Figure 31 Switch Setup: Select VLAN Type	68
Figure 32 VLAN: VLAN Status	68
Figure 33 VLAN: Static VLAN	70
Figure 34 VLAN: VLAN Port Setting	71
Figure 35 Port Based VLAN Setup (All Connected)	73
Figure 36 Port Based VLAN Setup (Port Isolation)	74
Figure 37 Static MAC Forwarding	77
Figure 38 Filtering	79

Figure 39 Spanning Tree Protocol: Status	83
Figure 40 Spanning Tree Protocol: Configuration	84
Figure 41 Bandwidth Control	87
Figure 42 Broadcast Storm Control	
Figure 43 Mirroring	91
Figure 44 Link Aggregation Control Protocol Status	94
Figure 45 Link Aggregation: Configuration	96
Figure 46 RADIUS Server	99
Figure 47 Port Authentication	100
Figure 48 Port Authentication: 802.1x	100
Figure 49 Port Authentication: RADIUS	101
Figure 50 Port Security	103
Figure 51 Queuing Method	106
Figure 52 Static Routing	107
Figure 53 DiffServ: Differentiated Service Field	109
Figure 54 DiffServ Network Example	110
Figure 55 DiffServ	110
Figure 56 DiffServ: DSCP Setting	111
Figure 57 Maintenance	113
Figure 58 Firmware Upgrade	114
Figure 59 Restore Configuration	114
Figure 60 Backup Configuration	115
Figure 61 Load Factory Default: Conformation	115
Figure 62 Load Factory Default: Start	116
Figure 63 Reboot System: Confirmation	116
Figure 64 Reboot System: Start	
Figure 65 Console Port Priority	119
Figure 66 Access Control	119
Figure 67 SNMP Management Model	120
Figure 68 Access Control: SNMP	122
Figure 69 Access Control: Logins	123
Figure 70 SSH Communication Example	124
Figure 71 How SSH Works	124
Figure 72 SSH Login Example	126
Figure 73 HTTPS Implementation	127
Figure 74 Security Alert Dialog Box (Internet Explorer)	128
Figure 75 Security Certificate 1 (Netscape)	128
Figure 76 Security Certificate 2 (Netscape)	129
Figure 77 Login Screen (Internet Explorer)	130
Figure 78 Login Screen (Netscape)	130
Figure 79 Access Control: Service Access Control	131
Figure 80 Access Control: Remote Management	132
Figure 81 Diagnostic	133

Figure 82 Clustering Application Example	135
Figure 83 Cluster Management: Status	136
Figure 84 Cluster Management: Cluster Member Web Configurator Screen	137
Figure 85 Example: Uploading Firmware to a Cluster Member Switch	138
Figure 86 Clustering Management Configuration	139
Figure 87 MAC Table Flowchart	141
Figure 88 MAC Table	142
Figure 89 ARP Table	144
Figure 90 Initial Console Port Screen	146
Figure 91 SSH Login Example	147
Figure 92 CLI Login	147
Figure 93 CLI Help: List of Commands: Example 1	149
Figure 94 CLI Help: List of Commands: Example 2	149
Figure 95 CLI Help: Detailed Command Information: Example 1	150
Figure 96 CLI: Help: Detailed Command Information: Example 2	150
Figure 97 CLI: History Command Example	151
Figure 98 CLI: write memory	
Figure 99 show system-information Command Example	
Figure 100 show ip Command Example	
Figure 101 show logging Command Example	
Figure 102 show interface Command Example	
Figure 103 show mac address-table Command Example	170
Figure 104 ping Command Example	
Figure 105 traceroute Command Example	171
Figure 106 Enable RSTP Command Example	
Figure 107 CLI: boot config Command Example	172
Figure 108 CLI: reload config Command Example	172
Figure 109 CLI: Reset to the Factory Default Example	172
Figure 110 no mirror-port Command Example	173
Figure 111 no https timeout Command Example	173
Figure 112 no trunk Command Example	174
Figure 113 no port-access-authenticator Command Example	174
Figure 114 no ssh Command Example	175
Figure 115 spq Command Example	175
Figure 116 wrr Command Example	176
Figure 117 interface Command Example	176
Figure 118 broadcast-limit Command Example	177
Figure 119 bandwidth-limit Command Example	177
Figure 120 mirror Command Example	178
Figure 121 gvrp Command Example	179
Figure 122 frame-type Command Example	179
Figure 123 egress set Command Example	180
Figure 124 qos priority Command Example	180

Figure 125 name Command Example	181
Figure 126 speed-duplex Command Example	
Figure 127 Tagged VLAN Configuration and Activation Example	
Figure 128 CPU VLAN Configuration and Activation Example	
Figure 129 GARP STATUS Command Example	
Figure 130 GARP Timer Command Example	
Figure 131 GVRP Status Command Example	
Figure 132 ingress-check Command Example	
Figure 133 vlan1q port default vid Command Example	
Figure 134 frame type Command Example	
Figure 135 no gvrp Command Example	
Figure 136 Modifying Static VLAN Example	
Figure 137 no vlan Command Example	
Figure 138 show vlan Command Example	
Figure 139 Pop-up Blocker	194
Figure 140 Internet Options	
Figure 141 Internet Options	
Figure 142 Pop-up Blocker Settings	197
Figure 143 Internet Options	
Figure 144 Security Settings - Java Scripting	
Figure 145 Security Settings - Java	
Figure 146 Java (Sun)	201

List of Tables

Table 1 Front Panel	. 33
Table 2 Front Panel LEDs	. 37
Table 3 Navigation Panel Sub-links Overview	.41
Table 4 Web Configurator Screen Sub-links Details	
Table 5 Navigation Panel Links	. 42
Table 6 Status	. 52
Table 7 Status: Port Details	. 53
Table 8 System Info	. 55
Table 9 General Setup	. 56
Table 10 Switch Setup	. 59
Table 11 IP Setup	. 61
Table 12 Port Setup	. 63
Table 13 IEEE 802.1Q VLAN Terminology	. 66
Table 14 VLAN: VLAN Status	. 69
Table 15 VLAN: Static VLAN	. 70
Table 16 VLAN: VLAN Port Setting	.71
Table 17 Port Based VLAN Setup	.75
Table 18 Static MAC Forwarding	.78
Table 19 Filtering	.79
Table 20 STP Path Costs	. 81
Table 21 STP Port States	. 82
Table 22 Spanning Tree Protocol: Status	. 83
Table 23 Spanning Tree Protocol: Configuration	. 84
Table 24 Bandwidth Control	. 87
Table 25 Broadcast Storm Control	. 90
Table 26 Mirroring	. 92
Table 27 Link Aggregation ID: Local Switch	. 94
Table 28 Link Aggregation ID: Peer Switch	. 94
Table 29 Link Aggregation Control Protocol Status	. 95
Table 30 Link Aggregation Control Protocol: Configuration	. 96
Table 31 Port Authentication: 802.1x	. 100
Table 32 Port Authentication: RADIUS	. 101
Table 33 Port Security	. 104
Table 34 Physical Queue Priority	. 105
Table 35 Queuing Method	
Table 36 Static Routing	. 107
Table 37 DiffServ	. 110
Table 38 Default DSCP-IEEE802.1p Mapping	. 111

Table 39 DiffServ: DSCP Setting	112
Table 40 Maintenance	113
Table 41 Filename Conventions	117
Table 42 Access Control Overview	119
Table 43 SNMP Commands	120
Table 44 SNMP Traps	121
Table 45 Access Control: SNMP	122
Table 46 Access Control: Logins	123
Table 47 Access Control: Service Access Control	131
Table 48 Access Control: Remote Management	132
Table 49 Diagnostic	
Table 50 ZyXEL Clustering Management Specifications	135
Table 51 Cluster Management: Status	136
Table 52 FTP Upload to Cluster Member Example	138
Table 53 Clustering Management Configuration	139
Table 54 MAC Table	142
Table 55 ARP Table	144
Table 56 Command Summary: User Mode	152
Table 57 Command Summary: Enable Mode	152
Table 58 Command Summary: Configuration Mode	
Table 59 interface port-channel Commands	162
Table 60 Command Summary: config-vlan Commands	164
Table 61 Troubleshooting the Start-Up of Your Switch	193
Table 62 Troubleshooting Accessing the Switch	193
Table 63 Troubleshooting the Password	201
Table 64 General Product Specifications	203
Table 65 Management Specifications	204
Table 66 Physical and Environmental Specifications	
Table 67 Classes of IP Addresses	207
Table 68 Allowed IP Address Range By Class	208
Table 69 "Natural" Masks	208
Table 70 Alternative Subnet Mask Notation	209
Table 71 Two Subnets Example	209
Table 72 Subnet 1	210
Table 73 Subnet 2	210
Table 74 Subnet 1	211
Table 75 Subnet 2	211
Table 76 Subnet 3	
Table 77 Subnet 4	212
Table 78 Eight Subnets	212
Table 79 Class C Subnet Planning	212
Table 80 Class B Subnet Planning	213



Congratulations on your purchase of the ES-2024A Ethernet Switch.

This preface introduces you to the ES-2024A Ethernet Switch and discusses the conventions of this User's Guide. It also provides information on other related documentation.

Note:	Register your product online to receive e-mail notices of firmware
	upgrades and information at www.zyxel.com for global products, or at
	www.us.zyxel.com for North American products.

About This User's Guide

This manual is designed to guide you through the installation and configuration of your ES-2024A for its various applications.

Related Documentation

• Web Configurator Online Help

Embedded web help for descriptions of individual screens and supplementary information.

• ZyXEL Glossary and Web Site

Please refer to www.zyxel.com for an online glossary of networking terms and additional support documentation.

Syntax Conventions

- "Enter" means for you to type one or more characters. "Select" or "Choose" means for you to use one of the predefined choices.
- Command and arrow keys are enclosed in square brackets. [ENTER] means the Enter, or carriage return key; [ESC] means the Escape key and [SPACE BAR] means the Space Bar.
- Mouse action sequences are denoted using a comma. For example, "click the Apple icon, **Control Panels** and then **Modem**" means first click the Apple icon, then point your mouse pointer to **Control Panels** and then click **Modem**.
- For brevity's sake, we will use "e.g.," as a shorthand for "for instance", and "i.e.," for "that is" or "in other words" throughout this manual.
- The ES-2024A Ethernet Switch may be referred to as "the ES-2024A" or "the switch" in this User's Guide.

Graphics Icons Key

ES-2024A	Computer	Server
Computer	DSLAM	Gateway
Central Office/ ISP	Internet	Hub/Switch
	\bigcirc	X

User Guide Feedback

Help us help you. E-mail all User Guide-related comments, questions or suggestions for improvement to techwriters@zyxel.com.tw or send regular mail to The Technical Writing Team, ZyXEL Communications Corp., 6 Innovation Road II, Science-Based Industrial Park, Hsinchu, 300, Taiwan. Thank you.

CHAPTER 1 Getting to Know Your Switch

This chapter introduces the main features and applications of the switch.

1.1 Introduction

The ES-2024A is a stand-alone layer-2 Ethernet switch with 24 10/100Mbps ports and two Gigabit Ethernet/mini-GBIC ports.

With its built-in web configurator, managing and configuring the switch is easy. In addition, the switch can also be managed via Telnet, SSH (Secure SHell), any terminal emulator program on the console port, or third-party SNMP management.

1.2 Software Features

This section describes the general software features of the switch.

DHCP Client

DHCP (Dynamic Host Configuration Protocol RFC 2131 and RFC 2132) allows individual computers to obtain TCP/IP configuration at start-up from a server. You can configure the switch as a DHCP client to obtain TCP/IP information (such as the IP address and subnet mask) from a DHCP server. If you disable the DHCP service, you must manually enter the TCP/IP information.

VLAN

A VLAN (Virtual Local Area Network) allows a physical network to be partitioned into multiple logical networks. Devices on a logical network belong to one group. A device can belong to more than one group. With VLAN, a device cannot directly talk to or hear from devices that are not in the same group(s); the traffic must first go through a router.

Differentiated Services (DiffServ)

With DiffServ, the switch marks packets so that they receive specific per-hop treatment at DiffServ-compliant network devices along the route based on the application types and traffic flow.

Queuing

Queuing is used to help solve performance degradation when there is network congestion. Two scheduling services are supported: Strict Priority Queuing (SPQ) and Weighted Round Robin (WRR). This allows the switch to maintain separate queues for packets from each individual source or flow and prevent a source from monopolizing the bandwidth.

Port Mirroring

Port mirroring allows you to copy traffic going from one or all ports to another or all ports in order that you can examine the traffic from the mirror port (the port you copy the traffic to) without interference.

Static Route

Static routes tell the switch how to forward IP traffic when you configure the TCP/IP parameters manually.

IGMP Snooping

The switch supports IGMP snooping enabling group multicast traffic to be only forwarded to ports that are members of that group; thus allowing you to significantly reduce multicast traffic passing through your switch.

STP (Spanning Tree Protocol) / RSTP (Rapid STP)

(R)STP detects and breaks network loops and provides backup links between switches, bridges or routers. It allows a switch to interact with other (R)STP -compliant switches in your network to ensure that only one path exists between any two stations on the network.

Link Aggregation

Link aggregation (trunking) is the grouping of physical ports into one logical higher-capacity link. You may want to trunk ports if for example, it is cheaper to use multiple lower-speed links than to under-utilize a high-speed, but more costly, single-port link.

Port Authentication and Security

For security, the switch allows authentication using IEEE 802.1x with an external RADIUS server and port security that allows only packets with dynamically learned MAC addresses and/or configured static MAC addresses to pass through a port on the switch.

Maintenance and Management Features

Access Control

You can specify the service(s) and computer IP address(es) to control access to the switch for management.

Cluster Management

Cluster management (also known as iStacking) allows you to manage switches through one switch, called the cluster manager. The switches must be directly connected and be in the same VLAN group so as to be able to communicate with one another.

Configuration and Firmware Maintenance

You can backup or restore the switch configuration or upgrade the firmware on the switch.

1.3 Hardware Features

This section describes the ports on the switch.

Ethernet Ports

The ports allow the switch to connect to another Ethernet devices.

Gigabit Ethernet Ports

The ports allow the switch to connect to another WAN switch or daisy-chain to other switches.

Mini-GBIC Slots

Install SPF transceivers in these slots to connect to other Ethernet switches at longer distances than the Ethernet port.

Console Port

Use the console port for local management of the switch.

1.4 Applications


This section shows a few examples of using the switch in various network environments.

1.4.1 Backbone Application

In this application, the switch is an ideal solution for small networks where rapid growth can be expected in the near future.

The switch can be used standalone for a group of heavy traffic users. You can connect computers directly to the switch's port or connect other switches to the switch.


In this example, all computers can share high-speed applications on the server. To expand the network, simply add more networking devices such as switches, routers, computers, print servers etc.



1.4.2 Bridging Example

In this example application the switch connects different company departments (**RD** and **Sales**) to the corporate backbone. It can alleviate bandwidth contention and eliminate server and network bottlenecks. All users that need high bandwidth can connect to high-speed department servers via the switch. You can provide a super-fast uplink connection by using a Gigabit Ethernet/mini-GBIC port on the switch.

Moreover, the switch eases supervision and maintenance by allowing network managers to centralize multiple servers at a single location.







1.4.3 High Performance Switched Example

The switch is ideal for connecting two networks that need high bandwidth. In the following example, use trunking to connect these two networks.

Switching to higher-speed LANs such as ATM (Asynchronous Transmission Mode) is not feasible for most people due to the expense of replacing all existing Ethernet cables and adapter cards, restructuring your network and complex maintenance. The switch can provide the same bandwidth as ATM at much lower cost while still being able to use existing adapters and switches. Moreover, the current LAN structure can be retained as all ports can freely communicate with each other.





1.4.4 IEEE 802.1Q VLAN Application Examples


This section shows a workgroup and a shared server example using 802.1Q tagged VLANs.

A VLAN (Virtual Local Area Network) allows a physical network to be partitioned into multiple logical networks. Stations on a logical network belong to one group. A station can belong to more than one group. With VLAN, a station cannot directly talk to or hear from stations that are not in the same group(s) unless such traffic first goes through a router.

For more information on VLANs, refer to Chapter 8, "VLAN," on page 65.

1.4.4.1 Tag-based VLAN Example


Ports in the same VLAN group share the same frame broadcast domain thus increase network performance through reduced broadcast traffic. VLAN groups can be modified at any time by adding, moving or changing ports without any re-cabling.



1.4.4.2 VLAN Shared Server Example

Shared resources such as a server can be used by all ports in the same VLAN as the server, as shown in the following example. In this example, only ports that need access to the server need belong to VLAN 1. Ports can belong to other VLAN groups too.

Figure 5 Shared Server Using VLAN Example




CHAPTER 2 Hardware Installation and Connection

This chapter shows you how to install and connect the switch.

2.1 Freestanding Installation

- **1** Make sure the switch is clean and dry.
- **2** Set the switch on a smooth, level surface strong enough to support the weight of the switch and the connected cables. Make sure there is a power outlet nearby.
- **3** Make sure there is enough clearance around the switch to allow air circulation and the attachment of cables and the power cord.
- **4** Remove the adhesive backing from the rubber feet.
- **5** Attach the rubber feet to each corner on the bottom of the switch. These rubber feet help protect the switch from shock or vibration and ensure space between devices when stacking.

Figure 6 Attaching Rubber Feet



Note: Do NOT block the ventilation holes. Leave space between devices when stacking.

For proper ventilation, allow at least 4 inches (10 cm) of clearance at the front and 3.4 inches (8 cm) at the back of the switch. This is especially important for enclosed rack installations.

2.2 Mounting the Switch on a Rack

This section lists the rack mounting requirements and precautions and describes the installation steps.

2.2.1 Rack-mounted Installation Requirements

- Two mounting brackets.
- Eight M3 flat head screws and a #2 Philips screwdriver.
- Four M5 flat head screws and a #2 Philips screwdriver.

Note: Failure to use the proper screws may damage the unit.


2.2.1.1 Precautions

- Make sure the rack will safely support the combined weight of all the equipment it contains.
- Make sure the position of the switch does not make the rack unstable or top-heavy. Take all necessary precautions to anchor the rack securely before installing the unit.

2.2.2 Attaching the Mounting Brackets to the Switch

1 Position a mounting bracket on one side of the switch, lining up the four screw holes on the bracket with the screw holes on the side of the switch.


Figure 7 Attaching the Mounting Brackets




- **2** Using a #2 Philips screwdriver, install the M3 flat head screws through the mounting bracket holes into the switch.
- **3** Repeat steps 1 and 2 to install the second mounting bracket on the other side of the switch.
- 4 You may now mount the switch on a rack. Proceed to the next section.

2.2.3 Mounting the Switch on a Rack

1 Position a mounting bracket (that is already attached to the switch) on one side of the rack, lining up the two screw holes on the bracket with the screw holes on the side of the rack.





- **2** Using a #2 Philips screwdriver, install the M5 flat head screws through the mounting bracket holes into the rack.
- **3** Repeat steps 1 and 2 to attach the second mounting bracket on the other side of the rack.


CHAPTER 3 Hardware Overview

This chapter describes the front panel and rear panel of the switch and shows you how to make the hardware connections.

3.1 Front Panel Connection

The figure below shows the front panel of the switch.

Figure 9 Front Panel



The following table describes the port labels on the front panel.

Table 1 Front Panel	Table 1	Front	Panel
---------------------	---------	-------	-------

LABEL	DESCRIPTION
CONSOLE	Only connect this port if you want to configure the switch using the command line interface (CLI) via the console port.
24 10/100 Mbps RJ-45 Ethernet Ports	Connect these ports to a computer, a hub, an Ethernet switch or router.
Gigabit Ethernet/ mini	Connect these Gigabit Ethernet ports to high-bandwidth backbone network Ethernet switches or use them to daisy-chain other switches.
GBIC ports	Alternatively, use mini-GBIC transceivers in these slots for fiber-optical connections to backbone Ethernet switches

3.1.1 Console Port

For local management, you can use a computer with terminal emulation software configured to the following parameters:

- VT100 terminal emulation
- 9600 bps

- No parity, 8 data bits, 1 stop bit
- No flow control

Connect the male 9-pin end of the console cable to the console port of the switch. Connect the female end to a serial port (COM1, COM2 or other COM port) of your computer.

3.1.2 Ethernet Ports

The switch has 24 10/100Mbps auto-negotiating, auto-crossover Ethernet ports. In 10/ 100Mbps Fast Ethernet, the speed can be 10Mbps or 100Mbps and the duplex mode can be half duplex or full duplex.

There are two pairs of Gigabit Ethernet/mini-GBIC ports. The mini-GBIC ports have priority over the Gigabit ports. This means that if a mini-GBIC port and the corresponding Gigabit port are connected at the same time, the Gigabit port will be disabled. The speed of the Gigabit Ethernet/mini-GBIC ports can be 100Mbps or 1000Mbps and the duplex mode can be half duplex (at 100 Mbps) or full duplex.

An auto-negotiating port can detect and adjust to the optimum Ethernet speed (10/100Mpbs) and duplex mode (full duplex or half duplex) of the connected device.

An auto-crossover (auto-MDI/MDI-X) port automatically works with a straight-through or crossover Ethernet cable.

3.1.2.1 Default Ethernet Settings

The factory default negotiation settings for the Ethernet ports on the switch are:

- Speed: Auto
- Duplex: Auto
- Flow control: off

3.1.3 Mini-GBIC Slots

These are slots for mini-GBIC (Gigabit Interface Converter) transceivers. A transceiver is a single unit that houses a transmitter and a receiver. The switch does not come with transceivers. You must use transceivers that comply with the SFP Transceiver MultiSource Agreement (MSA). See the SFF committee's INF-8074i specification Rev 1.0 for details.

There are two pairs of Gigabit Ethernet/mini-GBIC ports. The mini-GBIC ports have priority over the Gigabit ports. This means that if a mini-GBIC port and the corresponding Gigabit port are connected at the same time, the Gigabit port will be disabled.

You can change transceivers while the switch is operating. You can use different transceivers to connect to Ethernet switches with different types of fiber-optic connectors.


• Type: SFP connection interface


- Connection speed: 1 Gigabit per second (Gbps)
- **Note:** To avoid possible eye injury, do not look into an operating fiber-optic module's connectors.

3.1.3.1 Transceiver Installation

Use the following steps to install a mini GBIC transceiver (SFP module).

1 Insert the transceiver into the slot with the exposed section of PCB board facing down.





- **2** Press the transceiver firmly until it clicks into place.
- **3** The switch automatically detects the installed transceiver. Check the LEDs to verify that it is functioning properly.

Figure 11 Installed Transceiver




3.1.3.2 Transceiver Removal


Use the following steps to remove a mini GBIC transceiver (SFP module).

1 Open the transceiver's latch (latch styles vary).





2 Pull the transceiver out of the slot.



3.2 Rear Panel

The following figure shows the rear panel of the switch. The power receptacle is on the read panel.

Figure 14 Rear Panel



3.2.1 Power Connector

Make sure you are using the correct power source as shown on the panel.

To connect the power to the switch, insert the female end of power cord to the power receptacle on the rear panel. Connect the other end of the supplied power cord to the power source. Make sure that no objects obstruct the airflow of the fans.

3.3 Front Panel LEDs

The LEDs are located on the front panel. The following table describes the LEDs on the front panel.

LED	COLOR	STATUS	DESCRIPTION
PWR	Green	On	The system is turned on.
		Off	The system is off.
SYS	Green	Blinking	The system is rebooting and performing self-diagnostic tests.
		On	The system is on and functioning properly.
		Off	The power is off or the system is not ready/malfunctioning.
ALM	Red	On	There is a hardware failure.
		Off	The system is functioning normally.
LNK/ACT (Ethernet	Green	Blinking	The system is transmitting/receiving to/from a 10 Mbps Ethernet network.
ports)		On	The link to a 10 Mbps Ethernet network is up.
	Amber	Blinking	The system is transmitting/receiving to/from a 100 Mbps Ethernet network.
		On	The link to a 100 Mbps Ethernet network is up.
		Off	The link to an Ethernet network is down.
FDX/COL (Ethernet ports)	Amber	Blinking	The Ethernet port is negotiating in half-duplex mode and collisions are occurring; the more collisions that occur the faster the LED blinks.
		On	The Ethernet port is negotiating in full-duplex mode.
		Off	The Ethernet port is negotiating in half-duplex mode and no collisions are occurring.
100/1000	Green	On	The link to a 1000 Mbps Ethernet network is up.
	Amber	On	The link to a 100 Mbps Ethernet network is up.
		Off	The link to an Ethernet network is down.
ACT	Green	Blinking	The port is receiving or transmitting data.
		On	The port has a connection to an Ethernet network but not receiving or transmitting data.
		Off	The link to an Ethernet network is down.
LNK (mini	Green	On	The port has a successful connection.
GBIC Slots)		Off	No Ethernet device is connected to this port.
ACT (mini	Green	Blinking	The port is sending or receiving data.
GBIC Slots)		Off	The port is not sending or receiving data.

Table 2Front Panel LEDs

CHAPTER 4 The Web Configurator

This section introduces the configuration and functions of the web configurator.

4.1 Introduction

The web configurator is an HTML-based management interface that allows easy switch setup and management via Internet browser. Use Internet Explorer 6.0 and later or Netscape Navigator 7.0 and later versions. The recommended screen resolution is 1024 by 768 pixels.

In order to use the web configurator you need to allow:

- Web browser pop-up windows from your device. Web pop-up blocking is enabled by default in Windows XP SP (Service Pack) 2.
- JavaScript (enabled by default).
- Java permissions (enabled by default).

4.2 System Login

- **1** Start your web browser.
- **2** Type "http://" and the IP address of the switch (for example, the default is 192.168.1.1) in the Location or Address field. Press [ENTER].
- **3** The login screen appears. The default username is **admin** and associated default password is **1234**. The date and time display as shown if you have not configured a time server nor manually entered a time and date in the **General Setup** screen.

Figure 15 Web Configurator: Login

Enter Netv	vork Passwor	d	<u>?</u> ×
?	Please type yo	ur user name and password.	
S)	Site:	192.168.1.1	
	Realm	ES-2024A at Sat Jan 01 02:05:29 2000	
	<u>U</u> ser Name		
	<u>P</u> assword		
	\Box Save this p	bassword in your password list	
		OK Cano	;el

4 Click OK to view the first web configurator screen.

4.3 The Status Screen

The Status screen is the first screen that displays when you access the web configurator.

The following figure shows the navigating components of a web configurator screen.

Figure 16 Web Configurator Home Screen (Status)

ZyXEL						M	Status I	i Logo	it Di Hi	aln
MENU						imi.	Juana p	1 20900		=18
Basic Setting		Status								
ā		Up Time: 0:46:05								
Advanced Application	Port	Link	State	LACP	TxPkts	RxPkts	Errors	Tx KB/s	Rx KB/s	Up Time
F IP Application	<u>1</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
Management	2	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
ES	3	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
202	4	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
\$	5	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>6</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	Ī	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	8	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	9	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	10	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>11</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>12</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>13</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>14</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>15</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>16</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>17</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>18</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>19</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>20</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>21</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	22	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>23</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>24</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>25</u>	1000M/F Copper	FORWARDING	Disabled	674	2039	0	0.0	0.584	0:45:01
	<u>26</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	Poll Inte Port	erval(s) 40 ALL 💌	Set Interval Clear Counte	Stop						
							© Copyright	1005.2005	by ZyXEL	Pommunicatid

In the navigation panel, click a main link to reveal a list of submenu links.

BASIC SETTING	ADVANCED APPLICATION	IP APPLICATION	MANAGEMENT
MENU Basic Setting Advanced Application IP Application Management System Info General Setup Switch Setup IP Setup Port Setup	MENU Basic Setting Advanced Application IP Application Management VLAN Static MAC Forwarding Filtering Spanning Tree Protocol Bandwidth Control Broadcast Storm Control Mirroring Link Aggregation Port Authentication Port Security Queuing Method	MENU Basic Setting Advanced Application IP Application Management Static Routing DiffServ	MENU Basic Setting Advanced Application IP Application Management Maintenance Access Control Diagnostic Cluster Management MAC Table ARP Table

 Table 3
 Navigation Panel Sub-links Overview

The following table lists the various web configurator screens within the sub-links.

Table 4 Web Configurator Screen Sub-links Details
--

BASIC SETTING	ADVANCED APPLICATION	IP APPLICATION	MANAGEMENT
System Info General Setup Switch Setup IP Setup Port Setup	APPLICATION VLAN VLAN Status VLAN Port Setting Static VLAN Static MAC Forwarding Filtering Spanning Tree Protocol Status Spanning Tree Protocol Configuration Bandwidth Control Broadcast Storm	Static Routing DiffServ DSCP Setting	Maintenance Firmware Upgrade Restore Configuration Backup Configuration Load Factory Default Reboot System Diagnostic Access Control SNMP Logins Service Access
	Control Mirroring		Control Remote Management

BASIC SETTING	ADVANCED APPLICATION	IP APPLICATION	MANAGEMENT
	Link Aggregation Link Aggregation Protocol Status Link Aggregation Port Authentication RADIUS 802.1x Port Security Queuing Method		Cluster Management Status Cluster Management Configuration MAC Table ARP Table

Table 4	Web Configurator Screen Sub-lin	ks Details (continued)

The following table describes the links in the navigation panel.

LINK	DESCRIPTION
Basic Settings	
System Info	This link takes you to a screen that displays general system and hardware monitoring information.
General Setup	This link takes you to a screen where you can configure general identification information about the switch.
Switch Setup	This link takes you to a screen where you can set up global switch parameters such as VLAN type, MAC address learning, IGMP snooping, GARP and priority queues.
IP Setup	This link takes you to a screen where you can configure the management IP address, subnet mask (necessary for switch management) and DNS (domain name server).
Port Setup	This link takes you to screens where you can configure settings for individual switch ports.
Advanced Application	
VLAN	This link takes you to screens where you can configure port-based or 802.1Q VLAN (depending on what you configured in the Switch Setup menu).
Static MAC Forwarding	This link takes you to screens where you can configure static MAC addresses for a port. These static MAC addresses do not age out.
Filtering	This link takes you to a screen to set up filtering rules.
Spanning Tree Protocol	This link takes you to screens where you can configure the STP/RSTP to prevent network loops.
Bandwidth Control	This link takes you to screens where you can cap the maximum bandwidth allowed from specified source(s) to specified destination(s).
Broadcast Storm Control	This link takes you to a screen to set up broadcast filters.
Mirroring	This link takes you to screens where you can copy traffic from one port or ports to another port in order that you can examine the traffic from the first port without interference
Link Aggregation	This link takes you to a screen where you can logically aggregate physical links to form one logical, higher-bandwidth link.

LINK	DESCRIPTION
Port Authentication	This link takes you to a screen where you can configure RADIUS (Remote Authentication Dial-In User Service), a protocol for user authentication that allows you to use an external server to validate an unlimited number of users.
Port Security	This link takes you to a screen where you can activate MAC address learning and set the maximum number of MAC addresses to learn on a port.
Queuing Method	This link takes you to a screen where you can configure SPQ or WFQ with associated queue weights for each port.
IP Application	
Static Route	This link takes you to screens where you can configure static routes. A static route defines how the switch should forward traffic by configuring the TCP/IP parameters manually.
DiffServ	This link takes you to screens where you can enable DiffServ and set DSCP-to-IEEE802.1p mappings.
Advanced Management	
Maintenance	This link takes you to screens where you can perform firmware and configuration file maintenance as well as reboot the system.
Access Control	This link takes you to screens where you can change the system login password and configure SNMP and remote management.
Diagnostic	This link takes you to screens where you can view system logs and test port(s).
Cluster Management	This link takes you to a screen where you can configure clustering management and view its status.
MAC Table	This link takes you to a screen where you can view the MAC addresses (and types) of devices attached to what ports and VLAN IDs.
ARP Table	This link takes you to a screen where you can view the MAC addresses – IP address resolution table.
Routing Table	This link takes you to a screen where you can view the routing table in the switch.

 Table 5
 Navigation Panel Links (continued)

4.3.1 Change Your Password

After you log in for the first time, it is recommended you change the default administrator password. Click **Management**, **Access Control** and then **Logins** to display the next screen.

() Login	5		Access
dministrator			
Ht Password			
lew Password)
setype to confir	m 🗌		
	your new password rgotten your pa sswor		. The system will lock yo
you have fo Edit Logins	rgotten your passwor	d.	
you have fo			The system will lock yo
you have fo Edit Logins	rgotten your passwor	d.	
you have fo Edit Logins	rgotten your passwor	d.	
you have fo Edit Logins Login 1	rgotten your passwor	d.	

Figure 17 Change Administrator Login Password

4.4 Switch Lockout

You could lock yourself (and all others) out from the switch by:

- **1** Deleting the management VLAN (default is VLAN 1).
- **2** Deleting all port-based VLANs with the CPU port as a member. The "CPU port" is the management port of the switch.
- **3** Filtering all traffic to the CPU port.
- **4** Disabling all ports.
- **5** Assigning minimum bandwidth to the CPU port. If you limit bandwidth to the CPU port, you may find that the switch performs sluggishly or not at all.

Note: Be careful not to lock yourself and others out of the switch.

4.5 Resetting the Switch

If you lock yourself (and others) from the switch or forget the switch password, you will need to reload the factory-default configuration file or reset the switch back to the factory defaults.

4.5.1 Reload the Factory-default Configuration File

Uploading the factory-default configuration file replaces the current configuration file with the factory-default configuration file. This means that you will lose all previous configurations and the speed of the console port will be reset to the default of 9600bps with 8 data bit, no parity, one stop bit and flow control set to none. The password will also be reset to "1234" and the IP address to 192.168.1.1.

To upload the factory-default configuration file, do the following:

- 1 Connect to the console port using a computer with terminal emulation software. See Section 3.1.1 on page 33 for details.
- **2** Disconnect and reconnect the switch's power to begin a session. When you reconnect the switch's power, you will see the initial screen.
- **3** When you see the message "Press any key to enter Debug Mode within 3 seconds ..." press any key to enter debug mode.
- 4 Type atlc after the "Enter Debug Mode" message.
- **5** Wait for the "Starting XMODEM upload" message before activating XMODEM upload on your terminal.
- 6 After the factory-default configuration file upload, type atgo to restart the switch.

Figure 18 Resetting the Switch: Via the Console Port

```
Bootbase Version: V1.0 | 04/25/2003 10:01:06
RAM: Size = 32768 Kbytes
FLASH: Intel 32M
ZyNOS Version: V3.50(DU.0) | 07/11/2003 18:00:29
Press any key to enter debug mode within 3 seconds.
Enter Debug Mode
ES-2024A> atlc
Starting XMODEM upload (CRC mode)....
ccccccccccccccc
Total 262144 bytes received.
Erasing..
. . . . . . . . .
                       OK
ES-2024A> atgo
```

The switch is now reinitialized with the factory-default configuration file including the default password of "1234".

4.6 Logging Out of the Web Configurator

Click **Logout** in a screen to exit the web configurator. You have to log in with your password again after you log out. This is recommended after you finish a management session both for security reasons and so as you don't lock out other switch administrators.

Figure 19 Web Configurator: Logout Screen



4.7 Help

The web configurator's online help has descriptions of individual screens and some supplementary information.

Click the **Help** link from a web configurator screen to view an online help description of that screen.

CHAPTER 5 Initial Setup Example

This chapter shows how to set up the switch for an example network.

5.1 Overview

The following lists the configuration steps for the initial setup:


- Create a VLAN
- Set port VLAN ID
- Configure the switch IP management address

5.1.1 Creating a VLAN

VLANs confine broadcast frames to the VLAN group in which the port(s) belongs. You can do this with port-based VLAN or tagged static VLAN with fixed port members.

In this example, you want to configure port 10 as a member of VLAN 2.





							Po	rt Nun	nber							
Index	VID	2	4	6	8	10	12	14	16	18	20	22	24	26	Elapsed Time	Status
		1	3	5	7	9	11	13	15	17	19	21	23	25		
1	1	U	U	U	U	U	U	U	U	U	U	U	U	U	1:18:40	Static
		U	U	U	U	U	U	U	U	U	U	U	U	U	1.10.40	otatic

1 Click Advanced Application and VLAN in the navigation panel and click the Static VLAN link.

- 2 In the Static VLAN screen, select ACTIVE, enter a descriptive name in the Name field and enter 2 in the VLAN Group ID field for the VLAN2 network.
- Note: The VLAN Group ID field in this screen and the VID field in the IP Setup screen refer to the same VLAN ID.
 - **3** Since the VLAN2 network is connected to port 10 on the switch, select **Fixed** to configure port 10 to be a permanent member of the VLAN only.
 - **4** To ensure that VLAN-unaware devices (such as computers and hubs) can receive frames

	ACTIVE		2	
	Name		Example	
	VLAN Group ID		2	_
	VERN Group ID		le .	
Port		Control		Tagging
1	Normal	C Fixed	C Forbidden	Tx Tagging
2	Normal	C Fixed	C Forbidden	🗹 Tx Tagging
3	Normal	C Fixed	C Forbidden	🗹 Tx Tagging
4	Normal	O Fixed	O Forbidden	🗹 Tx Tagging
5	Normal	C Fixed	C Forbidden	🗹 Tx Tagging
6	Normal	C Fixed	C Forbidden	🗹 Tx Tagging
7	Normal	C Fixed	C Forbidden	🗹 Tx Tagging
8	Normal	C Fixed	C Forbidden	🗹 Tx Tagging
9	Normal	C Fixed	C Forbidden	Tx Tagging
10	C Normal	Fixed	C Forbidden	✓ Tx Tagging
11	Normal	C Fixed	C Forbidden	✓ Tx Tagging
~12~	Nor-al	- Crived	Forbiden	
21	Normal Normal	C Fixed	C Forbidden	Tx Tagging
22	Normal	C Fixed	C Forbidden	Tx Tagging
23	Normal	C Fixed	C Forbidden	Tx Tagging
24	Normal	C Fixed	C Forbidden	Tx Tagging
25	Normal	O Fixed	C Forbidden	Tx Tagging
26	 Normal 	C Fixed	C Forbidden	Tx Tagging

properly, clear the **TX Tagging** check box to set the switch to remove VLAN tags before sending.


5 Click **Add** to save the settings.

5.1.2 Setting Port VID

Use PVID to add a tag to incoming untagged frames received on that port so that the frames are forwarded to the VLAN group that the tag defines.

In the example network, configure 2 as the port VID on port 10 so that any untagged frames received on that port get sent to VLAN 2.





- 1 Click Advanced Applications and VLAN in the navigation panel. Then click the VLAN Port Setting link.
- 2 Enter 2 in the PVID field for port 10 and click Apply to save the settings.

	GVRP ort isolation gress Check			
	grood on one			
Port	PVID	GVRP	Acceptable Frame Type	VLAN Trunking
1	1		All	
2	1		All	
3	1		All	
4	1		All 💌	
5	1		All 💌	
6	1		All	
7	1		All	
8	1		All	
9	1			
10	2		All	
11	1	<u> </u>		
12			All	
\sim	\sim	$\sim \sim$		$\sim\sim\sim\sim$
21	1		All 💌	
22	1		All 💌	
23	1		All 💌	
24	1		All 💌	
25	1		All	
26	1		All	
			Apply Cancel	

5.1.3 Configuring Switch Management IP Address

The default management IP address of the switch is 192.168.1.1. You can configure another IP address in a different subnet for management purposes. The following figure shows an example.




Figure 22 Initial Setup Example: Management IP Address

- 1 Connect your computer to any Ethernet port on the switch. Make sure your computer is in the same subnet as the switch.
- **2** Open your web browser and enter 192.168.1.1 (the default IP address) in the address bar to access the web configurator. See Section 4.2 on page 39 for more information.
- **3** Click **Basic Setting** and **IP Setup** in the navigation panel.
- 4 Configure the related fields in the **IP Setup** screen.

For the VLAN2 network, enter 192.168.2.1 as the IP address and 255.255.255.0 as the subnet mask.

- 5 In the VID field, enter the ID of the VLAN group to which you want this management IP address to belong. This is the same as the VLAN ID you configure in the Static VLAN screen.
- 6 Click Add.

	onvor	0.0.0.0			
Domain Name S	eivei	10.0.0.0			
Default Management IP	O DHCP	Client			
ddress	Static	P Address			
		IP Addr	ess	192.168.1.1	
		IP Subr	et Mask	255.255.255	i.0
		Default	Gateway	0.0.0	
	VID	1			
Management IP Addr	esses	102 102 2 1			
IP Address		192.168.2.1			
IP Address IP Subnet Mas		255.255.255.0			
IP Address IP Subnet Mas VID	sk	255.255.255.0 2			
IP Address IP Subnet Mas	sk	255.255.255.0			
IP Address IP Subnet Mas VID	sk	255.255.255.0 2 192.168.2.1			
IP Address IP Subnet Mas VID	sk	255.255.255.0 2 192.168.2.1	ncel		
IP Address IP Subnet Mas VID	sk ay	255.255.255.0 2 192.168.2.1	ND	Default Gateway	Delete

CHAPTER 6 System Status and Port Statistics

This chapter describes the system status (web configurator home page) and port details screens.

6.1 Overview

The home screen of the web configurator displays a port statistical summary table with links to each port showing statistical details.

6.2 Port Status Summary

To view the port statistics, click **Status** in all web configurator screens to display the **Status** screen as shown next.

Port	Link	State	LACP	TxPkts	RxPkts	Errors	Tx KB/s	Rx KB/s	Up Time
1	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
2	100M/F	FORWARDING	Disabled	4739	1882	0	33.357	2.556	2:16:26
<u>3</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
<u>4</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
5	Down	STOP	Disabled			1	0.0	0.0	0:00:00
\sim		$\sim\sim\sim\sim$	∼~~e~~	$\sim\sim\sim\sim$	$\sim\sim\sim\sim$	$\sim\sim$	\sim	\sim	\sim
<u>21</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
<u>22</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
<u>23</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
<u>24</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
<u>25</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
26	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00



The following table describes the labels in this screen.

LABEL	DESCRIPTION
System up Time	This field shows how long the system has been running since the last time it was started.
Port	This identifies the Ethernet port. Click a port number to display the Port Details screen (refer to Figure 24 on page 53).
Link	This field displays the speed (either 10M for 10Mbps, 100M for 100Mbps or another value depending on the uplink module being used) and the duplex (F for full duplex or H for half duplex).
State	This field displays the STP (Spanning Tree Protocol) state of the port. See the chapter on STP for details on STP states.
LACP	This fields displays whether LACP (Link Aggregation Control Protocol) has been enabled on the port.
TxPkts	This field shows the number of transmitted frames on this port.
RxPkts	This field shows the number of received frames on this port.
Errors	This field shows the number of received errors on this port.
Tx KB/s	This field shows the number of kilobytes per second transmitted on this port.
Rx KB/s	This field shows the number of kilobytes per second received on this port.
Up Time	This field shows the total amount of time in hours, minutes and seconds the port has been up.
Poll Interval(s)	The text box displays how often (in seconds) this screen refreshes. You may change the refresh interval by typing a new number in the text box and then clicking Set Interval.
Stop	Click Stop to halt system statistic polling.
Clear Counter	Select a port from the Port drop-down list box and then click Clear Counter to erase the recorded statistical information for that port.

Table 6 Status

6.2.1 Status: Port Details

Click a number in the **Port** column in the **Status** screen to display individual port statistics. Use this screen to check status and detailed performance data about an individual port on the switch.

🛛 🎱 Port D	etails		<u>Statu</u>
Port Info	Port NO.	2	
	Link	100M/F	
	Status	FORWARDING	
	LACP	Disabled	
	Tx Pkts	4959	
	Rx Pkts	2001	
	Errors	0	
	Tx KBs/s	0.64	
	Rx KBs/s	0.0	
	Up Time	2:19:36	
TX Packet	TX Packets	4959	
	Multicast	3228	
	Broadcast	0	
	Pause	0	
RX Packet	RX Packets	2001	
	Multicast	23	
	Broadcast	406	
	Pause	0	
TX Collision	Single	0	
	Multiple	0	
	Excessive	0	
	Late	0	
Error Packet	RX CRC	0	
	Runt	0	
Distribution	64	1182	
	65 to 127	444	
	128 to 255	108	
	256 to 511	193	
	512 to 1023	72	
	1024 to 1518	2	
	Giant	0	
Poll Interval(s) 40	Set Interval Stop	

Figure 24 Status: Port Details

The following table describes the labels in this screen.

Table 7 Status: Port Details

LABEL	DESCRIPTION
Port Info	
Link	This field shows whether the Ethernet connection is down, and the speed/duplex mode.
Status	This field shows the training state of the ports. The states are FORWARDING (forwarding), which means the link is functioning normally or STOP (the port is stopped to break a loop or duplicate path).
LACP	This field shows if LACP is enabled on this port or not.
TxPkts	This field shows the number of transmitted frames on this port
RxPkts	This field shows the number of received frames on this port
Errors	This field shows the number of received errors on this port.
Tx KB/s	This field shows the number kilobytes per second transmitted on this port.
Rx KB/s	This field shows the number of kilobytes per second received on this port.
Up Time	This field shows the total amount of time the connection has been up.
Tx Packet	
The following	g fields display detailed information about packets transmitted.

LABEL	DESCRIPTION
TX Packet	This field shows the number of good packets (unicast, multicast and broadcast) transmitted.
Multicast	This field shows the number of good multicast packets transmitted.
Broadcast	This field shows the number of good broadcast packets transmitted.
Pause	This field shows the number of 802.3x Pause packets transmitted.
Tagged	This field shows the number of packets with VLAN tags transmitted.
Rx Packet The following fi	elds display detailed information about packets received.
RX Packet	This field shows the number of good packets (unicast, multicast and broadcast) received.
Multicast	This field shows the number of good multicast packets received.
Broadcast	This field shows the number of good broadcast packets received.
Pause	This field shows the number of 802.3x Pause packets received.
Error Packet	
RX CRC	This field shows the number of packets received with CRC (Cyclic Redundant Check) error(s).
Runt	This field shows the number of packets received that were too short (shorter than 64 octets), including the ones with CRC errors.
Distribution	
64	This field shows the number of packets (including bad packets) received that were 64 octets in length.
65-127	This field shows the number of packets (including bad packets) received that were between 65 and 127 octets in length.
128-255	This field shows the number of packets (including bad packets) received that were between 128 and 255 octets in length.
256-511	This field shows the number of packets (including bad packets) received that were between 256 and 511 octets in length.
512-1023	This field shows the number of packets (including bad packets) received that were between 512 and 1023 octets in length.
1024-1518	This field shows the number of packets (including bad packets) received that were between 1024 and 1518 octets in length.
Giant	This field shows the number of packets dropped because they were bigger than the maximum frame size.
Poll Interval(s)	The text box displays how often (in seconds) this screen refreshes. You may change the refresh interval by typing a new number in the text box and then clicking Set Interval .
Stop	Click Stop to stop port statistic polling.

 Table 7
 Status: Port Details (continued)

CHAPTER 7 Basic Setting

This chapter describes how to configure the **System Info, General Setup**, **Switch Setup**, **IP Setup** and **Port Setup** screens.

7.1 Overview

The **System Info** screen displays general switch information (such as firmware version number) and hardware polling information (such as fan speeds). The **General Setup** screen allows you to configure general switch identification information. The **General Setup** screen also allows you to set the system time manually or get the current time and date from an external server when you turn on your switch. The real time is then displayed in the switch logs. The **Switch Setup** screen allows you to set up and configure global switch features. The **IP Setup** screen allows you to configure a switch IP address, subnet mask(s) and DNS (domain name server) for management purposes.

7.2 System Information

In the navigation panel, click **Basic Setting** and **System Info** to display the screen as shown. You can check the firmware version number and monitor the switch temperature, fan speeds and voltage in this screen.

Figure 25 System Info	Figure	25	System	Info
-----------------------	--------	----	--------	------

System Info	
System Name	ES-2024A
ZyNOS F/W Version	V3.60(TX.0)b1 04/22/2005
Ethernet Address	00:13:49:1a:d4:fa

The following table describes the labels in this screen.

Table 8 System Info

LABEL	DESCRIPTION
System Name	This field displays the descriptive name of the switch for identification purposes.
ZyNOS F/W Version	This field displays the version number of the switch 's current firmware including the date created.
Ethernet Address	This field refers to the Ethernet MAC (Media Access Control) address of the switch.

LABEL	DESCRIPTION
Poll Interval(s)	The text box displays how often (in seconds) this screen refreshes. You may change the refresh interval by typing a new number in the text box and then clicking Set Interval .
Stop	Click Stop to halt statistic polling.

Table 8	System Info	(continued)
---------	-------------	-------------

7.3 General Setup

Click **Basic Setting** and **General Setup** in the navigation panel to display the screen as shown.

Figure 26	General Setup
-----------	---------------

) General Setup	
System Name	ES-2024A
Location	
Contact Person's Name	
Login Precedence	Local Only
Use Time Server when Bootup	None
Time Server IP Address	0.0.0
Current Time	00 : 38 : 10
New Time (hh:mm:ss)	00 : 38 : 10
Current Date	2000 _ 01 _ 01
New Date (уууу-mm-dd)	2000 _ 01 _ 01
Time Zone	
ill take 60 seconds if time server is un	rreachable.

The following table describes the labels in this screen.

Table 9 General Setup	Table 9	General	Setup
-------------------------------	---------	---------	-------

LABEL	DESCRIPTION
System Name	Choose a descriptive name for identification purposes. This name consists of up to 32 printable characters; spaces are not allowed.
Location	Enter the geographic location (up to 30 characters) of your switch.
Contact Person's Name	Enter the name (up to 30 characters) of the person in charge of this switch.

Table 9	General Setup	(continued)
---------	---------------	-------------

LABEL	DESCRIPTION
Login Precedence	Use this drop-down list box to select which database the switch should use (first) to authenticate an administrator (user for switch management).
	Configure the local user accounts in the Access Control Logins screen. The RADIUS is an external server. Before you specify the priority, make sure you have set up the corresponding database correctly first.
	Select Local Only to have the switch just check the administrator accounts configured in the Access Control Logins screen.
	Select Local then RADIUS to have the switch check the administrator accounts configured in the Access Control Logins screen. If the user name is not found, the switch then checks the user database on the specified RADIUS server. You need to configure Port Authentication Radius first.
	Select RADIUS Only to have the switch just check the user database on the specified RADIUS server for a login username and password.
Use Time Server when Bootup	Enter the time service protocol that a timeserver sends when you turn on the switch. Not all time servers support all protocols, so you may have to use trial and error to find a protocol that works. The main differences between them are the time format.
	When you select the Daytime (RFC 867) format, the switch displays the day, month, year and time with no time zone adjustment. When you use this format it is recommended that you use a Daytime timeserver within your geographical time zone.
	Time (RFC-868) format displays a 4-byte integer giving the total number of seconds since 1970/1/1 at 0:0:0.
	NTP (RFC-1305) is similar to Time (RFC-868).
	None is the default value. Enter the time manually. Each time you turn on the switch, the time and date will be reset to 2000-1-1 0:0.
Time Server IP Address	Enter the IP address (or URL if you configure a domain name server in the IP Setup screen) of your timeserver. The switch searches for the timeserver for up to 60 seconds. If you select a timeserver that is unreachable, then this screen will appear locked for 60 seconds. Please wait.
Current Time	This field displays the time you open this menu (or refresh the menu).
New Time (hh:min:ss)	Enter the new time in hour, minute and second format. The new time then appears in the Current Time field after you click Apply .
Current Date	This field displays the date you open this menu.
New Date (yyyy- mm-dd)	Enter the new date in year, month and day format. The new date then appears in the Current Date field after you click Apply .
Time Zone	Select the time difference between UTC (Universal Time Coordinated, formerly known as GMT, Greenwich Mean Time) and your time zone from the drop-down list box.
Apply	Click Apply to save the settings.
Cancel	Click Cancel to reset the fields to your previous configuration.

7.4 Introduction to VLANs

A VLAN (Virtual Local Area Network) allows a physical network to be partitioned into multiple logical networks. Devices on a logical network belong to one group. A device can belong to more than one group. With VLAN, a device cannot directly talk to or hear from devices that are not in the same group(s); the traffic must first go through a router.

In MTU (Multi-Tenant Unit) applications, VLAN is vital in providing isolation and security among the subscribers. When properly configured, VLAN prevents one subscriber from accessing the network resources of another on the same LAN, thus a user will not see the printers and hard disks of another user in the same building.

VLAN also increases network performance by limiting broadcasts to a smaller and more manageable logical broadcast domain. In traditional switched environments, all broadcast packets go to each and every individual port. With VLAN, all broadcasts are confined to a specific broadcast domain.

Note: VLAN is unidirectional; it only governs outgoing traffic.

See Chapter 8 on page 65 for information on port-based and 802.1Q tagged VLANs.

7.5 IGMP Snooping

A switch can passively snoop on IGMP Query, Report and Leave (IGMP version 2) packets transferred between IP multicast routers/switches and IP multicast hosts to learn the IP multicast group membership. It checks IGMP packets passing through it, picks out the group registration information, and configures multicasting accordingly. IGMP snooping allows the switch to learn multicast groups without you having to manually configure them.

The switch forwards multicast traffic destined for multicast groups (that it has learned from IGMP snooping or that you have manually configured) to ports that are members of that group. The switch discards multicast traffic destined for multicast groups that it does not know. IGMP snooping generates no additional network traffic, allowing you to significantly reduce multicast traffic passing through your switch.

7.6 Switch Setup Screen

Click **Basic Setting** and then **Switch Setup** in the navigation panel to display the screen as shown. The VLAN setup screens change depending on whether you choose **802.1Q** or **Port Based** in the **VLAN Type** field in this screen. Refer to the chapter on VLAN.

Switch Setup			
VLAN Type	● 802.1Q ○ Port Based		
IGMP Snooping	Active		
MAC Address Learning	Aging Time	300	seconds
	Join Timer	200	milliseconds
	Leave Timer	600	milliseconds
	Leave All Timer	10000	milliseconds
Priority Queue Assignment	level7	3 🗸	
	level6	3 🗸	
	level5	2 🗸	
	level4	2 💌	
	level3	1 💌	
	level2	0 🗸	
	level1	0 🗸	
	level0	1 🗸	
	Apply Cancel	1	

Figure 27 Switch Setup

The following table describes the labels in this screen.

LABEL	DESCRIPTION	
VLAN Type	Choose 802.1Q or Port Based . The VLAN Setup screen changes depending on whether you choose 802.1Q VLAN type or Port Based VLAN type in this screen. See Chapter 8 on page 65 for more information.	
IGMP Snooping	Select the Active checkbox to enable IGMP snooping have group multicast traffic only forwarded to ports that are members significantly reducing multicast traffic passing through your switch. See Section 7.5 on page 58 for more information on IGMP snooping.	
MAC Address Learning	MAC address learning reduces outgoing traffic broadcasts. For MAC address learning to occur on a port, the port must be active.	
Aging Time	Enter a time from 10 to 3000 seconds. This is how long all dynamically learned MAC addresses remain in the MAC address table before they age out (and must be relearned).	
GARP Timer: Switches join VLANs by making a declaration. A declaration is made by issuing a Jo message using GARP. Declarations are withdrawn by issuing a Leave message. A Leave All mess terminates all registrations. GARP timers set declaration timeout values. See the chapter on VLAN setup for more background information.		
Join Timer	Join Timer sets the duration of the Join Period timer for GVRP in milliseconds. Each port has a Join Period timer. The allowed Join Time range is between 100 and 65535 milliseconds. See the chapter on VLAN setup for more background information.	
Leave Timer	ave Timer Leave Time sets the duration of the Leave Period timer for GVRP in milliseconds Each port has a single Leave Period timer. Leave Time must be two times larger than Join Timer.	
Leave All Timer	Leave All Timer sets the duration of the Leave All Period timer for GVRP in milliseconds. Each port has a single Leave All Period timer. Leave All Timer must be larger than Leave Timer.	

LABEL	DESCRIPTION	
Priority Queue Assignment IEEE 802.1p defines up to eight separate traffic types by inserting a tag into a MAC-layer frame that contains bits to define class of service. Frames without an explicit priority tag are given the default priority of the ingress port. Use the next two fields to configure the priority level-to-physical queue mapping.		
The switch has four physical queues that you can map to the 8 priority levels. On the switch, traffic assigned to higher index queues gets through faster while traffic in lower index queues is dropped if the network is congested.		
	e following descriptions are based on the traffic types defined in the IEEE 802.1d ncorporates the 802.1p).	
Level 7	Typically used for network control traffic such as router configuration messages.	
Level 6	Typically used for voice traffic that is especially sensitive to jitter (jitter is the variations in delay).	
Level 5	Typically used for video that consumes high bandwidth and is sensitive to jitter.	
Level 4	Typically used for controlled load, latency-sensitive traffic such as SNA (Systems Network Architecture) transactions.	
Level 3	Typically used for "excellent effort" or better than best effort and would include important business traffic that can tolerate some delay.	
Level 2	This is for "spare bandwidth".	
Level 1	This is typically used for non-critical "background" traffic such as bulk transfers that are allowed but that should not affect other applications and users.	
Level 0	Typically used for best-effort traffic.	
Apply	Click Apply to save the settings.	
Cancel	Click Cancel to reset the fields to your previous configuration.	

Table 10	Switch Setup	(continued)
----------	--------------	-------------

7.7 IP Setup

Use the **IP Setup** screen to configure the default gateway device, the default domain name server and add switch IP address.

7.7.1 Management IP Addresses

The switch needs an IP address for it to be managed over the network. The factory default IP address is 192.168.1.1. The subnet mask specifies the network number portion of an IP address. The factory default subnet mask is 255.255.255.0.

You can configure up to 128 IP addresses which are used to access and manage the switch from the ports belonging to the pre-defined VLAN(s).

Note: You must configure a VLAN first.

Figure 28 IP Setup

🔵 IP Setup					
Domain Name Server 0.0.0.0					
Default Management IP	O DHCP Client				
Address	Static IP Addres	s			
		IP Addres	s	192.168.1.24	
		IP Subne	tMask	255.255.255.	.0
		Default G	ateway	0.0.0.0	
VID 1					
	Ap	ply Ca	ncel		
Management IP Addr	esses				
IP Address	0.0.0.0				
IP Subnet Mask 0.0.0.0					
VID					
Default Gateway 0.0.0.0					
· ·					
	Δ	dd Cano	-el		
Index IP Addre	ss IP Subnet	Mask	VID	Default Gateway	Delete
	De	elete Ca	incel		

The following table describes the labels in this screen.

Table 11 IP Setup

LABEL	DESCRIPTION		
Domain Name Server	DNS (Domain Name System) is for mapping a domain name to its corresponding IP address and vice versa. Enter a domain name server IP address in order to be able to use a domain name instead of an IP address.		
Default Manag	Default Management IP Address		
Configure the	fields to set the default management IP address.		
DHCP Client	Select this option if you have a DHCP server that can assign the switch an IP address and subnet mask, a default gateway IP address and a domain name server IP address.		
Static IP Address	Select this option if you don't have a DHCP server or if you wish to assign static IP address information to the switch. You need to fill in the following fields when you select this option.		
IP Address	Enter the IP address of your switch in dotted decimal notation for example 192.168.1.1.		
IP Subnet Mask	Enter the IP subnet mask of your switch in dotted decimal notation for example 255.255.255.0.		
Default Gateway	Enter the IP address of the default outgoing gateway in dotted decimal notation, for example 192.168.1.254		

LABEL	DESCRIPTION
VID	Enter the VLAN identification number associated with the switch IP address. This is the VLAN ID of the CPU and is used for management only. The default is "1". All ports, by default, are fixed members of this "management VLAN" in order to manage the device from any port. If a port is not a member of this VLAN, then users on that port cannot access the device. To access the switch make sure the port that you are connected to is a member of Management VLAN.
Apply	Click Apply to save the settings.
Cancel	Click Cancel to reset the fields to your previous configuration.
Management I	P Addresses
Configure the f	fields to set additional management IP address.
IP Address	Enter the IP address for managing the switch by the members of the VLAN specified in the VID field below.
IP Subnet Mask	Enter the IP subnet mask in dotted decimal notation. For example, 255.255.255.0.
VID	Enter the VLAN identification number.
Add	Click Add to save the new rule to the switch. It then displays in the summary table at the bottom of the screen.
Cancel	Click Cancel to reset the fields to your previous configuration.
Index	This field displays the index number of an entry.
IP Address	This field displays the management IP address of the switch.
Subnet Mask	This field displays the subnet mask of the switch.
VID	This field displays the VLAN identification number of the network.
Delete	Click Delete to remove the selected entry from the summary table.
Cancel	Click Cancel to clear the Delete check boxes.

Table 11	IP Setup	(continued)
----------	----------	-------------

7.8 Port Setup

Click **Basic Setting** and then **Port Setup** in the navigation panel to enter the port configuration screen.

1 Import01 10/100M 2 Import02 10/100M 3 Import03 10/100M 4 Import04 10/100M 20 Import04 10/100M 21 Import21 10/100M 22 Import21 10/100M 23 Import23 10/100M	Auto Auto Auto Auto Auto Auto Auto Auto		
3	Auto Auto Auto		
4	Auto		
20 port21 10/100M 22 port22 10/100M	Auto		
20 pon2 nonx 21 port21 10/100M 22 port22 10/100M	Auto		\sim
21 Image: port21 10/100M 22 Image: port22 10/100M	-		
22 🔽 port22 10/100M	-		0 🗸
	Auto	-	
22 🔽 nort23 10/100M			0 🖵
23 10 10/1000	Auto	-	0 🖵
24 🔽 port24 10/100M	Auto		0 🗸
25 🔽 port25 10/100/1000M	Auto	-	0 💌
26 🔽 port26 10/100/1000M	Auto		0 🗸

Figure 29 Port Setup

The following table describes the labels in this screen.

Table 12 Port Setup

LABEL	DESCRIPTION
Port	This is the port index number.
Active	Select this check box to enable a port. The factory default for all ports is enabled. A port must be enabled for data transmission to occur.
Name	Enter a descriptive name that identifies this port.
Туре	This field displays 10/100M for an Ethernet connection and 1000M for the Gigabit Ethernet/ mini-GBIC ports.
Speed/Duplex	Select the speed and the duplex mode of the Ethernet connection on this port. For Ethernet ports, select Auto , 10M/Half Duplex , 10M/Full Duplex , 100M/Half Duplex or 100M/Full Duplex . For Gigabit Ethernet/mini-GBIC ports (25 and 26), select Auto , 100M/Full Duplex or 1000M/Full Duplex .
	Selecting Auto (auto-negotiation) allows one port to negotiate with a peer port automatically to obtain the connection speed and duplex mode that both ends support. When auto-negotiation is turned on, a port on the switch negotiates with the peer automatically to determine the connection speed and duplex mode. If the peer port does not support auto-negotiation or turns off this feature, the switch determines the connection speed by detecting the signal on the cable and using half duplex mode. When the switch's auto-negotiation is turned off, a port uses the pre-configured speed and duplex mode when making a connection, thus requiring you to make sure that the settings of the peer port are the same in order to connect.

LABEL	DESCRIPTION
Flow Control	A concentration of traffic on a port decreases port bandwidth and overflows buffer memory causing packet discards and frame losses. Flow Control is used to regulate transmission of signals to match the bandwidth of the receiving port.
	The switch uses IEEE802.3x flow control in full duplex mode and backpressure flow control in half duplex mode.
	IEEE802.3x flow control is used in full duplex mode to send a pause signal to the sending port, causing it to temporarily stop sending signals when the receiving port memory buffers fill.
	Back Pressure flow control is typically used in half duplex mode to send a "collision" signal to the sending port (mimicking a state of packet collision) causing the sending port to temporarily stop sending signals and resend later. Select Flow Control to enable it.
802.1P Priority	This priority value is added to incoming frames without a (802.1p) priority queue tag. See Priority Queue Assignment in Table 10 on page 59 for more information.
Apply	Click Apply to save the settings.
Cancel	Click Cancel to reset the fields to your previous configuration.

Table 12 Port Setup (continued)

CHAPTER 8 VLAN

The type of screen you see here depends on the **VLAN Type** you selected in the **Switch Setup** screen. This chapter shows you how to configure 802.1Q tagged and port-based VLANs.

8.1 Introduction to IEEE 802.1Q Tagged VLAN

A tagged VLAN uses an explicit tag (VLAN ID) in the MAC header to identify the VLAN membership of a frame across bridges - they are not confined to the switch on which they were created. The VLANs can be created statically by hand or dynamically through GVRP. The VLAN ID associates a frame with a specific VLAN and provides the information that switches need to process the frame across the network. A tagged frame is four bytes longer than an untagged frame and contains two bytes of TPID (Tag Protocol Identifier, residing within the type/length field of the Ethernet frame) and two bytes of TCI (Tag Control Information, starts after the source address field of the Ethernet frame).

The CFI (Canonical Format Indicator) is a single-bit flag, always set to zero for Ethernet switches. If a frame received at an Ethernet port has a CFI set to 1, then that frame should not be forwarded as it is to an untagged port. The remaining twelve bits define the VLAN ID, giving a possible maximum number of 4,096 (212) VLANs. Note that user priority and VLAN ID are independent of each other. A frame with VID (VLAN Identifier) of null (0) is called a priority frame, meaning that only the priority level is significant and the default VID of the ingress port is given as the VID of the frame. Of the 4096 possible VIDs, a VID of 0 is used to identify priority frames and value 4095 (FFF) is reserved, so the maximum possible VLAN configurations are 4,094.

TPID	User Priority	CFI	VLAN ID
2 Bytes	3 Bits	1 Bit	12 bits

8.1.1 Forwarding Tagged and Untagged Frames

Each port on the switch is capable of passing tagged or untagged frames. To forward a frame from an 802.1Q VLAN-aware switch to an 802.1Q VLAN-unaware switch, the switch first decides where to forward the frame and then strips off the VLAN tag. To forward a frame from an 802.1Q VLAN-unaware switch to an 802.1Q VLAN-aware switch, the switch first decides where to forward the frame, and then inserts a VLAN tag reflecting the ingress port's default VID. The default PVID is VLAN 1 for all ports, but this can be changed.

A broadcast frame (or a multicast frame for a multicast group that is known by the system) is duplicated only on ports that are members of the VID (except the ingress port itself), thus confining the broadcast to a specific domain.

8.2 Automatic VLAN Registration

GARP and GVRP are the protocols used to automatically register VLAN membership across switches.

8.2.1 GARP

GARP (Generic Attribute Registration Protocol) allows network switches to register and deregister attribute values with other GARP participants within a bridged LAN. GARP is a protocol that provides a generic mechanism for protocols that serve a more specific application, for example, GVRP.

8.2.1.1 GARP Timers

Switches join VLANs by making a declaration. A declaration is made by issuing a Join message using GARP. Declarations are withdrawn by issuing a Leave message. A Leave All message terminates all registrations. GARP timers set declaration timeout values.

8.2.2 GVRP

GVRP (GARP VLAN Registration Protocol) is a registration protocol that defines a way for switches to register necessary VLAN members on ports across the network. Enable this function to permit VLANs groups beyond the local switch.

Please refer to the following table for common IEEE 802.1Q VLAN terminology.

VLAN PARAMETER	TERM	DESCRIPTION
VLAN Type	Permanent VLAN	This is a static VLAN created manually.
	Dynamic VLAN	This is a VLAN configured by a GVRP registration/ deregistration process.
VLAN Administrative Control	Registration Fixed	Fixed registration ports are permanent VLAN members.
	Registration Forbidden	Ports with registration forbidden are forbidden to join the specified VLAN.
	Normal Registration	Ports dynamically join a VLAN using GVRP.
VLAN Tag Control	Tagged	Ports belonging to the specified VLAN tag all outgoing frames transmitted.
	Untagged	Ports belonging to the specified don't tag all outgoing frames transmitted.


 Table 13
 IEEE 802.1Q
 VLAN
 Terminology

VLAN PARAMETER	TERM	DESCRIPTION
VLAN Port	Port VID	This is the VLAN ID assigned to untagged frames that this port received.
	Acceptable frame type	You may choose to accept both tagged and untagged incoming frames or just tagged incoming frames on a port.
	Ingress filtering	If set, the switch discards incoming frames for VLANs that do not have this port as a member

8.3 Port VLAN Trunking

Enable **VLAN Trunking** on a port to allow frames belonging to unknown VLAN groups to pass through that port. This is useful if you want to set up VLAN groups on end devices without having to configure the same VLAN groups on intermediary devices.


Refer to the following figure. Suppose you want to create VLAN groups 1 and 2 (V1 and V2) on devices A and B. Without **VLAN Trunking**, you must configure VLAN groups 1 and 2 on all intermediary switches C, D and E; otherwise they will drop frames with unknown VLAN group tags. However, with **VLAN Trunking** enabled on a port(s) in each intermediary switch you only need to create VLAN groups in the end devices (A and B). C, D and E automatically allow frames with VLAN group tags 1 and 2 (VLAN groups that are unknown to those switches) to pass through their VLAN trunking port(s).



8.4 Select the VLAN Type

1 Select a VLAN type in the Switch Setup screen.

Figure 31 Switch Setup: Select VLAN Type



8.5 Static VLAN

Use a static VLAN to decide whether an incoming frame on a port should be

- sent to a VLAN group as normal depends on its VLAN tag.
- sent to a group whether it has a VLAN tag or not.
- blocked from a VLAN group regardless of its VLAN tag.

You can also tag all outgoing frames (that were previously untagged) from a port with the specified VID.

8.5.1 Static VLAN Status

Click Advanced Application, VLAN from the navigation panel to display the VLAN Status screen as shown next.

VLAN S									1	VLAN	Port	Setti	ng		Static VLAN	
							Po	rt Nurr	nber							
Index	VID	2	4	6	8	10	12	14	16	18	20	22	24	26	Elapsed Time	Status
		1	3 U	5 U	7 U	9 U	11 U	13 U	15 U	17 U	19 U	21 U	23 U	25 U		
1	1	UU	U	U	U	U	U	U	U	U	U	U	U	U	1:18:40	Static
			_				1	1								
Poll Interval(s)	40			Se	et Inte	erval	St	ор								
Change Pages	Previous	s Page	э	N	ext Pa	age										

Figure 32 VLAN: VLAN Status

The following table describes the labels in this screen.

LABEL	DESCRIPTION
The Number of VLAN	This is the number of VLANs configured on the switch.
Index	This is the VLAN index number.
VID	This is the VLAN identification number that was configured in the VLAN Setup screen.
Port Number	This column displays the ports that are participating in a VLAN. A tagged port is marked as T , an untagged port is marked as U and ports not participating in a VLAN are marked as "–".
Elapsed Time	This field shows how long it has been since a normal VLAN was registered or a static VLAN was set up.
Status	This field shows how this VLAN was added to the switch; dynamically using GVRP or statically, that is, added as a permanent entry.
Poll Interval(s)	The text box displays how often (in seconds) this screen refreshes. You may change the refresh interval by typing a new number in the text box and then clicking Set Interval .
Stop	Click Stop to halt polling statistics.
Change Pages	Click Previous Page or Next Page to show the previous/next screen if all status information cannot be seen in one screen.

 Table 14
 VLAN: VLAN Status

8.5.2 Configure a Static VLAN

To configure a static VLAN, click **Static VLAN** in the **VLAN Status** screen to display the screen as shown next.

Static	VLAN			VLAN Statu
Jotacio	TENN			VEAN State
	ACTIVE			
	Name			
	VLAN Group ID			
Port		Control		Tagging
1	Normal	O Fixed	C Forbidden	🗹 Tx Tagging
2	Normal	O Fixed	C Forbidden	🗹 Tx Tagging
3	Normal	O Fixed	O Forbidden	🗹 Tx Tagging
4	Normal	O Fixed	O Forbidden	🗹 Tx Tagging
<u>_</u> 5_	Normal	 → Fixed		Tx Tagging
20	Normal	Fixed	V Forpidden	ix tägying
21	Normal	C Fixed	C Forbidden	Tx Tagging
22	Normal	C Fixed	C Forbidden	🗹 Tx Tagging
23	Normal	O Fixed	C Forbidden	🗹 Tx Tagging
24	Normal	O Fixed	O Forbidden	🗹 Tx Tagging
25	Normal	O Fixed	O Forbidden	🗹 Tx Tagging
26	Normal	O Fixed	C Forbidden	🗹 Tx Tagging
		Add Car	icel Clear	
VID	Active		Name	Delete
<u>1</u>	Yes		1	
		Delete	Cancel	

Figure 33	VLAN: Static VLAN
-----------	-------------------

The following table describes the related labels in this screen.

Table 15 VLAN: Static VLAN

LABEL	DESCRIPTION
ACTIVE	Select this check box to activate the VLAN settings.
Name	Enter a descriptive name for the VLAN group for identification purposes.
VLAN Group ID	Enter the VLAN ID for this static entry; the valid range is between 1 and 4094.
Port	The port number identifies the port you are configuring.
Control	Select Normal for the port to dynamically join this VLAN group using GVRP. This is the default selection.
	Select Fixed for the port to be a permanent member of this VLAN group. Select Forbidden if you want to prohibit the port from joining this VLAN group.
Tagging	Select TX Tagging if you want the port to tag all outgoing frames transmitted with this VLAN Group ID.
Add	Click Add to add the settings as a new entry in the summary table below.
Cancel	Click Cancel to reset the fields.
Clear	Click Clear to start configuring the screen again.
VID	This field displays the ID number of the VLAN group. Click the number to edit the VLAN settings.

LABEL	DESCRIPTION
Active	This field indicates whether the VLAN settings are enabled (Yes) or disabled (No).
Name	This field displays the descriptive name for this VLAN group.
Delete	Click Delete to remove the selected entry from the summary table.
Cancel	Click Cancel to clear the Delete check boxes.

Table 15	VLAN: Static VLAN	(continued)
----------	-------------------	-------------

8.5.3 Configure VLAN Port Settings

To configure the VLAN settings on a port, click the VLAN Port Setting link in the VLAN Status screen.

) VLA	N Port Settir	ıg		VLAN Statu
	GVRP			
P	ort isolation			
Ing	gress Check			
Port	PVID	GVRP	Acceptable Frame Type	VLAN Trunking
1	1		All 🔽	
2	1		All 🔽	
3	1		All 🗨	
4	1		All	
\sim	\sim	\sim		$\sim \overline{\sim}$
20		$\sim\sim$		
21	1		All 🔽	
22	1		All 🔽	
23	1		All	
24	1		All	
25	1		All	
26	1		All	
		1	Apply Cancel	

The following table describes the labels in this screen.

Table 16	VLAN: VLAN Port Setting
----------	-------------------------

LABEL	DESCRIPTION
GVRP	GVRP (GARP VLAN Registration Protocol) is a registration protocol that defines a way for switches to register necessary VLAN members on ports across the network. Select this check box to permit VLAN groups beyond the local switch.
Port Isolation	Port Isolation allows each port (1 to 26) to communicate only with the CPU management port but not communicate with each other. All incoming ports are selected while only the CPU outgoing port is selected. This option is the most limiting but also the most secure.

LABEL	DESCRIPTION
Ingress Check	Select this check box to activate ingress filtering on the switch. Clear this check box to disable ingress filtering the switch.
Port	This field displays the port number.
PVID	Enter a number between 1 and 4094 as the port VLAN ID.
GVRP	Select this check box to allow GVRP on this port.
Acceptable Frame Type	Specify the type of frames allowed on a port. Choices are All and Tag Only . Select All from the drop-down list box to accept all untagged or tagged frames on this port. This is the default setting. Select Tag Only to accept only tagged frames on this port. All untagged frames will be dropped.
VLAN Trunking	Enable VLAN Trunking on ports connected to other switches or routers (but not ports directly connected to end users) to allow frames belonging to unknown VLAN groups to pass through the switch.
Apply	Click Apply to save the changes
Cancel	Click Cancel to start configuring the screen again.

Table 16	VLAN: VLAN Port Setting	(continued)
----------	-------------------------	-------------

8.6 Port-based VLAN Setup

Port-based VLANs are VLANs where the packet forwarding decision is based on the destination MAC address and its associated port.

Port-based VLANs require allowed outgoing ports to be defined for each port. Therefore, if you wish to allow two subscriber ports to talk to each other, for example, between conference rooms in a hotel, you must define the egress (an egress port is an outgoing port, that is, a port through which a data packet leaves) for both ports.

Port-based VLANs are specific only to the switch on which they were created.

Note: When you activate port-based VLAN, the switch uses a default VLAN ID of 1. You cannot change it.

In screens (such as **IP Setup** and **Filtering**) that require a VID, you must enter 1 as the VID.

The port-based VLAN setup screen is shown next. The **CPU** management port forms a VLAN with all Ethernet ports.

8.6.1 Configure a Port-based VLAN

Select **Port Based** as the VLAN Type in the Switch Setup screen (see Figure 31 on page 68) and then click VLAN from the navigation panel to display the next screen.

	Setting Wizard All connected Apply																											
														Inco	min	g												
		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	
	1	☑	•	•	◄	◄								☑		☑	☑	☑	•				•			M	V	1
	2			•	•		•	◄	•	•		•	•	•		•		•	•	•	•	•	•	•	◄		•	2
	3	•	•	•	•	•	☑			•		•	•	•	₹	•	•	•	•	•	•		•					3
	4			•	•		•	◄	◄	•	•	₽	◄	•	•	•		•	•	₽	•	₹	₽	•	◄			4
	5	₽	•	•	•	₹				•		•	•	₽	V	₽	₽	₽	₽	•	•		•				•	5
	6			•	•		•	◄	◄	•	•	₽	◄	•	•	•		•	•	₽	•	₹	₽	•	◄			6
	7			•	•		•	◄	•	•	•	◄	•	•		•		•	•	◄	•	•	•	•	◄			7
	8	◄	•	•	•	•	◄			•				•	◄	◄	◄	•	•				•					8
	9			•			•	₽	•	•		◄	◄	•					•	•	•	•	•	•	◄			9
	10	•	•	•	•	•	₹		•			•		•	•	•	•	•	•	•	•		•				•	10
	11	•		•			•		•	•	•	•	•		•	•	•		•	•	•	•	•	•	◄			11
	12	◄	◄	•	◄	◄	₹			•		•	•	₽	₹	₽	◄	₽	₽	•	•	•	•	•			•	12
	13	◄	•	•	•	•	•	◄		•		•		•	•	•	•	•	•	•	•	M	•			V	•	13
outgoing	14	•		•	•		•	◄	•	•	•	•	•	•	•	•	•		•	•	•	•	•	•	•			14
	15	•	•	•	•	•	•		•	•		•		•	•	•	•	•	•	•	•		•				•	15
	16	•	•	•	•		•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•	•			16
	17	•	•	•	•	•	•		•	•		•		•	•	•	•	•	•	•	•		•			•	•	17
	18	•	•	•	•	•	•	◄	◄	•	•	₽	◄	•	•	•		•	•	₽	◄	◄	₽	•	◄		•	18
	19	•	•	•	•	•	•	◄	◄	~	•	◄	~	•	•	•	•	•	•	◄	•	•	•	•	◄	•	•	19
	20	◄	₽	•	◄	•	◄			•		•	•	◄	◄	•	◄	◄	•	•	•	•	•			₽	•	20
	21	•		•	•		•	◄	•	•	•	•	◄	•	•	•		•	•	•	•	•	•	•	◄			21
	22	◄	◄	•	•	•	•	•	•	•		•		◄	•	•	◄	◄	•	•	•		•	•		₽	•	22
	23	•		•	•		•	◄	•	•	•	•	◄	•	•	•		•	•	•	•	•	•	•	◄		•	23
	24	◄	◄	•	•	•	•	•	•	•		•	•	•	•	•	◄	◄	•	•	•		•	•			•	24
	25	◄	•	•	~	•	•	•	•	•	•	•	•	◄	•	•	◄	◄	•	•	•	•	•	•		☑	•	25
	26	•		•	•		•	◄	◄	•	•	•	◄	•	•	•	•	•	•	•	•	•	•	•	◄		•	26
	CPU	◄	◄	•	•	•	•	◄	•	•	•	•	•	•	•	•	◄	◄	•	•	~	•	•	•	◄	₽	•	CPL
		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	

Figure 35 Port Based VLAN Setup (All Connected)




Figure 36 Port Based VLAN Setup (Port Isolation)

LABEL	DESCRIPTION
Setting Wizard	Choose All connected or Port isolation.
	All connected means all ports can communicate with each other, that is, there are no virtual LANs. All incoming and outgoing ports are selected. This option is the most flexible but also the least secure.
	Port isolation means that each port can only communicate with the CPU management port and cannot communicate with each other. All incoming ports are selected while only the CPU outgoing port is selected. This option is the most limiting but also the most secure.
	After you make your selection, click Apply (top right of screen) to display the screens as mentioned above. You can still customize these settings by adding/deleting incoming or outgoing ports, but you must also click Apply at the bottom of the screen.
Incoming	These are the ingress ports; an ingress port is an incoming port, that is, a port through which a data packet enters. If you wish to allow two subscriber ports to talk to each other, you must define the ingress port for both ports. The numbers in the top row denote the incoming port for the corresponding port listed on the left (its outgoing port). CPU refers to the switch management port. By default it forms a VLAN with all Ethernet ports. If it does not form a VLAN with a particular port then the switch cannot be managed from that port.
Outgoing	These are the egress ports; an egress port is an outgoing port, that is, a port through which a data packet leaves. If you wish to allow two subscriber ports to talk to each other, you must define the egress port for both ports. CPU refers to the switch management port. By default it forms a VLAN with all Ethernet ports. If it does not form a VLAN with a particular port then the switch cannot be managed from that port.
Apply	Click Apply to save the changes.
Cancel	Click Cancel to start configuring the screen again.

CHAPTER 9 Static MAC Forwarding

Use these screens to configure static MAC address forwarding.

9.1 Overview

A static MAC address is an address that has been manually entered in the MAC address table. Static MAC addresses do not age out. When you set up static MAC address rules, you are setting static MAC addresses for a port. This may reduce the need for broadcasting.

Static MAC address forwarding together with port security allow only computers in the MAC address table on a port to access the switch. See Chapter 17 on page 103 for more information on port security.

9.2 Configuring Static MAC Forwarding

Click Advanced Applications, Static MAC Forwarding in the navigation panel to display the configuration screen as shown.

<u> </u>		0			
COD Static MAC F	orwarding				
Active					
Name					
MAC Address]:		:		
VID					
Port	Port 1	•			
		Add Cancel C	lear		
Index Active	Name	MAC Address	VID	Port	Delete
<u></u>					
		Delete Cance	el		

Figure 37 Static MAC Forwarding

LABEL	DESCRIPTION
Active	Select this check box to activate your rule. You may temporarily deactivate a rule without deleting it by clearing this check box.
Name	Enter a descriptive name for identification purposes for this static MAC address forwarding rule.
MAC Address	Enter the MAC address in valid MAC address format, that is, six hexadecimal character pairs.
	Note: Static MAC addresses do not age out.
VID	Enter the VLAN identification number.
Port	Select a port where the MAC address entered in the previous field will be automatically forwarded.
Add	After you set the fields above, click Add to insert a new rule.
Cancel	Click Cancel to reset the fields.
Clear	Click Clear to begin configuring this screen afresh.
Index	Click an index number to modify a static MAC address rule for a port.
Active	This field displays whether this static MAC address forwarding rule is active (Yes) or not (No). You may temporarily deactivate a rule without deleting it.
Name	This field displays the descriptive name for identification purposes for this static MAC address-forwarding rule.
MAC Address	This field displays the MAC address that will be forwarded and the VLAN identification number to which the MAC address belongs.
Port	This field displays the port where the MAC address shown in the next field will be forwarded.
VID	This field displays the VLAN identification number.
Delete	Click Delete to remove the selected entry from the summary table.
Cancel	Click Cancel to clear the Delete check boxes.

 Table 18
 Static MAC Forwarding

CHAPTER 10 Filtering

This chapter discusses static IP and MAC address port filtering.

10.1 Overview

Port filtering means discarding (or dropping) packets based on the MAC addresses and VLAN group.

10.2 Configure a Filtering Rule

Click **Advanced Application** and **Filtering** in the navigation panel to display the screen as shown next.

Figure 38 Filtering

🔵 Filt	ering				
Active					
Name					
MAC] : 🔤 : 🖂	::		
VID					
		Add C	Cancel Clear		
Index	Active	Name	MAC Address	VID	Delete
		Delete	e Cancel		

The following table describes the related labels in this screen.

Table 19 Filtering

LABEL	DESCRIPTION
Active	Make sure to select this check box to activate your rule. You may temporarily deactivate a rule without deleting it by deselecting this check box.
Name	Type a descriptive name (up to 32 printable ASCII characters) for this rule. This is for identification purpose only.
MAC	Type a MAC address in valid MAC address format, that is, six hexadecimal character pairs.
VID	Type the VLAN group identification number.

LABEL	DESCRIPTION
Add	Click Add to save the new rule to the switch. It then displays in the summary table at the bottom of the screen.
Cancel	Click Cancel to reset the fields to your previous configuration.
Clear	Click Clear to clear the fields to the factory defaults.
Index	This field displays the index number of the rule. Click an index number to change the settings.
Active	This field displays Yes when the rule is activated and No when is it deactivated.
Name	This field displays the descriptive name for this rule. This is for identification purpose only.
MAC Address	This field displays the source/destination MAC address with the VLAN identification number to which the MAC address belongs.
VID	This field displays the VLAN identification number.
Delete	Check the rule(s) that you want to remove in the Delete column and then click the Delete button.
Cancel	Click Cancel to clear the selected checkbox(es) in the Delete column.

Table 19 Filtering (continued)

CHAPTER 11 Spanning Tree Protocol

This chapter introduces the Spanning Tree Protocol (STP).

11.1 Overview

STP detects and breaks network loops and provides backup links between switches, bridges or routers. It allows a switch to interact with other STP-compliant switches in your network to ensure that only one route exists between any two stations on the network.

11.1.1 STP Terminology

The root bridge is the base of the spanning tree; it is the bridge with the lowest identifier value (MAC address).

Path cost is the cost of transmitting a frame onto a LAN through that port. It is assigned according to the speed of the link to which a port is attached. The slower the media, the higher the cost.

	LINK SPEED	RECOMMENDED VALUE	RECOMMENDED RANGE	ALLOWED RANGE
Path Cost	4Mbps	250	100 to 1000	1 to 65535
Path Cost	10Mbps	100	50 to 600	1 to 65535
Path Cost	16Mbps	62	40 to 400	1 to 65535
Path Cost	100Mbps	19	10 to 60	1 to 65535
Path Cost	1Gbps	4	3 to 10	1 to 65535
Path Cost	10Gbps	2	1 to 5	1 to 65535

Table 20 STP Path Costs

On each bridge, the root port is the port through which this bridge communicates with the root. It is the port on this switch with the lowest path cost to the root (the root path cost). If there is no root port, then this switch has been accepted as the root bridge of the spanning tree network.

For each LAN segment, a designated bridge is selected. This bridge has the lowest cost to the root among the bridges connected to the LAN.

11.1.2 How STP Works

After a bridge determines the lowest cost-spanning tree with STP, it enables the root port and the ports that are the designated ports for connected LANs, and disables all other ports that participate in STP. Network packets are therefore only forwarded between enabled ports, eliminating any possible network loops.

STP-aware switches exchange Bridge Protocol Data Units (BPDUs) periodically. When the bridged LAN topology changes, a new spanning tree is constructed.

Once a stable network topology has been established, all bridges listen for Hello BPDUs (Bridge Protocol Data Units) transmitted from the root bridge. If a bridge does not get a Hello BPDU after a predefined interval (Max Age), the bridge assumes that the link to the root bridge is down. This bridge then initiates negotiations with other bridges to reconfigure the network to re-establish a valid network topology.

11.1.3 STP Port States

STP assigns five port states to eliminate packet looping. A bridge port is not allowed to go directly from blocking state to forwarding state so as to eliminate transient loops.

PORT STATE	DESCRIPTION
Disabled	STP is disabled (default).
Blocking	Only configuration and management BPDUs are received and processed.
Listening	All BPDUs are received and processed.
Learning	All BPDUs are received and processed. Information frames are submitted to the learning process but not forwarded.
Forwarding	All BPDUs are received and processed. All information frames are received and forwarded.

Table 21STP Port States

11.2 STP Status

Click Advanced Application, Spanning Tree Protocol in the navigation panel to display the status screen as shown next.

anning Tree Protocol : Runr	col Status	<u>Configuration</u>
paining free Frotocol. Run	ning	
Bridge	Root	Our Bridge
Bridge ID	8000-0013491ad4fa	8000-0013491ad4fa
Hello Time (second)	2	2
Max Age (second)	20	20
Forwarding Delay (second)	15	15
Cost to Bridge	0	
Port ID	0X0000	
Topology Changed Times	C)
Time Since Last Change	0:00):26

Figure 39 Spanning Tree Protocol: Statu

Table 22	Spanning	Tree Protocol: Sta	atus
----------	----------	--------------------	------

LABEL	DESCRIPTION
Spanning Tree Protocol	This field displays Running if STP is activated. Otherwise, it displays Down .
Configuration	Click Configuration to configure STP settings. Refer to Section 11.3 on page 84.
Bridge	Root refers to the base of the spanning tree (the root bridge). Our Bridge is this switch. This switch may also be the root bridge.
Bridge ID	This is the unique identifier for this bridge, consisting of bridge priority plus MAC address. This ID is the same for Root and Our Bridge if the switch is the root switch.
Hello Time (second)	This is the time interval (in seconds) at which the root switch transmits a configuration message. The root bridge determines Hello Time, Max Age and Forwarding Delay
Max Age (second)	This is the maximum time (in seconds) a switch can wait without receiving a configuration message before attempting to reconfigure.
Forwarding Delay (second)	This is the time (in seconds) the root switch will wait before changing states (that is, listening to learning to forwarding).
Cost to Bridge	This is the path cost from the root port on this switch to the root switch.
Port ID	This is the priority and number of the port on the switch through which this switch must communicate with the root of the Spanning Tree.
Topology Changed Times	This is the number of times the spanning tree has been reconfigured.
Time Since Last Change	This is the time since the spanning tree was last reconfigured.

LABEL	DESCRIPTION
Poll Interval(s)	The text box displays how often (in seconds) this screen refreshes. You may change the refresh interval by typing a new number in the text box and then clicking Set Interval .
Stop	Click Stop to halt STP statistic polling.

Table 22 Spanning Tree Protocol: Status (continued)	Table 22	Spanning	Tree Protocol:	Status	(continued)
---	----------	----------	----------------	--------	-------------

11.3 Configure STP

To configure STP, click the **Configuration** link in the **Spanning Tree Protocol** screen as shown next.

🔵 🌖 Spannir	ng Tree Protocol		<u>Status</u>
	Active		
	Bridge Priority	32768 💌	
	Hello Time	2 Seconds	
	Max Age	20 Seconds	
F	orwarding Delay	15 Seconds	
Port	Active	Priority	Path Cost
1		128	19
2		128	19
3		128	19
4		128	19
\sim	~~~~	128	
20	$\sim\sim\sim\sim$	$\sim \sim \sim \sim$	$\sim\sim\sim\sim\sim\sim\sim$
21		128	19
22		128	19
23		128	19
24		128	19
25		128	4
26		128	4
		L	L
		Apply Cancel	

Figure 40	Spanning Tree Protocol: Configuration

Table 23	Spanning Tr	ee Protocol:	Configuration
----------	-------------	--------------	---------------

LABEL	DESCRIPTION
Status	Click Status to display the Spanning Tree Protocol Status screen (see Figure 39 on page 83).
Active	Select this check box to activate STP. Clear this checkbox to disable STP.

LABEL	DESCRIPTION
Bridge Priority	Bridge priority is used in determining the root switch, root port and designated port. The switch with the highest priority (lowest numeric value) becomes the STP root switch. If all switches have the same priority, the switch with the lowest MAC address will then become the root switch. Select a value from the drop-down list box. The lower the numeric value you assign, the higher the priority for this bridge. Bridge Priority determines the root bridge, which in turn determines Hello Time, Max Age and Forwarding Delay.
Hello Time	This is the time interval in seconds between BPDU (Bridge Protocol Data Units) configuration message generations by the root switch. The allowed range is 1 to 10 seconds.
Max Age	This is the maximum time (in seconds) a switch can wait without receiving a BPDU before attempting to reconfigure. All switch ports (except for designated ports) should receive BPDUs at regular intervals. Any port that ages out STP information (provided in the last BPDU) becomes the designated port for the attached LAN. If it is a root port, a new root port is selected from among the switch ports attached to the network. The allowed range is 6 to 40 seconds.
Forwarding Delay	This is the maximum time (in seconds) a switch will wait before changing states. This delay is required because every switch must receive information about topology changes before it starts to forward frames. In addition, each port needs time to listen for conflicting information that would make it return to a blocking state; otherwise, temporary data loops might result. The allowed range is 4 to 30 seconds. As a general rule:
	Note: 2 * (Forward Delay - 1) >= Max Age >= 2 * (Hello Time + 1)
Port	This field displays the port number.
Active	Select this check box to activate STP on this port.
Priority	Configure the priority for each port here. Priority decides which port should be disabled when more than one port forms a loop in a switch. Ports with a higher priority numeric value are disabled first. The allowed range is between 0 and 255 and the default value is 128.
Path Cost	Path cost is the cost of transmitting a frame on to a LAN through that port. It is assigned according to the speed of the bridge. The slower the media, the higher the cost - see Table 20 on page 81 for more information.
Apply	Click Apply to save your changes back to the switch.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 23
 Spanning Tree Protocol: Configuration (continued)

CHAPTER 12 Bandwidth Control

This chapter shows you how you can cap the maximum bandwidth using the **Bandwidth Control** screen.

12.1 Bandwidth Control Setup

Bandwidth control means defining a maximum allowable bandwidth for incoming and/or outgoing traffic flows on a port.

Click **Advanced Application** and then **Bandwidth Control** in the navigation panel to bring up the screen as shown next.

Port	Active	Ingress	Rate	Egress	Rate
1		64	Kbps	64	Kbps
2		64	Kbps	64	Kbps
3		64	Kbps	64	Kbps
4		64	Kbps	64	Kbps
	$\sim \overline{\sim} \sim$	64	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~		- Kby
\sim	\sim	\sim	Kopo	\sim	ps
21		64	Kbps	64	Kbps
22		64	Kbps	64	Kbps
23		64	Kbps	64	Kbps
24		64	Kbps	64	Kbps
25		64	Kbps	64	Kbps
26		64	Kbps	64	Kbps

Figure 41 Bandwidth Control

Table 24 Ba	ndwidth Control
-------------	-----------------

LABEL	DESCRIPTION	
Active	Select this check box to enable bandwidth control on the switch.	
Port This field displays the port number.		

LABEL	DESCRIPTION	
Active	Make sure to select this check box to activate bandwidth control on a port.	
Ingress Rate	Specify the maximum bandwidth allowed in Kilobits per second (Kbps) for the incoming traffic flow on a port.	
	If you enter a number between 64 and 1728, the switch automatically rounds the number down to the nearest multiple of 64.	
	If you enter a number between 1729 and 1999, the rate is fixed at 1792.	
	If you enter a number between 2000 and 103999, the switch rounds the number down to the nearest multiple of 1000.	
	On a Gigabit Ethernet/ Mini-GBIC port, the switch rounds a number down to the nearest multiple of 8000 for a number between 104000 and 1000000.	
Egress Rate	Specify the maximum bandwidth allowed in Kilobits per second (Kbps) for the out- going traffic flow on a port.	
	If you enter a number between 64 and 1728, the switch automatically rounds the number down to the nearest multiple of 64.	
	If you enter a number between 1729 and 1999, the rate is fixed at 1792.	
	If you enter a number between 2000 and 103999, the switch rounds the number down to the nearest multiple of 1000.	
	On a Gigabit Ethernet/ Mini-GBIC port, the switch rounds a number down to the nearest multiple of 8000 for a number between 104000 and 1000000.	
Apply	Click Apply to save the settings.	
Cancel	Click Cancel to reset the fields to your previous configuration.	

Table 24	Bandwidth Control	(continued)
----------	-------------------	-------------

CHAPTER 13 Broadcast Storm Control

This chapter introduces and shows you how to configure the broadcast storm control feature.

13.1 Overview

Broadcast storm control limits the number of broadcast frames that can be stored in the switch buffer or sent out from the switch. Broadcast frames that arrive when the buffer is full are discarded. Enable this feature to reduce broadcast traffic coming into your network.

13.2 Broadcast Storm Control Setup

Click Advanced Application, Broadcast Storm Control in the navigation panel to display the screen as shown next.

Figure 42	Broadcast Storm	Control
i igaio +	Diodaodot Otorini	001101

	Active			
Port	Active	64	Rate	-
1		······		Kbps -
2		64		Kbps
3		64		Kbps
4		64		Kbps
<i>5</i> ~~~	~~~		\sim	Jan
\sim			Ň	
21		64		Kbps
22		64		Kbps
23		64		Kbps
24		64		Kbps
25		64		Kbps
26		64		Kbps

LABEL	DESCRIPTION
Active	Select this check box to enable broadcast storm control on the switch. Clear this check box to disable the feature.
Port	This field displays a port number.
Active	Select this check box to enable broadcast storm control on the port. Clear this check box to disable the feature.
Rate	Specify the traffic a port receives in Kilobits per second (Kbps).
	If you enter a number between 64 and 1728, the switch automatically rounds the number down to the nearest multiple of 64.
	If you enter a number between 1729 and 1999, the rate is fixed at 1792.
	If you enter a number between 2000 and 103999, the switch rounds the number down to the nearest multiple of 1000.
	On a Gigabit Ethernet/ Mini-GBIC port, the switch rounds a number down to the nearest multiple of 8000 for a number between 104000 and 1000000.
Apply	Click Apply to save your changes back to the switch.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 25
 Broadcast Storm Control

CHAPTER 14 Mirroring

This chapter discusses the Mirror setup screens.

14.1 Overview

Port mirroring allows you to copy a traffic flow to a mirror port (the port you copy the traffic to) in order that you can examine the traffic from the mirror port without interference.

14.2 Port Mirroring Setup

Click **Advanced Application**, **Mirroring** in the navigation panel to display the **Mirroring** screen. Use this screen to select a mirror port and specify the traffic flow to be copied to the mirror port.

) Mirroring		
Active		
Monitor Port	Port 1 💌	
Ingress	All C Destination M. : : : : : : : : : : : : : : : : :	
Egress	All O Destination M. : : : : : : : : : : : : : : : : :	
Port	Mirrored	Direction
1		Ingress 💌
2		Ingress 💌
3		Ingress 💌
4		Ingress 💌
\sim	~~~	Incress -
	$\sim\sim\sim\sim\sim\sim\sim$	
21		Ingress 💌
22		Ingress 💌
23		Ingress 💌
24		Ingress 💌
25		Ingress 💌
26		Ingress 💌
	Apply Cancel	

Figure 43 Mirroring

LABEL	DESCRIPTION
Active	Clear this check box to deactivate port mirroring on the switch.
Mirror Port	The mirror port is the port you copy the traffic to in order to examine it in more detail without interfering with the traffic flow on the original port(s). Select this port from this drop-down list box.
Ingress	You can specify to copy all incoming traffic or traffic to/from a specified MAC address.
	Select All to copy all incoming traffic from the mirrored port(s).
	Select Destination MAC to copy incoming traffic to a specified MAC address on the mirrored port(s). Enter the destination MAC address in the fields provided.
	Select Source MAC to copy incoming traffic from a specified MAC address on the mirrored port(s). Enter the source MAC address in the fields provided.
Egress	You can specify to copy all outgoing traffic or traffic to/from a specified MAC address.
	Select All to copy all outgoing traffic from the mirrored port(s).
	Select Destination MAC to copy outgoing traffic to a specified MAC address on the mirrored port(s). Enter the destination MAC address in the fields provided.
	Select Source MAC to copy outgoing traffic from a specified MAC address on the mirrored port(s). Enter the source MAC address in the fields provided.
Port	This field displays the port number.
Mirrored	Select this option to mirror the traffic on a port.
Direction	Specify the direction of the traffic to mirror. Choices are Egress (outgoing), Ingress (incoming) and Both .
Apply	Click Apply to save the changes.
Cancel	Click Cancel to start configuring the screen again.

CHAPTER 15 Link Aggregation

This chapter shows you how to logically aggregate physical links to form one logical, higherbandwidth link.

15.1 Overview

Link aggregation (trunking) is the grouping of physical ports into one logical higher-capacity link. You may want to trunk ports if for example, it is cheaper to use multiple lower-speed links than to under-utilize a high-speed, but more costly, single-port link.

However, the more ports you aggregate then the fewer available ports you have. A trunk group is one logical link containing multiple ports.

The beginning port of each trunk group must be physically connected to form a trunk group.

15.2 Dynamic Link Aggregation

The switch adheres to the IEEE 802.3ad standard for static and dynamic (LACP) port trunking.

The switch supports the link aggregation IEEE802.3ad standard. This standard describes the Link Aggregate Control Protocol (LACP), which is a protocol that dynamically creates and manages trunk groups.

When you enable LACP link aggregation on a port, the port can automatically negotiate with the ports at the remote end of a link to establish trunk groups. LACP also allows port redundancy, that is, if an operational port fails, then one of the "standby" ports become operational without user intervention. Please note that:

- You must connect all ports point-to-point to the same Ethernet switch and configure the ports for LACP trunking.
- LACP only works on full-duplex links.
- All ports in the same trunk group must have the same media type, speed, duplex mode and flow control settings.

Configure trunk groups or LACP before you connect the Ethernet switch to avoid causing network topology loops.

15.2.1 Link Aggregation ID

LACP aggregation ID consists of the following information¹:

 Table 27
 Link Aggregation ID: Local Switch

SYSTEM PRIORITY	MAC ADDRESS	KEY	PORT PRIORITY	PORT NUMBER
0000	00-00-00-00-00	0000	00	0000

Table 28 Link Aggregation ID: Peer Switch

SYSTEM PRIORITY	MAC ADDRESS	KEY	PORT PRIORITY	PORT NUMBER
0000	00-00-00-00-00	0000	00	0000

15.3 Link Aggregation Status

Click Advanced Application, Link Aggregation in the navigation panel. The Link Aggregation Control Protocol Status screen displays by default.

	_ink Aggr	egation Co	ntrol Protocol	Status		Configuration
Index		Aggregator ID			Enabled Ports	Synchronized Ports
1			0,0000,00,0000)] 0,0000,00,0000)]	[(0000,00-	-	-
2	•• •		0,0000,00,0000)] 0,0000,00,0000)]	[(0000,00-	-	-
3			0,0000,00,0000)] 0,0000,00,0000)]	[(0000,00-	-	-
Polling l	nterval(s)	40	Set Interval	Stop		

Figure 44 Link Aggregation Control Protocol Status

^{1.} Port Priority and Port Number are 0 as it is the aggregator ID for the trunk group, not the individual port.

LABEL	DESCRIPTION
Index	This field displays the trunk ID to identify a trunk group, that is, one logical link containing multiple ports.
Aggregator ID	Refer to Section 15.2.1 on page 94 for more information on this field.
Enabled Port	These are the ports you have configured in the Link Aggregation screen to be in the trunk group.
Synchronized Ports	These are the ports that are currently transmitting data as one logical link in this trunk group.
Poll Interval(s)	The text box displays how often (in seconds) this screen refreshes. You may change the refresh interval by typing a new number in the text box and then clicking Set Interval .
Stop	Click Stop to halt statistic polling.

 Table 29
 Link Aggregation Control Protocol Status

15.4 Link Aggregation Setup

Click **Configuration** in the **Link Aggregation Control Protocol Status** screen to display the screen shown next.

riority 65535]
Active	Dynamic(LACP)
Group	LACP Timeout
None 🔽	30 💌 seconds
None 👻	30 💌 seconds
None 👻	30 💌 seconds
None 💌	30 💌 seconds
	30 - exconder
	Jib seconds
None 🗸	30 💌 seconds
None 🗸	30 💌 seconds
None 🗸	30 🗸 seconds
None 🗸	30 🗸 seconds
None 🗸	30 🗸 seconds
None 🗸	30 - seconds
	Active

Figure 45 Link Aggregation: Configuration

The following table describes the labels in this screen.

LABEL	DESCRIPTION			
Link Aggregatio	Link Aggregation Control Protocol			
Active	Select this checkbox to enable Link Aggregation Control Protocol (LACP).			
System Priority	LACP system priority is a number between 1 and 65,535. The switch with the lowest system priority (and lowest port number if system priority is the same) becomes the LACP "server". The LACP "server" controls the operation of LACP setup. Enter a number to set the priority of an active port using Link Aggregate Control Protocol (LACP). The smaller the number, the higher the priority level.			
Group ID	The field identifies the link aggregation group, that is, one logical link containing multiple ports			
Active	Select this option to activate a trunk group.			
Dynamic (LACP)	Select this check box to enable LACP for a trunk.			
Port	This field displays the port number.			
Group	Select the trunk group to which a port belongs.			

 Table 30
 Link Aggregation Control Protocol: Configuration

LABEL	DESCRIPTION	
LACP Timeout	Timeout is the time interval between the individual port exchanges of LACP packets in order to check that the peer port in the trunk group is still up. If a port does not respond after three tries, then it is deemed to be "down" and is removed from the trunk. Set a short timeout (one second) for busy trunked links to ensure that disabled ports are removed from the trunk group as soon as possible. Select either 1 second or 30 seconds.	
Apply	Click Apply to save your changes back to the switch.	
Cancel	Click Cancel to begin configuring this screen afresh.	

Table 30	Link Aggregation	Control Protocol:	Configuration	(continued)
----------	------------------	-------------------	---------------	-------------

CHAPTER 16 Port Authentication

This chapter describes the 802.1x authentication method and RADIUS server connection setup.

16.1 Overview

IEEE 802.1x is an extended authentication protocol² that allows support of RADIUS (Remote Authentication Dial In User Service, RFC 2138, 2139) for centralized user profile and accounting management on a network RADIUS server.

16.1.1 RADIUS

RADIUS (Remote Authentication Dial-In User Service) authentication is a popular protocol used to authenticate users by means of an external server instead of (or in addition to) an internal device user database that is limited to the memory capacity of the device. In essence, RADIUS authentication allows you to validate an unlimited number of users from a central location.





16.2 Port Authentication Configuration

To enable port authentication, first activate IEEE802.1x security (both on the switch and the port(s)) then configure the RADIUS server settings.

Click Advanced Application, Port Authentication in the navigation panel to display the screen as shown.

^{2.} At the time of writing, only Windows XP of the Microsoft operating systems supports it. See the Microsoft web site for information on other Windows operating system support. For other operating systems, see its documentation. If your operating system does not support 802.1x, then you may need to install 802.1x client software.





16.2.1 Activate IEEE 802.1x Security

From the **Port Authentication** screen, display the configuration screen as shown.

Figure 48 Port Authentication: 802.1x

802.1x			Port.	Authenticat
Active				
Port	Active	Reauthentication	Reauthent	ication Time
1		On 💌	3600	seconds
2		On 👻	3600	seconds
3		On 💌	3600	seconds
4		On 💌	3600	seconds
\sim	$\sim \sim \sim$		3600	sronds
~20~~				Second
21		On 👻	3600	seconds
22		On 👻	3600	seconds
23		On 🔽	3600	seconds
24		On 🗸	3600	seconds
25		On 👻	3600	seconds
26	Π	On 🔽	3600	seconds

Table 31Port Authentication: 802.1x

LABEL	DESCRIPTION
Active	Select this check box to permit 802.1x authentication on the switch.
	Note: You must first enable 802.1x authentication on the switch before configuring it on each port.
Port	This field displays a port number.
Active	Select this checkbox to permit 802.1x authentication on this port. You must first allow 802.1x authentication on the switch before configuring it on each port.
Reauthentication	Specify if a subscriber has to periodically re-enter his or her username and password to stay connected to the port.
Reauthentication Timer	Specify how often a client has to re-enter his or her username and password to stay connected to the port.

LABEL	DESCRIPTION
Apply	Click Apply to save your changes back to the switch.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 31
 Port Authentication: 802.1x (continued)

16.2.2 Configuring RADIUS Server Settings

From the **Port Authentication** screen, click **RADIUS** to display the configuration screen as shown.

Figure 49 Port Authentication: RADIUS

Table 32 Port Authentication: RADIUS

LABEL	DESCRIPTION		
Authentication Se	Authentication Server		
IP Address	Enter the IP address of the external RADIUS server in dotted decimal notation.		
UDP Port	The default port of the RADIUS server for authentication is 1812 . You need not change this value unless your network administrator instructs you to do so.		
Shared SecretSpecify a password (up to 32 alphanumeric characters) as the key to be sl between the external RADIUS server and the switch. This key is not sent of network. This key must be the same on the external RADIUS server and the			
Apply	Click Apply to save your changes back to the switch.		
Cancel	Click Cancel to begin configuring this screen afresh.		

CHAPTER 17 Port Security

This chapter shows you how to set up port security.

17.1 Overview

Port security allows only packets with dynamically learned MAC addresses and/or configured static MAC addresses to pass through a port on the switch.

For maximum port security, enable this feature, disable MAC address learning and configure static MAC address(es) for a port. It is not recommended you disable **Port Security** together with MAC address learning as this will result in many broadcasts.

17.2 Port Security Setup

Click **Advanced Application**, **Port Security** in the navigation panel to display the screen as shown.

OPort	Security		
	Activ	B	
Port	Active	Address Learning	Limited Number of Learned MAC Address
1			0
2			0
3		V	O
4			D
\sim	$\sim \nabla \sim$	$\sim \sim \sim$	
\sim	\sim	$\sim \sim \sim$	
21			0
22			p
23			0
24			0
		Apply	Cancel



LABEL	DESCRIPTION
Active	Select this check box to enable the port security feature on the switch.
Port	This field displays a port number.
Active	Select this check box to enable the port security feature on this port. The switch forwards packets whose MAC address(es) is in the MAC address table on this port. Packets with no matching MAC address(es) are dropped.
	Clear this check box to disable the port security feature. The switch forwards all packets on this port.
Address Learning	MAC address learning reduces outgoing broadcast traffic. For MAC address learning to occur on a port, the port itself must be active with address learning enabled.
Limited Number of Learned MAC Address	Use this field to limit the number of (dynamic) MAC addresses that may be learned on a port. For example, if you set this field to "5" on port 2, then only the devices with these five learned MAC addresses may access port 2 at any one time. A sixth device would have to wait until one of the five learned MAC addresses aged out. MAC address aging out time can be set in the Switch Setup screen. The valid range is from "0" to "254". "0" means this feature is disabled.
Apply	Click Apply to save your changes back to the switch.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 33
 Port Security

CHAPTER 18 Queuing Method

This chapter introduces the queuing methods supported.

18.1 Overview

Queuing is used to help solve performance degradation when there is network congestion. Use the **Queuing Method** screen to configure queuing algorithms for outgoing traffic. See also **Priority Queue Assignment** in **Switch Setup** and **802.1p Priority** in **Port Setup** for related information.

Queuing algorithms allow switches to maintain separate queues for packets from each individual source or flow and prevent a source from monopolizing the bandwidth.

QUEUE	PRIORITY
Q3	4 (highest)
Q2	3
Q1	2
Q0	1 (lowest)

Table 34	Physical Queue	Priority
----------	----------------	----------

18.1.1 Strict Priority Queuing (SPQ)

Strict Priority Queuing (SPQ) services queues based on priority only. As traffic comes into the switch, traffic on the highest priority queue, Q3 is transmitted first. When that queue empties, traffic on the next highest-priority queue, Q2 is transmitted until Q2 empties, and then traffic is transmitted on Q1 and so on. If higher priority queues never empty, then traffic on lower priority queues never gets sent. SPQ does not automatically adapt to changing network requirements.

18.1.2 Weighted Round Robin Scheduling (WRR)

Round Robin Scheduling services queues on a rotating basis and is activated only when a port has more traffic than it can handle. A queue is a given an amount of bandwidth irrespective of the incoming traffic on that port. This queue then moves to the back of the list. The next queue is given an equal amount of bandwidth, and then moves to the end of the list; and so on, depending on the number of queues being used. This works in a looping fashion until a queue is empty. Weighted Round Robin Scheduling (WRR) uses the same algorithm as round robin scheduling, but services queues based on their priority and queue weight (the number you configure in the queue **Weight** field) rather than a fixed amount of bandwidth. WRR is activated only when a port has more traffic than it can handle. Queues with larger weights get more service than queues with smaller weights. This queuing mechanism is highly efficient in that it divides any available bandwidth across the different traffic queues and returns to queues that have not yet emptied.

18.2 Configuring Queuing Method

Click Advanced Application, Queuing Method in the navigation panel.

🔍 🕘 Queuing Method 👘 👘			
Method	Strictly Priority Weighted Round Robin Scheduling		
	Q0 Weight	1 💌	
	Q1 Weight	1 💌	
	Q2 Weight	1 💌	
	Q3 Weight	15 🗸	
	Apply Cancel		

Table	35	Queuing	Method
-------	----	---------	--------

LABEL	DESCRIPTION
Method	Select Strictly Priority or Weighted Round Robin Scheduling.
	Strict Priority Queuing (SPQ) services queues based on priority only. When the highest priority queue empties, traffic on the next highest-priority queue begins. Q3 has the highest priority and Q0 the lowest. The default queuing method is Strictly Priority .
	Weighted Round Robin Scheduling (WRR) services queues on a rotating basis based on their queue weight (the number you configure in the queue Weight field). Queues with larger weights get more service than queues with smaller weights.
Weight	When you select Weighted Round Robin Scheduling , use the drop-down list boxes to choose queue weights (1-15). Bandwidth is divided across the different traffic queues according to their weights.
Apply	Click Apply to save your changes back to the switch.
Cancel	Click Cancel to begin configuring this screen afresh.

CHAPTER 19 Static Route

This chapter shows you how to configure static routes.

19.1 Configuring Static Route

Static routes tell the switch how to forward IP traffic when you configure the TCP/IP parameters manually.

Click IP Application, Static Routing in the navigation panel to display the screen as shown.

Figure 52	Statio	Routing				
C () Static	Routing					
	Ac	tive				
	Na	ame				
	Destination	n IP Address	0.0.0.0			
	IP Subi	net Mask	0.0.0.0			
	Gateway	IP Address	0.0.0.0			
	M	ətric				
		Add	ancel Clear	1		
Index Active	Name	Destination Address	Subnet Mask	Gateway Address	Metric	Delete
<u>1</u> Yes	Example	172.21.1.1	255.255.0.0	192.168.1.2	2	
		Delete	e Cancel			

Table 36 Static Routing

LABEL	DESCRIPTION		
Active	This field allows you to activate/deactivate this static route.		
Name	Enter a descriptive name (up to 32 printable ASCII characters) for identification purposes.		
Destination IP Address	This parameter specifies the IP network address of the final destination. Routing is always based on network number. If you need to specify a route to a single host, use a subnet mask of 255.255.255.255 in the subnet mask field to force the network number to be identical to the host ID.		
IP Subnet Mask	Enter the subnet mask for this destination.		
Gateway IP Address	Enter the IP address of the gateway. The gateway is an immediate neighbor of your switch that will forward the packet to the destination. The gateway must be a router on the same segment as your switch.		

LABEL	DESCRIPTION
Metric	The metric represents the "cost" of transmission for routing purposes. IP routing uses hop count as the measurement of cost, with a minimum of 1 for directly connected networks. Enter a number that approximates the cost for this link. The number need not be precise, but it must be between 1 and 15. In practice, 2 or 3 is usually a good number.
Add	Click Add to insert a new static route.
Cancel	Click Cancel to reset the above fields to your previous configuration.
Clear	Click Clear to set the above fields back to the factory defaults.
Index	This field displays the index number of the route. Click a number to edit the static route entry.
Active	This field displays Yes when the static route is activated and NO when it is deactivated.
Name	This field displays the descriptive name for this route. This is for identification purpose only.
Destination Address	This field displays the IP network address of the final destination.
Subnet Mask	This field displays the subnet mask for this destination.
Gateway Address	This field displays the IP address of the gateway. The gateway is an immediate neighbor of your switch that will forward the packet to the destination.
Metric	This field displays the cost of transmission for routing purposes.
Delete	Click Delete to remove the selected entry from the summary table.
Cancel	Click Cancel to clear the Delete check boxes.

 Table 36
 Static Routing (continued)

CHAPTER 20 Differentiated Services

This chapter shows you how to configure Differentiated Services (DiffServ) on the switch.

20.1 Overview

Quality of Service (QoS) mechanisms provide the best service on a per-flow guarantee. To fine-tune the levels of services on the priority of the traffic flow using QoS places a heavy burden on the network infrastructure.

DiffServ is a class of service (CoS) model that marks packets so that they receive specific perhop treatment at DiffServ-compliant network devices along the route based on the application types and traffic flow. Packets are marked with DiffServ Code Points (DSCPs) indicating the level of service desired. This allows the intermediary DiffServ-compliant network devices to handle the packets differently depending on the code points without the need to negotiate paths or remember state information for every flow. In addition, applications do not have to request a particular service or give advanced notice of where the traffic is going.

20.1.1 DSCP and Per-Hop Behavior

DiffServ defines a new DS (Differentiated Services) field to replace the Type of Service (ToS) field in the IP header. The DS field contains a 2-bit unused field and a 6-bit DSCP field which can define up to 64 service levels. The following figure illustrates the DS field.

DSCP is backward compatible with the three precedence bits in the ToS octet so that non-DiffServ compliant, ToS-enabled network device will not conflict with the DSCP mapping.


Figure 53 DiffServ: Differentiated Service Field

|--|

The DSCP value determines the forwarding behavior, the PHB (Per-Hop Behavior), that each packet gets across the DiffServ network. Based on the marking rule different kinds of traffic can be marked for different priorities of forwarding. Resources can then be allocated according to the DSCP values and the configured policies.

20.1.2 DiffServ Network Example

The following figure depicts a simple DiffServ network consisting of a group of contiguous DiffServ-compliant network devices.



Switch A marks traffic flowing into the network based on the configured marking rules. Intermediary network devices 1 and 2 allocate network resources (such as bandwidth) by mapping the DSCP values and the associated policies.

20.2 Activating DiffServ

Activate DiffServ to allow the switch to enable DiffServ on the selected port(s).

Click IP Application, DiffServ in the navigation panel to display the screen as shown.

Diffserv	DSCP Set
Active	
Port	Active
1	
2	
3	
4	
$\sim\sim\sim\sim$	~~~~~
21	
22	
23	
24	
25	
26	
	Apply Cancel

Figure 55 DiffServ

The following table describes the labels in this screen.

Table 37 DiffServ

LABEL	LABEL DESCRIPTION	
Active	Select this option to enable DiffServ on the switch.	
Port	This field displays the index number of a port on the switch.	
Active	Select this option to enable DiffServ on the port.	

Table 37	DiffServ	(continued)
----------	----------	-------------

LABEL	DESCRIPTION	
Apply	Click Apply to save the changes.	
Cancel	Click Cancel to start configuring this screen again.	

20.3 DSCP-to-IEEE802.1p Priority Mapping

You can configure the DSCP to IEEE802.1p mapping to allow the switch to prioritize all traffic based on the incoming DSCP value according to the DiffServ to IEEE802.1p mapping table.

The following table shows the default DSCP-to-IEEE802.1P mapping.

Table 38 Default DSCP-IEEE802.1p Mapping

DSCP VALUE	0 – 7	8 – 15	16 – 23	24 – 31	32 – 39	40 – 47	48 – 55	56 – 63
IEEE802.1P	0	1	2	3	4	5	6	7

20.3.1 Configuring DSCP Settings

To change the DSCP-IEEE 802.1p mapping click the DSCP Setting link in the DiffServ screen to display the screen as shown next.

igu	re 56			'v: D	SCP	Set	ting						D107		
DSCP	to 802.				-								Diffsen	2	
0	0 🗸	1	0 🗸	2	0 -	3	0 🗸	4	0 🗸	5	0 🗸	6	0 🗸	7	0 -
8	1 -	9	1 🗸	10	1 🕶	11	1 🗸	12	1 🗸	13	1 🕶	14	1 🗸	15	1 -
16	2 🗸	17	2 💌	18	2 🗸	19	2 🗸	20	2 🗸	21	2 🗸	22	2 🗸	23	2 🗸
24	3 🗸	25	3 🗸	26	3 🗸	27	3 🗸	28	3 🗸	29	3 🗸	30	3 🗸	31	3 🗸
32	4 🗸	33	4 🗸	34	4 🗸	35	4 🗸	36	4 🗸	37	4 🗸	38	4 🗸	39	4 🗸
40	5 🕶	41	5 🕶	42	5 🕶	43	5 🕶	44	5 🕶	45	5 🕶	46	5 🕶	47	5 🕶
48	6 🕶	49	6 💌	50	6 🕶	51	6 🕶	52	6 🔻	53	6 🗸	54	6 🕶	55	6 🗸
56	7 🗸	57	7 🗸	58	7 🗸	59	7 🗸	60	7 🗸	61	7 🗸	62	7 🗸	63	7 🗸
						A	pply	Cano	el						

The following table describes the labels in this screen.

LABEL	DESCRIPTION
0 63	This is the DSCP classification identification number. To set the IEEE802.1p priority mapping, select the priority level from the drop-down list box.
Apply	Click Apply to save the changes.
Cancel	Click Cancel to discard all changes and start configuring the screen again.

Table 39 DiffServ: DSCP Setting

CHAPTER 21 **Maintenance**

This chapter explains how to configure the maintenance screens that let you maintain the firmware and configuration files.

21.1 The Maintenance Screen

Click Management, Maintenance in the navigation panel to open the following screen.

Figure 57	Maintenance

Firmware Upgrade	Click Here
Restore Configuration	Click Here
Backup Configuration	Click Here
Load Factory Default	Click Here
Reboot System	Click Here

The following table describes the labels in this screen.

LABEL	DESCRIPTION
Firmware Upgrade	Access this screen to upload a new firmware.
Restore Configuration	Access this screen to upload a previously saved configuration file to the switch.
Backup Configuration	Access this screen to back up the current switch configuration.
Load Factory Default	Click the button to clear all switch configuration information you configured and return to the factory defaults.
	Note: All custom configuration will be lost.
	This takes up to two minutes(or wait until the switch finishes rebooting). If you want to access the switch web configurator again, you may need to change the IP address of your computer to be in the same subnet as that of the default switch IP address (192.168.1.1).
Reboot System	Click the button to restart the switch without physically turning the power off.
	Note: This takes up to two minutes (or wait until the switch finishes rebooting). This does not affect the switch's configuration.

Table 40 Maintenance

21.2 Firmware Upgrade

Make sure you have downloaded (and unzipped) the correct model firmware and version to your computer before uploading to the device.

Note: Be sure to upload the correct model firmware as uploading the wrong model firmware may damage your device.

From the Maintenance screen, display the Firmware Upgrade screen as shown next.

Figure 58	Firmware	Upgrade
-----------	----------	---------

🔇 🌖 Firmware Upgrade 💦 🔵	Maintenance
To upgrade the internal switch firmware, browse to button.) the location of the binary (.BIN) file and click Apply
File Path Browse	
Up	grade

Type the path and file name of the firmware file you wish to upload to the switch in the **File Path** text box or click **Browse** to locate it. After you have specified the file, click **Upgrade**.

After the firmware upgrade process is complete, see the **System Info** screen to verify your current firmware version number.

21.3 Restore a Configuration File

Restore a previously saved configuration from your computer to the switch using the **Restore Configuration** screen.

Figure 59 Restore Configuration

🔵 Restore Configu	uration	<u>Maintenance</u>
To restore the device's confi Restore button.	guration from a file, browse to the locat	ion of the configuration file and click
File Path	Browse	
	Restore	

Type the path and file name of the configuration file you wish to restore in the **File Path** text box or click **Browse** to display the **Choose File** screen (below) from which you can locate it. After you have specified the file, click **Restore**. "config" is the name of the configuration file on the switch, so your backup configuration file is automatically renamed when you restore using this screen.

21.4 Backing Up a Configuration File

Backing up your switch configurations allows you to create various "snap shots" of your device from which you may restore at a later date.

Back up your current switch configuration to a computer using the **Backup Configuration** screen.

Figure 60 Backup Configuration

Backup Configuration	<u>Maintenance</u>
This page allows you to back up the device's current configuration Backup button.	to your workstation. Now click the
Backup	

Follow the steps below to back up the current switch configuration to your computer in this screen.

- 1 Click Backup.
- 2 Click Save to display the Save As screen.
- **3** Choose a location to save the file on your computer from the **Save in** drop-down list box and type a descriptive name for it in the **File name** list box. Click **Save** to save the configuration file to your computer.

21.5 Load Factory Defaults

Follow the steps below to reset the switch back to the factory defaults.

1 In the **Maintenance** screen, click the **Click Here** button next to **Load Factory Defaults** to clear all switch configuration information you configured and return to the factory defaults. The following message appears.

Figure 61 Load Factory Default: Conformation

Microsof	i Internet Explorer 🛛 🔀
?	Are you sure you want to load factory default?
	Cancel

2 Click **OK** to display the screen shown next.



3 Click **OK** to begin resetting all switch configurations to the factory defaults and then wait for the switch to restart. This takes up to two minutes. If you want to access the switch web configurator again, you may need to change the IP address of your computer to be in the same subnet as that of the default switch IP address (192.168.1.1).

21.6 Reboot System

Reboot System allows you to restart the switch without physically turning the power off. Follow the steps below to reboot the switch.


1 In the **Maintenance** screen, click the **Click Here** button next to **Reboot System** to display the next screen.

Figure 63 Reboot System: Confirmation

Microsof	t Internet Explor	er	×
?	Are you sure you	ı want to reboot	system?
	ОК	Cancel	

2 Click OK to display the screen shown next.

Figure 64 Reboot System: Start



3 Click **OK** again and then wait for the switch to restart. This takes up to two minutes. This does not affect the switch's configuration.

21.7 FTP Command Line

This section shows some examples of uploading to or downloading files from the switch using FTP commands. First, understand the filename conventions.

21.7.1 Filename Conventions

The configuration file contains the settings in the screens such as password, switch setup, IP Setup, etc.. Once you have customized the switch's settings, they can be saved (as a plain text file) back to your computer under a filename of your choosing.

ZyNOS (ZyXEL Network Operating System sometimes referred to as the "ras" file) is the system firmware and has a "bin" filename extension.

Table 41 Fi	ename Conventions
-------------	-------------------

FILE TYPE	INTERNAL NAME	EXTERNAL NAME	DESCRIPTION
Configuration File	config		This is the configuration filename on the switch. Uploading the config file replaces the specified configuration file system, including your switch configurations, system-related data (including the default password), the error log and the trace log.
Firmware	Ras	*.bin	This is the generic name for the ZyNOS firmware on the switch.

21.7.1.1 Example FTP Commands

ftp> put firmware.bin ras

This is a sample FTP session showing the transfer of the computer file "firmware.bin" to the switch.

ftp> get config config.cfg

This is a sample FTP session saving the current configuration to a file called "config.cfg" on your computer.

If your (T)FTP client does not allow you to have a destination filename different than the source, you will need to rename them as the switch only recognizes "config" and "ras". Be sure you keep unaltered copies of both files for later use.

Note: Be sure to upload the correct model firmware as uploading the wrong model firmware may damage your device.

21.7.2 FTP Command Line Procedure

- **1** Launch the FTP client on your computer.
- **2** Enter open, followed by a space and the IP address of your switch.
- **3** Press [ENTER] when prompted for a username.
- 4 Enter your password as requested (the default is "1234").
- **5** Enter bin to set transfer mode to binary.
- 6 Use put to transfer files from the computer to the switch, for example, put firmware.bin ras transfers the firmware on your computer (firmware.bin) to the switch and renames it to "ras". Similarly, put config.cfg config transfers the configuration file on your computer (config.cfg) to the switch and renames it to "config". Likewise get config config.cfg transfers the configuration file on the switch to your computer and renames it to "config.cfg". See Table 41 on page 117 for more information on filename conventions.

7 Enter quit to exit the ftp prompt.

21.7.3 GUI-based FTP Clients

The following table describes some of the commands that you may see in GUI-based FTP clients.

General Commands for GUI-based FTP Clients

COMMAND	DESCRIPTION
Host Address	Enter the address of the host server.
Login Type	Anonymous. This is when a user I.D. and password is automatically supplied to the server for anonymous access. Anonymous logins will work only if your ISP or service administrator has enabled this option. Normal. The server requires a unique User ID and Password to login.
Transfer Type	Transfer files in either ASCII (plain text format) or in binary mode. Configuration and firmware files should be transferred in binary mode.
Initial Remote Directory	Specify the default remote directory (path).
Initial Local Directory	Specify the default local directory (path).

21.7.4 FTP over WAN Restrictions

FTP over WAN will not work when:

- Telnet service is disabled in Secured Client Sets.
- The IP address(es) in the **Secured Client Sets** menu does not match the client IP address. If it does not match, the switch will disconnect the Telnet session immediately.

CHAPTER 22 Access Control

This chapter describes how to control access to the switch.

22.1 Overview

• A console port access control session and Telnet access control session cannot coexist. The console port has higher priority. If you telnet to the switch and someone is already logged in from the console port, then you will see the following message.

Figure 65 Console Port Priority

```
"Local administrator is configuring this device now!!!
Connection to host lost."
```

• A console port or Telnet session can coexist with one FTP session, up to five Web sessions (five different usernames and passwords) and/or limitless SNMP access control sessions.

 Table 42
 Access Control Overview

	Console Port	SSH	Telnet	FTP	Web	SNMP
Number of concurrent sessions allowed	1 console port, 3 Console port ha priority and Teln priority.	s the higl	nest	1	5	No limit

22.2 The Access Control Main Screen

Click **Management**, **Access Control** in the navigation panel to display the main screen as shown.


Figure 66	Access Control
-----------	----------------

🌔 Access Control 💦 🔵	
SNMP	Click Here
Logins	Click Here
Service Access Control	Click Here
Remote Management	Click Here

22.3 About SNMP

Simple Network Management Protocol (SNMP) is an application layer protocol used to manage and monitor TCP/IP-based devices. SNMP is used to exchange management information between the network management system (NMS) and a network element (NE). A manager station can manage and monitor the switch through the network via SNMP version one (SNMPv1) and/or SNMP version 2c. The next figure illustrates an SNMP management operation. SNMP is only available if TCP/IP is configured.

Figure 67 SNMP Management Model



An SNMP managed network consists of two main components: agents and a manager.

An agent is a management software module that resides in a managed switch (the switch). An agent translates the local management information from the managed switch into a form compatible with SNMP. The manager is the console through which network administrators perform network management functions. It executes applications that control and monitor managed devices.

The managed devices contain object variables/managed objects that define each piece of information to be collected about a switch. Examples of variables include such as number of packets received, node port status etc. A Management Information Base (MIB) is a collection of managed objects. SNMP allows a manager and agents to communicate for the purpose of accessing these objects.

SNMP itself is a simple request/response protocol based on the manager/agent model. The manager issues a request and the agent returns responses using the following protocol operations:

COMMAND	DESCRIPTION
Get	Allows the manager to retrieve an object variable from the agent.
GetNext	Allows the manager to retrieve the next object variable from a table or list within an agent. In SNMPv1, when a manager wants to retrieve all elements of a table from an agent, it initiates a Get operation, followed by a series of GetNext operations.

Table 43 SNMP Commands

 Table 43
 SNMP Commands

COMMAND	DESCRIPTION
Set	Allows the manager to set values for object variables within an agent.
Тгар	Used by the agent to inform the manager of some events.

22.3.1 Supported MIBs

MIBs let administrators collect statistics and monitor status and performance.

The switch supports the following MIBs:

- SNMP MIB II (RFC 1213)
- RFC 1157 SNMP v1
- RFC 1493 Bridge MIBs
- RFC 1643 Ethernet MIBs
- RFC 1155 SMI
- RFC 2674 SNMPv2, SNMPv2c
- RFC 1757 RMON
- SNMPv2, SNMPv2c or later version, compliant with RFC 2011 SNMPv2 MIB for IP, RFC 2012 SNMPv2 MIB for TCP, RFC 2013 SNMPv2 MIB for UDP
- Private MIBs

22.3.2 SNMP Traps

The switch sends traps to an SNMP manager when an event occurs. SNMP traps supported are outlined in the following table.

GENERIC TRAP	SPECIFIC TRAP	DESCRIPTION
0 (Cold Start)	0	This trap is sent when the switch is turned on.
1 (WarmStart)	0	This trap is sent when the switch restarts.
2 (linkDown)	0	This trap is sent when the Ethernet link is down.
3 (linkUp)	0	This trap is sent when the Ethernet link is up.
4 (authenticationFailure)	0	This trap is sent when an SNMP request comes from non-authenticated hosts.

Table 44 SNMP Traps

22.3.3 Configuring SNMP

From the Access Control screen, display the SNMP screen. You can click Access Control to go back to the Access Control screen.

Get Community	public	
Set Community	public	
Trap Community	public	
Trap Destination	0.0.0.0	
	0.0.0.0	
	0.0.0.0	
	0.0.0	

Figure 68 Access Control: SNMP

The following table describes the labels in this screen.

Table 45 Access Control: SNMP

LABEL	DESCRIPTION
Get Community	Enter the get community, which is the password for the incoming Get- and GetNext-requests from the management station.
Set Community	Enter the set community, which is the password for incoming Set- requests from the management station.
Trap Community	Enter the trap community, which is the password sent with each trap to the SNMP manager.
Trap Destination	Enter the IP addresses of up to four stations to send your SNMP traps to.
Apply	Click Apply to save your changes back to the switch.
Cancel	Click Cancel to begin configuring this screen afresh.

22.4 Setting Up Login Accounts

Up to five people (one administrator and four non-administrators) may access the switch via web configurator at any one time.

• An administrator is someone who can both view and configure switch changes. The username for the Administrator is always **admin**. The default administrator password is **1234**.

Note: It is highly recommended that you change the default administrator password (**1234**).

• A non-administrator (username is something other than **admin**) is someone who can view but not configure switch settings.

Click Access Control from the navigation panel and then click Logins from this screen.

Figure 69 Access Control: Logins

Administrator			Access Control
Old Password			
New Password			
Retype to confirm			
	your new password v jotten your password		The system will lock you out
Login	User Name	Password	Retype to confirm
1			
2			
3			
4			
		Apply Cancel	

The following table describes the labels in this screen.

Table 46	Access	Control:	Logins
----------	--------	----------	--------

LABEL	DESCRIPTION				
Administrator	Administrator				
	This is the default administrator account with the "admin" user name. You cannot change the default administrator user name. Only the administrator has read/write access.				
Old Password	Type the existing system password (1234 is the default password when shipped).				
New Password	Enter your new system password.				
Retype to confirm	Retype your new system password for confirmation				
Edit Logins	Edit Logins				
You may configure pas	swords for up to four users. These people have read-only access.				
User Name	Set a user name (up to 30 characters long).				
Password	Enter your new system password.				
Retype to confirm	Retype your new system password for confirmation				
Apply	Click Apply to save your changes back to the switch.				
Cancel	Click Cancel to begin configuring this screen afresh.				

22.5 SSH Overview


Unlike Telnet or FTP, which transmit data in clear text, SSH (Secure Shell) is a secure communication protocol that combines authentication and data encryption to provide secure encrypted communication


between two hosts over an unsecured network.



22.6 How SSH works

The following table summarizes how a secure connection is established between two remote hosts.





1 Host Identification

The SSH client sends a connection request to the SSH server. The server identifies itself with a host key. The client encrypts a randomly generated session key with the host key and server key and sends the result back to the server.

The client automatically saves any new server public keys. In subsequent connections, the server public key is checked against the saved version on the client computer.

2 Encryption Method

Once the identification is verified, both the client and server must agree on the type of encryption method to use.

3 Authentication and Data Transmission

After the identification is verified and data encryption activated, a secure tunnel is established between the client and the server. The client then sends its authentication information (user name and password) to the server to log in to the server.

22.7 SSH Implementation on the Switch

Your switch supports SSH version 2 using RSA authentication and three encryption methods (DES, 3DES and Blowfish). The SSH server is implemented on the switch for remote management and file transfer on port 22. Only one SSH connection is allowed at a time.

22.7.1 Requirements for Using SSH

You must install an SSH client program on a client computer (Windows or Linux operating system) that is used to connect to the switch over SSH.

22.7.2 SSH Login Example

You can use an SSH client program to access the switch. The following figure shows an example using a text-based SSH client program. Refer to the documentation that comes with your SSH program for information on using it.



```
C:\>ssh2 admin@192.168.1.1
Ø
       WARNING: HOST IDENTIFICATION HAS CHANGED!
                                                     ß
IT IS POSSIBLE THAT SOMEONE IS DOING SOMETHING NASTY!
Someone could be eavesdropping on you right now (man-in-the-middle attack)!
It is also possible that the host key has just been changed.
Please contact your system administrator.
Add correct host key to "C:/Documents and Settings/Administrator/Application
Data/SSH/hostkeys/key_22_192.168.1.1.pub" to get rid of this message.
Received server key's fingerprint: xigil-gidot-homug-duzab-tocyh-pamyb-
ronep-tisaf-hebip-gokeb-goxix You can get a public key's fingerprint by
running % ssh-keygen -F publickey.pub
on the keyfile. Agent forwarding is disabled to avoid attacks by corrupted
servers. X11 forwarding is disabled to avoid attacks by corrupted servers.
Are you sure you want to continue connecting (yes/no)? yes
Do you want to change the host key on disk (yes/no)? yes
Agent forwarding re-enabled.
X11 forwarding re-enabled.
Host key saved to C:/Documents and Settings/Administrator/Application Data/
SSH/hostkeys/key 22 192.168.1.1.pub host key for 192.168.1.1, accepted by
Administrator Thu May 12 2005 09:52:21
admin's password:
Authentication successful.
Copyright (c) 1994 - 2005 ZyXEL Communications Corp.
ras>
```

22.8 Introduction to HTTPS

HTTPS (HyperText Transfer Protocol over Secure Socket Layer, or HTTP over SSL) is a web protocol that encrypts and decrypts web pages. Secure Socket Layer (SSL) is an application-level protocol that enables secure transactions of data by ensuring confidentiality (an unauthorized party cannot read the transferred data), authentication (one party can identify the other party) and data integrity (you know if data has been changed).


It relies upon certificates, public keys, and private keys.

HTTPS on the switch is used so that you may securely access the switch using the web configurator. The SSL protocol specifies that the SSL server (the switch) must always authenticate itself to the SSL client (the computer which requests the HTTPS connection with the switch), whereas the SSL client only should authenticate itself when the SSL server requires it to do so. Authenticating client certificates is optional and if selected means the SSL-client must send the switch a certificate. You must apply for a certificate for the browser from a CA that is a trusted CA on the switch.

Please refer to the following figure.

- **1** HTTPS connection requests from an SSL-aware web browser go to port 443 (by default) on the switch's WS (web server).
- **2** HTTP connection requests from a web browser go to port 80 (by default) on the switch's WS (web server).

Figure 73 HTTPS Implementation



Note: If you disable **HTTP** in the **Service Access Control** screen, then the switch blocks all HTTP connection attempts.

22.9 HTTPS Example

If you haven't changed the default HTTPS port on the switch, then in your browser enter "https://switch IP Address/" as the web site address where "switch IP Address" is the IP address or domain name of the switch you wish to access.

22.9.1 Internet Explorer Warning Messages

When you attempt to access the switch HTTPS server, a Windows dialog box pops up asking if you trust the server certificate. Click **View Certificate** if you want to verify that the certificate is from the switch.

You see the following **Security Alert** screen in Internet Explorer. Select **Yes** to proceed to the web configurator login screen; if you select **No**, then web configurator access is blocked.

-		, ,	
Security	Aler	t 🕺	
ß	Information you exchange with this site cannot be viewed or changed by others. However, there is a problem with the site's security certificate.		
	A The security certificate was issued by a company you have not chosen to trust. View the certificate to determine whether you want to trust the certifying authority.		
	The security certificate date is valid.		
	The name on the security certificate is invalid or does not match the name of the site		
	Do you want to proceed?		
		Yes No View Certificate	

Figure 74 Security Alert Dialog Box (Internet Explorer)

22.9.2 Netscape Navigator Warning Messages

When you attempt to access the switch HTTPS server, a **Website Certified by an Unknown Authority** screen pops up asking if you trust the server certificate. Click **Examine Certificate** if you want to verify that the certificate is from the switch.

If Accept this certificate temporarily for this session is selected, then click OK to continue in Netscape.

Select Accept this certificate permanently to import the switch's certificate into the SSL client.

Website	Certified by an Unknown Authority	×		
	Unable to verify the identity of ES-2024A 0013491ad4fa as a trusted site.			
<u> </u>	Possible reasons for this error:			
	- Your browser does not recognize the Certificate Authority that issued the site's certificate			
	- The site's certificate is incomplete due to a server misconfiguration.			
	- You are connected to a site pretending to be ES-2024A 0013491ad4fa, possibly to obtain your confidential information.			
	Please notify the site's webmaster about this problem.			
	Before accepting this certificate, you should examine this site's certificate carefully. Are you willing to to accept this certificate for the purpose of identifying the Web site ES-2024A 0013491ad4fa?			
	Examine Certificate			
	O Accept this certificate permanently			
	 Accept this certificate temporarily for this session 			
	O Do not accept this certificate and do not connect to this Web site			
	OK Cancel <u>H</u> elp			

Figure 75 Security Certificate 1 (Netscape)

Figure 76	Security Certifica	te 2 (Netscape)


Server Certificate Expired	×
"ES-2024A 0013491ad4fa" is a site that uses a security certificate to encrypt data during transmission, but its certificate expired on 2/19/1924 1:39 AM.	
You should check to make sure that your computer's time (currently set to Thursday, May 12, 2005 17:46:00) is com	rect.
Would you like to continue anyway?	
View Certificate	
OK Cancel Help	

22.9.3 The Main Screen

After you accept the certificate and enter the login username and password, the switch main screen appears. The lock displayed in the bottom right of the browser status bar denotes a secure connection.

Veb Configurator - Microsoft Inte	rnet Explo	rer									. 8
Edit ⊻iew Favorites <u>T</u> ools	Help										*
Back 🔹 🔿 🖌 🔕 🐼 🚮 🗔 Se	earch 🙀 I	Favorites 🌒 M	edia 🎯 🖏 🖉) ei E							
ress 🐻 https://192.168.1.1/										▼ ∂₀₀	Li
ZyXEL						ß	Status 🗈	l Logou	t 🖸 Hel	lp	
MENU											
Basic Setting		Status									
Advanced Application		Jp Time: 2:50:5									
IP Application	Port	Link	State	LACP	TxPkts	RxPkts	Errors	Tx KB/s			
	1	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
Management	2	100M/F	FORWARDING	Disabled	977	1019	0	43.266	2.805	2:50:48	
	3	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	4	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	5	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	<u>6</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	<u>7</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	8	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	9	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	<u>10</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	11	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	<u>12</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	<u>13</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	<u>14</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	<u>15</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	<u>16</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	17	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
	18	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00	
		rval(s) 40	Set Interval	Stop	··						
							© Copyright '	1995- 0 05 b	oy ZyXEL Co	mmunicatio	ns (
									Interr		_

Figure 77 Login Screen (Internet Explorer)



ack 🚽 Forward 🚽 Reload	Stop 🚺	https://19	2.168.1.1/						-	- Go 🤇
ZyXEL						@ S1	atus 🗎	Logout		
MENU		Status								
Basic Setting		Up Time: 2	2:53:48							
Advanced Application	Port	Link	State	LACP	TxPkts	RxPkts	Errors	Tx KB/s	Rx KB/s	Up Time
IP Application	1	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
Management	<u>-</u>	100M/F	FORWARDING		1226	1192	0	0.0	0.0	2:53:38
	<u>-</u> <u>3</u>	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>4</u>	Down	STOP	Disabled	0		Ŭ	0.0	0.0	0:00:00
	5	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	<u>6</u>	Down	STOP	Disabled	0	- 0	0	0.0	0.0	0:00:00
	7	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	8	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	9	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	10	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	11	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	12	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	13	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	14	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	15	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	16	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	17	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	18	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	19	Down	STOP	Disabled	0	0	0	0.0	0.0	0:00:00
	Poll Inte	rval(s) 4	0 Set Interval	Stop						
	Port	4	ALL - Clear Counte	er						

22.10 Service Port Access Control

Service Access Control allows you to decide what services you may use to access the switch. You may also change the default service port and configure "trusted computer(s)" for each service in the **Remote Management** screen (discussed later). Click **Access Control** to go back to the main **Access Control** screen.

Services	Active	Service Port	Timeout	
Telnet	~	23		
SSH		22		
FTP		21		
HTTP		80	3 Minutes	
HTTPS	V	443		
ICMP	~			
SNMP	~			

Figure 79 Access Control: Service Access Control

The following table describes the fields in this screen.

LABEL	DESCRIPTION
Services	Services you may use to access the switch are listed here.
Active	Select this option for the corresponding services that you want to allow to access the switch.
Service Port	For Telnet, SSH, FTP, HTTP or HTTPS services, you may change the default service port by typing the new port number in the Server Port field. If you change the default port number then you will have to let people (who wish to use the service) know the new port number for that service.
Timeout	Type how many minutes a management session (via the web configurator) can be left idle before the session times out. After it times out you have to log in with your password again. Very long idle timeouts may have security risks. A value of "0" means a management session never times out, no matter how long it has been left idle (not recommended).
Apply	Click Apply to save your changes back to the switch.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 47
 Access Control: Service Access Control

22.11 Remote Management

From the Access Control screen, display the Remote Management screen as shown next.

You can specify a group of one or more "trusted computers" from which an administrator may use a service to manage the switch. Click **Access Control** to return to the **Access Control** screen.

		te Management It Setup						-	100000	Contro
Entry	Active	Start Address	End Address	Telnet	FTP	HTTP	ICMP	SNMP	SSH	HTTPS
1	•	0.0.0.0	0.0.0.0		\checkmark	\checkmark	\checkmark	•	•	\checkmark
2		0.0.0.0	0.0.0.0							
3		0.0.0.0	0.0.0.0							
4		0.0.0.0	0.0.0.0							

Figure 80 Access Control: Remote Management

The following table describes the labels in this screen.

 Table 48
 Access Control: Remote Management

LABEL	DESCRIPTION
Entry	This is the client set index number. A "client set" is a group of one or more "trusted computers" from which an administrator may use a service to manage the switch.
Active	Select this check box to activate this secured client set. Clear the check box if you wish to temporarily disable the set without deleting it.
Start Address End Address	Configure the IP address range of trusted computers from which you can manage this switch. The switch checks if the client IP address of a computer requesting a service or protocol matches the range set here. The switch immediately disconnects the session if it does not match.
Telnet/FTP/ Web/ICMP/ SNMP/SSH/ HTTPS	Select services that may be used for managing the switch from the specified trusted computers.
Apply	Click Apply to save your changes back to the switch.
Cancel	Click Cancel to begin configuring this screen afresh.

CHAPTER 23 Diagnostic

This chapter explains the **Diagnostic** screen.

23.1 Diagnostic

Click **Management**, **Diagnostic** in the navigation panel to open this screen. Use this screen to check system logs, reset the system or ping IP addresses.

Figure 81 Diagnostic

Piagnostic Resolving 192.168. Reply from 192.188 Reply from 192.186 Ping Host Successf	1.10 1.10	A
System Log	Display Clear	
IP Ping	IP Address Ping	
Ethernet Port Test	Port 1 Port Test	

The following table describes the labels in this screen.

Table 49	Diagnostic
	Diagnootio

LABEL	DESCRIPTION
System Log	Click Display to display a log of events in the multi-line text box. Click Clear to empty the text box and reset the syslog entry.
IP Ping	Type the IP address of a device that you want to ping in order to test a connection. Click Ping to have the switch ping the IP address (in the field to the left).
Ethernet Port Test	From the Port drop-down list box, select a port number and click Port Test to perform internal loopback test.

CHAPTER 24 Cluster Management

This chapter introduces cluster management.

24.1 Overview


Cluster Management allows you to manage switches through one switch, called the cluster manager. The switches must be directly connected and be in the same VLAN group so as to be able to communicate with one another.

Table 50 ZYAEL Clustering Management Specification	Table 50	ZyXEL Clustering Management Specifications
--	----------	--

Maximum number of cluster members	24
Cluster Member Models	Must be compatible with ZyXEL cluster management implementation.
Cluster Manager	The switch through which you manage the cluster member switches.
Cluster Members	The switches being managed by the cluster manager switch.

In the following example, switch **A** in the basement is the cluster manager and the other switches on the upper floors of the building are cluster members.





24.2 Cluster Management Status

Click **Management**, **Cluster Management** in the navigation panel to display the following screen.

Note: A cluster can only have one manager.

Figure 83	Cluster	Management:	Status
-----------	---------	-------------	--------

	stering Manageme			<u>Configura</u>
	Status	Manager		
Manager		00:a0:c5:d4:88:bf		
e Numbe	r Of Member = 2			
e Numbe Index	r Of Member = 2 MacAddr	Name	Model	Status
		Name ES-4024A	Model ES-4024A	Status Online

The following table describes the labels in this screen.

Table 51 Cluster Management: Statu	S
------------------------------------	---

LABEL	DESCRIPTION
Status	This field displays the role of this switch within the cluster. Manager
	Member (you see this if you access this screen in the cluster member switch directly and not via the cluster manager)
	None (neither a manager nor a member of a cluster)
Manager	This field displays the cluster manager switch's hardware MAC address.
The Number of Member	This field displays the number of switches that make up this cluster. The following fields describe the cluster member switches.
Index	You can manage cluster member switches via the cluster manager switch. Each number in the Index column is a hyperlink leading to the cluster member switch's web configurator (see Figure 84 on page 137).
MacAddr	This is the cluster member switch's hardware MAC address.
Name	This is the cluster member switch's System Name.
Model	This field displays the model name.
Status	This field displays:
	Online (the cluster member switch is accessible)
	Error (for example the cluster member switch password was changed or the switch was set as the manager and so left the member list, etc.)
	Offline (the switch is disconnected - Offline shows approximately 1.5 minutes after the link between cluster member and manager goes down)

24.2.1 Cluster Member Switch Management

Go to the **Clustering Management Status** screen of the cluster manager switch and then select an **Index** hyperlink from the list of members to go to that cluster member switch's web configurator home page. This cluster member web configurator home page and the home page that you'd see if you accessed it directly are different.



				🕅 Status 🖬 Logout 🖬 Help
Basic Setting	ES-4024A/ES	5-402 <u>4A</u>		Member Menu
Advanced Application				
P Application	Basic Setting	Advanced Applications	Routing Protocol	Management
Maintenance Access Control Diagnostic	System Info General Setup Switch Setup IP Setup Port Setup	<u>VLAN</u> Static MAC Forward <u>Filtering</u> Spanning Tree Protocol Bandwidth Control Broadcast Storm Control Mirroring	<u>Static Routing</u> <u>RIP</u> IGMP DVMRP OSPE	Maintenance Diagnostic MAC Table IP Table ARP Table Routing Table DHCP Server Status
Cluster Management MAC Table IP Table ARP Table Routing Table		Link Aggregation Port Authentication Port Security DHCP Access Control Classifier DiffServ Queuing Method		Port Status
		VRRP		_

24.2.1.1 Uploading Firmware to a Cluster Member Switch

You can use FTP to upload firmware to a cluster member switch through the cluster manager switch as shown in the following example.

Figure 85 Example: Uploading Firmware to a Cluster Member Switch

```
C:\>ftp 192.168.1.1
Connected to 192.168.1.1.
220 FTP version 1.0 ready at Thu Jan 1 00:47:52 1970
User (192.168.1.1: (none)): admin
331 Enter PASS command
Password:
230 Logged in
ftp> ls
200 Port command okay
150 Opening data connection for LIST
--w--w- 1 owner group 3209434 Jul 01 12:00 ras
                                  393216 Jul 01 12:00 config
-rw-rw-rw-
          1 owner group
                                    0 Jul 01 12:00 fw-00-a0-c5-d4-88-bf
--w--w--w- 1 owner group
-rw-rw-rw- 1 owner group
                                        0 Jul 01 12:00 config-00-a0-c5-d4-88-bf
226 File sent OK
ftp: 463 bytes received in 0.00Seconds 463000.00Kbytes/sec.
ftp> bin
200 Type I OK
ftp> put 350du1.bin fw-00-a0-c5-d4-88-bf
200 Port command okay
150 Opening data connection for STOR fw-00-a0-c5-d4-88-bf
226 File received OK
ftp: 262144 bytes sent in 0.63Seconds 415.44Kbytes/sec.
ftp>
```

The following table explains some of the FTP parameters.

FTP PARAMETER	DESCRIPTION
User	Enter "admin".
Password	The web configurator password default is 1234.
ls	Enter this command to list the name of cluster member switch's firmware and configuration file.
350dul.bin	This is the name of the firmware file you want to upload to the cluster member switch.
fw-00-a0-c5-d4-88-bf	This is the cluster member switch's firmware name as seen in the cluster manager switch.
config-00-a0-c5-d4-88-bf	This is the cluster member switch's configuration file name as seen in the cluster manager switch.

Table 52 FTP Upload to Cluster Member Example

24.3 Configuring Cluster Management

Click Configuration from the Cluster Management screen to display the next screen.

Clustering Manag	ng Management C ger:	onfigurati	on		<u>Status</u>
Active Name VID	Master				
	1	Apply C	Cancel		
Clustering Candi	date:				
List	00:a0:c5:00:00:01/ES	-4024A/ES	4024A		
Password 🛛					
	Add	Cancel	Refresh		
Index	MacAddr		Name	Model	Remove
	F	Remove	Cancel		

Figure 86 Clustering Management Configuration

The following table describes the labels in this screen.

Table 53 (Clustering	Management	Configuration
------------	------------	------------	---------------

LABEL	DESCRIPTION
Clustering Manager	
Active	Select Active to have this switch become the cluster manager switch. A cluster can only have one manager. Other (directly connected) switches that are set to be cluster managers will not be visible in the Clustering Candidates list. If a switch that was previously a cluster member is later set to become a cluster manager, then its Status is displayed as Error in the Cluster Management Status screen and a warning icon () appears in the member summary list below.
Name	Type a name to identify the Clustering Manager. You may use up to 20 printable characters (no spaces are allowed).
VID	This is the VLAN ID and is only applicable if the switch is set to 802.1Q VLAN. All switches must be directly connected and in the same VLAN group to belong to the same cluster. Switches that are not in the same VLAN group are not visible in the Clustering Candidates list. This field is ignored if the Clustering Manager is using Port-based VLAN.
Apply	Click Apply to save these changes to the switch.
Cancel	Click Cancel to begin configuring this part of the screen afresh.
Clustering Candidate	The following fields relate to the switches that are potential cluster members.
List	A list of suitable candidates found by auto-discovery is shown here. The switches must be directly connected. Directly connected switches that are set to be cluster managers will not be visible in the Clustering Candidate list. Switches that are not in the same management VLAN group will not be visible in the Clustering Candidate list.

LABEL	DESCRIPTION
Password	Each cluster member's password is its web configurator password. Select a member in the Clustering Candidate list and then enter its web configurator password. If that switch administrator changes the web configurator password afterwards, then it cannot be managed from the Cluster Manager . Its Status is displayed as Error in the Cluster Management Status screen and a warning icon () appears in the member summary list below. If multiple devices have the same password then hold [SHIFT] and click those switches to select them. Then enter their common web configurator password.
Add	Click Add to save this part of the screen to the switch.
Cancel	Click Cancel to begin configuring this part of the screen afresh.
Refresh	Click Refresh to perform auto-discovery again to list potential cluster members.
The next summary ta	ble shows the information for the clustering members configured.
Index	This is the index number of a cluster member switch.
HwAddr	This is the cluster member switch's hardware MAC address.
Name	This is the cluster member switch's System Name.
Model	This is the cluster member switch's model name.
Remove	Select this checkbox and then click the Remove button to remove a cluster member switch from the cluster.
Cancel	Click Cancel to begin configuring this part of the screen afresh.

 Table 53
 Clustering Management Configuration (continued)

CHAPTER 25 MAC Table

This chapter introduces the MAC Table screen.


25.1 Overview

The **MAC Table** screen (a MAC table is also known as a filtering database) shows how frames are forwarded or filtered across the switch's ports. It shows what device MAC address, belonging to what VLAN group (if any) is forwarded to which port(s) and whether the MAC address is dynamic (learned by the switch) or static (manually entered in the **Static MAC Forwarding** screen).

The switch uses the MAC table to determine how to forward frames. See the following figure.

- **1** The switch examines a received frame and learns the port on which this source MAC address came.
- **2** The switch checks to see if the frame's destination MAC address matches a source MAC address already learned in the MAC table.
 - If the switch has already learned the port for this MAC address, then it forwards the frame to that port.
 - If the switch has not already learned the port for this MAC address, then the frame is flooded to all ports. Too much port flooding leads to network congestion.
 - If the switch has already learned the port for this MAC address, but the destination port is the same as the port it came in on, then it filters the frame.

Figure 87 MAC Table Flowchart



25.2 Viewing the MAC Table

Click Management, MAC Table in the navigation panel to display the following screen.

Figure 88 MAC Table

Bort by	MAC	VID	Port	
Index	MAC Address	VID	Port	Туре
1	00:85:a0:01:01:00	1	8	dynamic
2	00:85:a0:01:01:04	1	8	dynamic
3	00:a0:c5:00:00:01	1	2	dynamic
4	00:a0:c5:fe:ea:71	1	CPU	static
5	00:a0:c5:fe:ea:71	2	CPU	static

The following table describes the labels in this screen.

LABEL	DESCRIPTION
Sort by	Click one of the following buttons to display and arrange the data according to that button type. The information is then displayed in the summary table below.
MAC	Click this button to display and arrange the data according to MAC address.
VID	Click this button to display and arrange the data according to VLAN group.
Port	Click this button to display and arrange the data according to port number. This field displays Drop if you configure a filtering rule to drop the traffic from the MAC address.
Index	This is the incoming frame index number.
MAC Address	This is the MAC address of the device from which this incoming frame came.
VID	This is the VLAN group to which this frame belongs.
Port	This is the port from which the above MAC address was learned. This field displays drop if you configure a filter rule for the MAC address in the Filtering screen.
Туре	This shows whether the MAC address is dynamic (learned by the switch) or static (manually entered in the Static MAC Forwarding screen).

CHAPTER 26 ARP Table

This chapter introduces ARP Table.

26.1 Overview

Address Resolution Protocol (ARP) is a protocol for mapping an Internet Protocol address (IP address) to a physical machine address, also known as a Media Access Control or MAC address, on the local area network.

An IP (version 4) address is 32 bits long. In an Ethernet LAN, MAC addresses are 48 bits long. The ARP Table maintains an association between each MAC address and its corresponding IP address.

26.1.1 How ARP Works

When an incoming packet destined for a host device on a local area network arrives at the switch, the switch's ARP program looks in the ARP Table and, if it finds the address, sends it to the device.

If no entry is found for the IP address, ARP broadcasts the request to all the devices on the LAN. The switch fills in its own MAC and IP address in the sender address fields, and puts the known IP address of the target in the target IP address field. In addition, the switch puts all ones in the target MAC field (FF.FF.FF.FF.FF.FF.FF is the Ethernet broadcast address). The replying device (which is either the IP address of the device being sought or the router that knows the way) replaces the broadcast address with the target's MAC address, swaps the sender and target pairs, and unicasts the answer directly back to the requesting machine. ARP updates the ARP Table for future reference and then sends the packet to the MAC address that replied.

26.2 Viewing the ARP Table

Click **Management**, **ARP Table** in the navigation panel to open the following screen. Use the ARP table to view IP-to-MAC address mapping(s).

Index	IP Address	MAC Address	Туре
1	172.21.0.2	00:05:5d:04:30:f1	dynami
2	172.21.3.16	00:05:1c:15:08:71	dynami
3	172.21.3.19	00:0b:cd:8c:6d:ed	dynami
4	172.21.3.40	00:0c:76:07:41:0d	dynami
5	172.21.3.66	00:50:8d:47:73:4f	dynami
6	172.21.3.90	00:05:5d:f4:49:20	dynami
7	172.21.3.91	00:50:ba:ad:56:7c	dynami
8	172.21.3.95	00:10:b5:ae:56:97	dynami
9	172.21.3.120	00:10:b5:ae:62:32	dynami
10	172.21.3.138	00:a0:c5:b2:62:26	dynami
11	172.21.4.99	00:0c:76:09:cf:88	dynami
12	172.21.10.11	08:00:20:ad:f6:88	dynami
13	172.21.100.153	00:90:27:be:a2:8c	dynami
14	172.21.207.247	00:0c:76:09:17:1a	dynami
15	192.168.1.1	00:a0:c5:3f:91:56	dynami
16	192.168.1.5	00:85:a0:01:01:04	dynami
17	192.168.1.10	00:a0:c5:5e:df:f9	static
18	192.168.1.100	00:85:a0:01:01:00	dynami

Figure 89 AR	RP Table
--------------	----------

The following table describes the labels in this screen.

Table 55 ARP Table

LABEL	DESCRIPTION	
Index	This is the ARP Table entry number.	
IP Address	This is the learned IP address of a device connected to a switch port with corresponding MAC address below.	
MAC Address	This is the MAC address of the device with corresponding IP address above.	
Туре	This shows whether the MAC address is dynamic (learned by the switch) or static (manually entered in the Static MAC Forwarding screen).	

CHAPTER 27 Introducing the Commands

This chapter introduces the commands and gives a summary of commands available.

27.1 Overview

In addition to the web configurator, you can use line commands to configure the switch. Use line commands for advanced switch diagnosis and troubleshooting. If you have problems with your switch, customer support may request that you issue some of these commands to assist them in troubleshooting.

Note: See the web configurator parts of this User's Guide for background information on features configurable by the web configurator.

27.1.1 Switch Configuration File

When you configure the switch using either the CLI (Command Line Interface) or web configurator, the settings are saved as a series of commands in a configuration file on the switch. You can perform the following with a configuration file:

- Back up switch configuration once the switch is set up to work in your network.
- Restore switch configuration.
- Use the same configuration file to set all switches (of the same model) in your network to the same settings.

Note: You may also edit a configuration file using a text editor.

Make sure you use valid commands. The switch rejects configuration files with invalid or incomplete commands.

27.2 Accessing the CLI

You can use a direct console connection or Telnet to access the CLI on the switch.

Note: The switch automatically logs you out of the management interface after five minutes of inactivity. If this happens to you, simply log back in again.

27.2.1 Access Priority

- You can only access the CLI with the administrator account (the default username is **admin** and password is **1234**).
- By default, only one CLI management session is allowed via either the console port or Telnet. Console port access has higher priority.
- Use the configure multi-login command in the configuration mode to allow multiple concurrent logins. However, no more than five concurrent login sessions are allowed.

27.2.2 The Console Port

Connect to the switch's console port using a terminal emulation software configured to the following settings:

- VT100 terminal emulation
- 9600 bps
- No parity
- 8 data bits
- 1 stop bit
- No flow control

27.2.2.1 Initial Screen

When you turn on your switch, it performs several internal tests as well as line initialization. You can view the initialization information using the console port. After the initialization, the login screen displays (refer to Section 27.3 on page 147).

Figure 90 Initial Console Port Screen

```
Copyright (c) 1994 - 2004 ZyXEL Communications Corp.
initialize switch, ethernet address: 00:13:49:1a:d4:fa
ZyXEL ADM5120 10/100 Mbps Ethernet Controller 2002.9.27.0
Press ENTER to continue...
```

27.2.3 Telnet

Use the following steps to telnet into your switch.

- **1** For local management, connect your computer to the RJ-45 management port (labeled **MGMT**) on the switch.
- 2 Make sure your computer IP address and the switch IP address are on the same subnet. In Windows, click Start (usually in the bottom left corner), Run and then type telnet 192.168.1.1 (the default management IP address) and click OK.
- **3** A login screen displays (refer to Section 27.3 on page 147).

27.2.4 SSH

You can use an SSH client program to access the switch. The following figure shows an example using a text-based SSH client program. Refer to the documentation that comes with your SSH program for information on using it.

Figure 91 SSH Login Example

```
C:\>ssh2 admin@192.168.1.1
WARNING: HOST IDENTIFICATION HAS CHANGED!
ß
IT IS POSSIBLE THAT SOMEONE IS DOING SOMETHING NASTY!
Someone could be eavesdropping on you right now (man-in-the-middle attack)!
It is also possible that the host key has just been changed.
Please contact your system administrator.
Add correct host key to "C:/Documents and Settings/Administrator/Application
Data/SSH/hostkeys/key 22 192.168.1.1.pub" to get rid of this message.
Received server key's fingerprint: xigil-gidot-homug-duzab-tocyh-pamyb-
ronep-tisaf-hebip-gokeb-goxix You can get a public key's fingerprint by
running % ssh-keygen -F publickey.pub
on the keyfile. Agent forwarding is disabled to avoid attacks by corrupted
servers. X11 forwarding is disabled to avoid attacks by corrupted servers.
Are you sure you want to continue connecting (yes/no)? yes
Do you want to change the host key on disk (yes/no)? yes
Agent forwarding re-enabled.
X11 forwarding re-enabled.
Host key saved to C:/Documents and Settings/Administrator/Application Data/
SSH/hostkeys/key 22 192.168.1.1.pub host key for 192.168.1.1, accepted by
Administrator Thu May 12 2005 09:52:21
admin's password:
Authentication successful.
Copyright (c) 1994 - 2005 ZyXEL Communications Corp.
ras>
```

27.3 The Login Screen

After you have successfully established a connection to the switch using a direct console connection or Telnet, a login screen displays as shown below. For your first login, enter the default administrator login username "admin" and password "1234".

Figure 92 CLI Login

Enter User Name : admin Enter Password : XXXX

27.4 Command Syntax Conventions

The rules of the commands are listed next.

- The command keywords are in courier new font.
- The required fields in a command are enclosed in angle brackets <>, for instance, ping <ip> means that you must specify an IP number for this command.
- The optional fields in a command are enclosed in square brackets [], for instance,

```
configure snmp-server [contact <system contact>] [location
<system location>]
```

means that the contact and location fields are optional.

- "Command" refers to a command used in the command line interface (CI command).
- The | symbol means "or".
- The entry <cr> in the command lines refers to carriage return. Press [ENTER] or carriage return after a command to execute the command.
- Use the up (\blacklozenge) or down (\blacklozenge) arrow key to scroll through the command history list.
- The CLI does not accept partial or incomplete commands. You may enter a unique part of a command and press [TAB] to have the switch automatically display the full command. For example, if you enter "config" and press [TAB], the full command of "configure" automatically displays.
- Each interface refers to an Ethernet port on the switch. Commands configured after the interface command correspond to those ports.
- Type multiple ports or port ranges separated by a comma. Ranges of port numbers are typed separated by a dash.

27.5 Getting Help

The system includes a help facility to provide you with the following information about the commands:

- List of available commands under a command group.
- Detailed descriptions of the commands.

27.5.1 List of Available Commands

Enter "help" to display a list of available commands and the corresponding sub commands.

Enter "?" to display a list of commands you can use.

Figure 93 CLI Help: List of Commands: Example 1

```
ras> help
 Commands available:
 help
 logout
 exit
 history
 enable
 show ip <cr>
 show hardware-monitor <C|F>
 show system-information
 ping help
 ping <ip|host-name> [vlan <vlan-id>][..]
 ping <ip|host-name> <cr>
 traceroute help
 traceroute <ip|host-name> [vlan <vlan-id>][..]
traceroute <ip|host-name> <cr>
ssh <1|2> <[user@]dest-ip> [command </>]
ssh <1|2> <[user@]dest-ip> <cr>
ras>
```

Figure 94 CLI Help: List of Commands: Example 2

ras> ?	
enable	Turn on privileged commands
exit	Exit from the EXEC
help	Description of the interactive help system
history	Show a list of previously run commands
logout	Exit from the EXEC
ping	Exec ping
show	Show system information
ssh	SSH client
traceroute	Exec traceroute
ras>	

27.5.2 Detailed Command Information

Enter <command> help to display detailed sub command and parameters.

Enter <command> ? to display detailed help information about the sub commands and parameters.

Figure 95 CLI Help: Detailed Command Information: Example 1

Figure 96 CLI: Help: Detailed Command Information: Example 2

ras> ping ?<ip>destination ip addresshelpDescription of ping help

27.6 Command Modes

There are three CLI command modes: User, Enable and Configure.

When you first log into the CLI, the initial command mode is the User mode. The User mode commands are a subset of the Enable mode commands. The User mode command prompt ends with an angle bracket (>).

To enter Enable (or privileged) mode, type enable and enter a password when prompted (the default is 1234). When you enter the Enable mode, the command prompt changes to the pound sign (#).

To enter the configuration mode, type configure or config. The Configure mode command prompt consists of the word "config" and the pound sign (#). There are various sub configuration modes: interface, router and VLAN.

- To enter config-vlan mode, type vlan followed by a number (between 1 to 4094). For example, vlan 10 to configure settings for VLAN 10.
- To enter config-interface mode and configure the ports, enter interface portchannel followed by a port number. For example, interface port-channel 10.

Enter exit or logout to quit from the current mode or log out from the CLI.

27.7 Using Command History

The switch keeps a list of up to 256 commands(s) you have entered for the current CLI session. You can use any commands in the history again by pressing the up (\blacklozenge) or down (\blacklozenge) arrow key to scroll through the previously used commands and press [ENTER]. Use the history command to display the list of commands.

Figure 97 CLI: History Command Example

```
ras> history
  enable
  exit
  show ip
  history
ras>
```

27.8 Saving Your Configuration

After you set the switch settings with the configuration commands, use the write memory command to save the changes permanently.

Figure 98 CLI: write memory

ras# write memory

Note: The write memory command is not available in User mode.

You must save your changes after each CLI session. All unsaved configuration changes are lost once you restart the switch.

27.8.1 Logging Out

In User mode, enter the exit or logout command to log out of the CLI.

27.9 Command Summary

The following sections summarize the commands available in the switch together with a brief description of each command. Commands listed in the tables are in the same order as they are displayed in the CLI. See the related section in the User's Guide for more background information.

27.9.1 User Mode

The following table describes the commands available for User mode.

Table 56	Command	Summary:	User Mode
----------	---------	----------	-----------

COMMAND		DESCRIPTION	
enable		Accesses Enable (or privileged) mode. See Section 27.9.2 on page 152.	
exit		Logs out from the CLI.	
help		Displays help information.	
history		Displays a list of previously command(s) that you have executed. The switch stores up to 256 commands in history.	
logout		Exits from the CLI.	
ping	<ip host-name></ip host-name>	Sends Ping request to an Ethernet device.	
	<ip host-name> [vlan <vlan-id>] [size <0-1472>] [-t]</vlan-id></ip host-name>	Sends Ping request to an Ethernet device in the specified VLAN(s) with the specified parameters.	
	help	Displays command help information.	
show	ip	Displays IP related information.	
	system-information	Displays general system information.	
ssh	<1 2> <[user@]dest-ip>	Connects to an SSH server with the specified SSH version.	
traceroute	<ip host-name></ip host-name>	Determines the path a packet takes to a device.	
	<ip host-name> [vlan <vlan-id>] [ttl <1-255>] [wait <1-60>] [queries <1-10>]</vlan-id></ip host-name>	Determines the path a packet takes to a device in a VLAN.	
	help	Displays command help information.	

27.9.2 Enable Mode

The following table describes the commands available for Enable mode.

	Table 57	Command	Summary:	Enable Mode
--	----------	---------	----------	-------------

COMMAND		DESCRIPTION	
baudrate	<1 2 3 4 5>		Changes the console port speed. Choices are 1 (9600), 2 (19200), 3(38400), 4 (57600) and 5 (115200).
boot	config		Restarts the system.
configure			Accesses Configuration mode. See Section 27.9.3 on page 155.
disable			Exits Enable (or privileged) mode.

COMMAND			DESCRIPTION
enable			Accesses Enable (or privileged) mode.
erase	running-config		Resets to the factory default settings.
exit			Exits Enable (or privileged) mode.
help			Displays help information.
history			Displays a list of command(s) that you have previously executed.
logout			Exits Enable (or privileged) mode.
mac-flush			Clears the MAC address table.
	<port-num></port-num>		Removes all learned MAC address on the specified port(s).
no	arp		Clears the ARP table.
	interface		Clears interface statistics.
	logging		Disables syslog logging.
ping	<ip host-name></ip host-name>		Sends Ping request to an Ethernet device.
		[vlan <vlan- id>][]</vlan- 	Sends Ping request to an Ethernet device in the specified VLAN(s).
	help		Displays command help information.
reload	config		Restarts the system.
show	cluster		Displays cluster management status.
		candidates	Displays cluster candidate information.
		member	Displays the MAC address of the cluster member(s).
		<pre>member mac <mac- addr></mac- </pre>	Displays the status of the cluster member(s).
		members config	Displays the configuration of the cluster member(s).
	diffserv		Displays general DiffServ settings.
	garp		Displays GARP information.
	https		Displays the HTTPS information.
		certificate	Displays the HTTPS certificates.
		key <rsa dsa></rsa dsa>	Displays the HTTPS key.
		session	Displays current HTTPS session(s).
		timeout	Displays the HTTPS session timeout.
	interface <port- number></port- 		Displays current interface status.
	<pre>interfaces config <port-list></port-list></pre>		Displays current interface configuration.
		bandwidth- control	Displays bandwidth control settings.

 Table 57
 Command Summary: Enable Mode (continued)

Table 57	Command Summary: Enable Mode	(continued)
----------	------------------------------	-------------

COMMAND			DESCRIPTION
		bstorm-control	Displays broadcast storm control settings.
		egress	Displays outgoing port information.
	ip		Displays IP related information.
		arp	Displays the ARP table.
		route	Displays IP routing information.
		route static	Displays IP static route information.
	lacp		Displays LACP (Link Aggregation Control Protocol) settings.
	logging		Displays system logs.
	loginPrecedence		Displays login precedence settings.
	logins		Displays login account information.
	mac	address-table <all [mac vid port]></all 	Displays MAC address table. You can sort by MAC address, VID or port.
		address-table static	Displays static MAC address table.
	mac-aging-time		Displays MAC learning aging time.
	multi-login		Displays multi-login information
	plt		DIsplays PLT (Port Loopback Test) information.
	port-access- authenticator		Displays all port authentication settings.
		[port-list]	Displays port authentication settings on the specified port(s).
	port-security		Displays all port security settings.
		[port-list]	Displays port security settings on the specified port(s).
	radius-server		Displays RADIUS server settings.
	remote-management		Displays all secured client information.
		[index]	Displays the specified secured client information.
	running-config		Displays current operating configuration.
	service-control		Displays service control settings.
	snmp-server		Displays SNMP settings.
	spanning-tree	config	Displays Spanning Tree Protocol (STP) settings.
	ssh		Displays general SSH settings.
		key <rsal rsa dsa></rsal rsa dsa>	Displays internal SSH public and private key information.
		known-hosts	Displays known SSH hosts information.

COMMAND			DESCRIPTION
		session	Displays current SSH session(s).
	system-information		Displays general system information.
	time		Displays current system time and date.
	timesync		Displays time server information.
	trunk		Displays link aggregation information.
	vlan		Displays the status of all VLANs.
		<vlan-id></vlan-id>	Displays the status of the specified VLAN.
	vlan-stacking		Displays VLAN stacking settings.
	vlanlq	gvrp	Displays GVRP settings.
		port-isolation	Displays port isolation settings.
ssh	<1 2> <[user@]dest- ip>		Connects to an SSH server with the specified SSH version.
		[command]	Connects to an SSH server with the specified SSH version and addition commands to be executed on the server.
traceroute	<pre><ip host-name> [in- band out-of- band vlan <vlan- id>][ttl <1-255>] [wait <1-60>] [queries <1-10>]</vlan- </ip host-name></pre>		Determines the path a packet takes to a device.
	help		Displays command help information.
write	memory		Saves current configuration to the configuration file the switch is currently using.
		<index></index>	Saves current configuration to the specified configuration file on the switch.

 Table 57
 Command Summary: Enable Mode (continued)

27.9.3 General Configuration Mode

The following table lists the commands in Configuration (or Config) mode.

 Table 58
 Command Summary: Configuration Mode

COMMAND		DESCRIPTION	
admin-password	<pw-string> <confirm-string></confirm-string></pw-string>		Changes the administrator password.
bandwidth- control			Enables bandwidth control.
diffserv			Enables DiffServ.
	dscp <0-63> priority <0-7>		Sets the DSCP-to-IEEE 802.1q mappings.

COMMAND		DESCRIPTION	
exit			Exits from the CLI.
garp	join <100-65535> leave <msec> leaveall <msec></msec></msec>		Configures GARP time settings.
help			Displays help information.
history			Displays a list of previous command(s) that you have executed.
hostname	<name_string></name_string>		Sets the switch's name for identification purposes.
https	cert-regeneration <rsa dsa></rsa dsa>		Re-generates a certificate.
	timeout <0-65535>		Sets the HTTPS timeout period.
igmp-snooping			Enables IGMP snooping.
interface	port-channel <port- list></port- 		Enables a port or a list of ports for configuration. See Section 27.9.4 on page 162 for more details.
ip	name-server	<ip></ip>	Sets the IP address of a domain name server.
	route	<ip> <mask> <next- hop-ip></next- </mask></ip>	Creates a static route.
		<ip> <mask> <next- hop-ip> [metric <metric>] [name <name>] [inactive]</name></metric></next- </mask></ip>	Sets the metric of a static route or deactivates a static route.
lacp			Enables Link Aggregation Control Protocol (LACP).
	system-priority	<1-65535>	Sets the priority of an active port using LACP.
loginPrecedence	<localonly <br="">LocalRADIUS RADIUSOnly></localonly>		Select which database the switch should use (first) to authenticate a user.
logins	username <name> password <pwd></pwd></name>		Configures up to four read-only login accounts.
logout			Exits from the CLI.
mac-aging-time	<10-3000>		Sets learned MAC aging time.
mac-filter	name <name> mac <mac-addr> vlan <vlan-id></vlan-id></mac-addr></name>		Configures a static MAC address port filtering rule.
		inactive	Disables a static MAC address port filtering rule.

Table 58 Command Summary: Configuration Mode (continued)

COMMAND			DESCRIPTION
mac-forward	<pre>name <name> mac <mac-addr> vlan <vlan-id> interface <interface-id></interface-id></vlan-id></mac-addr></name></pre>		Configures a static MAC address forwarding rule.
		inactive	Disables a static MAC address forwarding rule.
mirror-filter	egress	mac <mac-addr></mac-addr>	Sets port mirroring for the MAC address on the outgoing traffic.
		type <all dest src></all dest src>	Sets the direction of the outgoing traffic for port mirroring.
	ingress	mac <mac-addr></mac-addr>	Sets port mirroring for the MAC address on the incoming traffic.
		type <all dest src></all dest src>	Sets the direction of the incoming traffic for port mirroring.
mirror-port			Enables port mirroring.
	<port-num></port-num>		Enables port mirroring on a specified port.
mode	zynos		Changes the CLI mode to the ZyNOS format.
multi-login			Enables multi-login.
no	bandwidth-control		Disable bandwidth control on the switch.
	cluster		Disables cluster management on the switch.
	cluster member	<mac-address></mac-address>	Removes the cluster member.
	diffserv		Disables the DiffServ settings.
	https	timeout	Resets the session timeout to the default of 300 seconds.
	igmp-snooping		Disables IGMP snooping.
	ip		Sets the management IP address to the default value.
		route <ip> <mask></mask></ip>	Removes a specified IP static route.
		route <ip> <mask> inactive</mask></ip>	Enables a specified IP static route.
	lacp		Disables the link aggregation control protocol (dynamic trunking) on the switch.
	logins		Disables login access to the specified name.

 Table 58
 Command Summary: Configuration Mode (continued)

Table 58	Command Summary:	Configuration Mode	(continued)
----------	------------------	--------------------	-------------

COMMAND			DESCRIPTION
	mac-filter	<pre>mac <mac-addr> vlan <vlan-id> drop <src both="" dst=""> inactive</src></vlan-id></mac-addr></pre>	Enables the specified MAC-filter rule.
		<pre>mac <mac-addr> vlan <vlan-id> drop <src both="" dst=""></src></vlan-id></mac-addr></pre>	Disables the specified MAC filter rule.
	mac-forward	<pre>mac <mac-addr> vlan <vlan-id> interface <interface-id></interface-id></vlan-id></mac-addr></pre>	Removes the specified MAC forwarding entry, belonging to a VLAN group (if any) forwarded through an interface(s).
		<pre>mac <mac-addr> vlan <vlan-id> interface <interface-id> inactive</interface-id></vlan-id></mac-addr></pre>	Enables the specified MAC address, belonging to a VLAN group (if any) forwarded through an interface(s).
	mirror-port		Disables port mirroring on the switch.
	multi-login		Disables another administrator from logging into Telnet or the CLI.
	port-access- authenticator		Disables port authentication on the switch.
		<port-list></port-list>	Disables authentication on the listed ports.
		<port-list> reauthenticate</port-list>	Disables the re-authentication mechanism on the listed port(s).
	port-security		Disables port security on the switch.
		<port-list></port-list>	Disables port security on the specified ports.
		<port-list> learn inactive</port-list>	Enables MAC address learning on the specified ports.
	radius-server		Disables the use of authentication from the RADIUS server.
	remote-management	<index></index>	Clears a secure client set entry from the list of secure clients.
		<index> service [telnet][ftp] [http][icmp] [snmp][ssh][https]</index>	Disables a secure client set entry number from using the selected remote management service(s).
	service-control	ftp	Disables FTP access to the switch.
		http	Disables web browser control to the switch.

COMMAND			DESCRIPTION
		https	Disables secure web browser access to the switch.
		icmp	Disables ICMP access to the switch such as pinging and tracerouting.
		snmp	Disables SNMP management.
		ssh	Disables SSH (Secure Shell) server access to the switch.
		telnet	Disables telnet access to the switch.
	snmp-server	trap-destination <ip></ip>	Disables sending of SNMP traps to a station.
	spanning-tree		Disables STP.
		<port-list></port-list>	Disables STP on listed ports.
	ssh	key <rsal rsa dsa></rsal rsa dsa>	Disables the secure shell server encryption key. Your switch supports SSH versions 1 and 2 using RSA and DSA authentication.
		known-hosts	Removes all remote hosts.
		known-hosts <host- ip></host- 	Removes the specified remote hosts from the list of all known hosts.
		known-hosts <host- ip> [1024 ssh- rsa ssh-dsa]</host- 	Removes remote known hosts with the specified public key (1024-bit RSA1, RSA or DSA).
	storm-control		Disables broadcast storm control.
	timesync		Disables timeserver settings.
	trunk	<t1 t2 t3></t1 t2 t3>	Disables the specified trunk group.
		<t1 t2 t3> interface <port- list></port- </t1 t2 t3>	Removes ports from the specified trunk group.
		<t1 t2 t3> lacp</t1 t2 t3>	Disables LACP in the specified trunk group.
	vlan	<vlan-id></vlan-id>	Deletes the static VLAN entry.
	vlanlq	gvrp	Disables GVRP on the switch.
		ingress-check	Disables VLAN tag checking on incoming traffic.
		port-isolation	Disables port isolation.
password			Change the password for Enable mode.
port-access- authenticator			Enables 802.1x authentication on the switch.

Table 58 Command Summary: Configuration Mode (continued)

Table 58 Command Summary: Configuration Mode (continued)

COMMAND			DESCRIPTION
	<port-list></port-list>		Enables 802.1x authentication on the specified port(s).
		reauthenticate	Sets a subscriber to periodically re-enter his or her username and password to stay connected to a specified port.
		reauth-period <reauth-period></reauth-period>	Specifies how often a client has to re-enter the username and password to stay connected to the specified port(s).
port-security			Enables port security on the switch.
	<port-list></port-list>		Enables the port security feature on the specified port(s).
		learn inactive	Disables MAC address learning on the specified port(s).
		address-limit <number></number>	Limits the number of (dynamic) MAC addresses that may be learned on a port.
queue	level <0-7> priority <0-3>		Sets the priority level-to- physical queue mapping.
radius-server	host <ip> [acct- port <socket- number>] [key <key- string>]</key- </socket- </ip>		Sets the IP address and/or the port number and key of the external RADIUS server.
remote- management	<pre><index> start-addr <ip> end-addr <ip> service [telnet][ftp][http][icmp][snmp][ssh] [https]</ip></ip></index></pre>		Specifies a group of trusted computer(s) from which an administrator may use a service to manage the switch.
service-control	ftp <socket-number></socket-number>		Allows FTP access on the specified service port.
	http <socket- number> <timeout></timeout></socket- 		Allows HTTP access on the specified service port and defines the timeout period.
	https <socket- number></socket- 		Allows HTTPS access on the specified service port.
	icmp		Allows ICMP access for services such as Ping.
	snmp		Allows SNMP management.
	ssh <socket-number></socket-number>		Allows SSH access on the specified service port.
	telnet <socket- number></socket- 		Allows Telnet access on the specified service port.
snmp-server	[contact <system contact>] [location <system location="">]</system></system 		Sets the geographic location and the name of the person in charge of this switch.

COMMAND		DESCRIPTION
	get-community <property></property>	Sets the get community.
	set-community <property></property>	Sets the set community.
	trap-community <property></property>	Sets the trap community.
	trap-destination <ip></ip>	Sets the IP addresses of up to four stations to send your SNMP traps to.
spanning-tree		Enables STP on the switch.
	<port-list></port-list>	Enables STP on a specified port.
	<port-list> path- cost <1-65535></port-list>	Sets the STP path cost for a specified port.
	<port-list> priority <0-255></port-list>	Sets the priority for a specified port.
	hello-time <1-10> maximum-age <6-40> forward-delay <4- 30>	Sets Hello Time, Maximum Age and Forward Delay.
	help	Displays help information.
	priority <0-61440>	Sets the bridge priority of the switch.
spq		Sets the switch to use Strictly Priority Queuing (SPQ).
ssh	known-hosts <host- ip> <1024 ssh- rsa ssh-dsa> <key></key></host- 	Adds a remote host to which the switch can access using SSH service.
storm-control		Enables broadcast storm control on the switch.
time	<hour:min:sec></hour:min:sec>	Sets the time in hour, minute and second format.
	date <month <br="" day="">year></month>	Sets the date in year, month and day format.
	help	Displays help information.
	timezone <- 1200 1200>	Selects the time difference between UTC (formerly known as GMT) and your time zone.
timesync	<daytime time ntp></daytime time ntp>	Sets the time server protocol.
	server <ip></ip>	Sets the IP address of your time server.
trunk	<t1 t2 t3></t1 t2 t3>	Activates a trunk group.
	<t1 t2 t3>interface <port-list></port-list></t1 t2 t3>	Adds a port(s) to the specified trunk group.

Table 58	Command Summary	: Configuration Mode	(continued)
Table 50	Command Summary		(continueu)

COMMAND		DESCRIPTION	
	<t1 t2 t3>lacp</t1 t2 t3>		Enables LACP for a trunk group.
	<pre>interface <port- list> timeout <lacp-timeout></lacp-timeout></port- </pre>		Defines the port number and LACP timeout period.
vlan	<1-4094>		Enters the VLAN configuration mode. See Section 27.9.5 on page 164 for more information.
vlan-type	<802.1q port-based>		Specifies the VLAN type.
vlan1q	gvrp		Enables GVRP.
	ingress-check		Enables VLAN tag checking on incoming traffic.
	port-isolation		Enables port-isolation.
wrr			Sets the switch to use Weighted Round Robin queuing (WRR).
		<wt1 wt4=""></wt1>	Sets the WRR weight. A weight value of one to eight is given to each variable from wt1 to wt4.

 Table 58
 Command Summary: Configuration Mode (continued)

27.9.4 interface port-channel Commands

The following table lists the interface port-channel commands in configuration mode. Use these commands to configure the ports.

Table 59 interface port-channel Commands

COMMAND		DESCRIPTION	
interface port-channel <port-list></port-list>			Enables a port or a list of ports for configuration.
	bandwidth-limit		Enables bandwidth control on the port(s).
		egress <kbps></kbps>	Sets the maximum bandwidth allowed for outgoing traffic on the port(s).
		ingress <kbps></kbps>	Sets the maximum bandwidth allowed for incoming traffic on the port(s).
	bmstorm-limit		Enables broadcast storm control on the port.
		<kpbs></kpbs>	Sets the limit of broadcast storm packets in kilobit per second (Kbps).
	diffserv		Enables DiffServ on the port(s).

COMMAND			DESCRIPTION
	egress set <port- list></port- 		Sets the outgoing traffic port list for a port-based VLAN.
	exit		Exits from the interface port- channel command mode.
	flow-control		Enables interface flow control. Flow control regulates transmissions to match the bandwidth of the receiving port.
	frame-type <all tagged></all tagged>		Choose to accept both tagged and untagged incoming frames or just tagged incoming frames on a port.
	gvrp		Enables this function to permit VLAN groups beyond the local switch.
	help		Displays a description of the interface port-channel commands.
	inactive		Disables the specified port(s) on the switch.
	mirror		Enables port mirroring in the interface.
		dir <ingress egress bo th></ingress egress bo 	Enables port mirroring for incoming, outgoing or both incoming and outgoing traffic. Port mirroring copies traffic from one or all ports to another or all ports for external analysis.
	name <port-name- string></port-name- 		Sets a name for the port(s). Enter a descriptive name (up to nine printable ASCII characters).
	no	bandwidth-limit	Disables bandwidth limit on the port(s).
		bmstorm-limit	Disables broadcast storm control limit on the port(s).
		diffserv	Disables DiffServ on the port(s).
		egress set	Disables outgoing traffic on the port for port-based VLAN.
		flow-control	Disables flow control on the port(s).
		gvrp	Disable GVRP on the port(s).
		inactive	Enables the port(s) on the switch.
		mirror	Disables port mirroring on the port(s).
		vlan-trunking	Disables VLAN trunking on the port(s).

Table 59 interface port-channel Commands (continued)

COMMAND			DESCRIPTION
	pvid <1-4094>		The default PVID is VLAN 1 for all ports. Sets a PVID in the range 1 to 4094 for the specified interface.
	qos priority	<0 7>	Sets the quality of service priority for an interface.
	speed-duplex	<auto 10-half 10- full 100-half 100- full 1000-full></auto 10-half 10- 	Sets the duplex mode (half or full) and speed (10, 100 or 1000 Mbps) of the connection on the interface. Selecting auto (auto-negotiation) makes one port able to negotiate with a peer automatically to obtain the connection speed and duplex mode that both ends support.
	test		Performs an interface loopback test.
	vlan-trunking		Enables VLAN Trunking on ports connected to other switches or routers (but not ports directly connected to end users) to allow frames belonging to unknown VLAN groups to pass through the switch.

Table 59 interface port-channel Commands (continued)

27.9.5 config-vlan Commands

The following table lists the vlan commands in configuration mode.

 Table 60
 Command Summary: config-vlan Commands

COMMAND		DESCRIPTION	
vlan<1-4094>			Creates a new VLAN group.
	exit		Leaves the VLAN configuration mode.
	fixed <port-list></port-list>		Specifies the port(s) to be a permanent member of this VLAN group.
	forbidden <port- list></port- 		Specifies the port(s) you want to prohibit from joining this VLAN group.
	help		Displays a list of available VLAN commands.
	inactive		Disables the specified VLAN.
	ip address	<ip-address> <mask></mask></ip-address>	Sets the IP address and subnet mask of the switch in the specified VLAN.
		<ip-address> <mask> [manageable]</mask></ip-address>	Sets the management IP address and subnet mask of the switch in the specified VLAN.

COMMAND			DESCRIPTION
		default-gateway <ip-address></ip-address>	Sets a default gateway IP address for this VLAN.
		default- management dhcp- bootp	Sets the dynamic in-band IP address
		default- management <ip- address> <mask></mask></ip- 	Sets a static in-band IP address and subnet mask.
		default- management dhcp- bootp release	Releases the dynamic in-band IP address.
		default- management dhcp- bootp renew	Updates the dynamic in-band IP address.
	name <name-str></name-str>		Specifies a name for identification purposes.
	no	fixed <port-list></port-list>	Sets fixed port(s) to normal port(s).
		forbidden <port- list></port- 	Sets forbidden port(s) to normal port(s).
		inactive	Enables the specified VLAN.
		ip address <ip- address> <mask></mask></ip- 	Deletes the IP address and subnet mask from this VLAN.
		ip address default-gateway	Deletes the default gateway from this VLAN.
		ip address default- management dhcp- bootp	Sets the default in-band interface to use a static IP address in this VLAN. The switch will use the default IP address of 0.0.0.0 if you do not configure a static IP address.
		untagged <port- list></port- 	Enables VLAN tagging for outgoing traffic on the specified port(s).
	normal <port- list></port- 		Specifies the port(s) to dynamically join this VLAN group using GVRP
	untagged <port- list></port- 		Specifies the port(s) you don't want to tag all outgoing frames transmitted with this VLAN Group ID.

Table 60 Command Summary: config-vlan Commands (continued)

CHAPTER 28 Command Examples

This chapter describes some commands in more detail.

28.1 Overview

These are commands that you may use frequently in maintaining your switch.

28.2 show Commands

These are the commonly used show commands.

28.2.1 show system-information

Syntax:

show system-information

This command shows the general system information (such as the firmware version and system up time).

An example is shown next.

Figure 99 show system-information Command Example

```
ras> show system-information
System Name : ES-2024A
System Contact :
System Location :
Ethernet Address : 00:13:49:1a:d4:fa
ZyNOS F/W Version : V3.60(TX.0) | 04/22/2005
RomRasSize : 1816320
System up Time : 0:59:37 (5757d ticks)
Bootbase Version : V1.07 | 04/20/2005
ras>
```

28.2.2 show ip

Syntax:

show ip

This command displays the IP related information (such as IP address and subnet mask) on all switch interfaces.

The following figure shows the default interface settings.

Figure 100 show ip Command Example

28.2.3 show logging

Note: This command is not available in User mode.

Syntax:

show logging

This command displays the system logs. The following figure shows an example.

Figure 101 show logging Command Example

ras#	show logg	ng	
	0 Thu Ja	1 00:00:11 1970 PP2b INFO adjtime task pause 1 day	
7	Thu Jan	01:06:26 1970 PP23 ERROR ospfReadConf: can't get spOSPFArea_t	
10	Thu Jan	01:06:38 1970 PP23 ERROR ospfReadConf: can't get spOSPFArea_t	
13	Thu Jan	01:06:50 1970 PP23 ERROR ospfReadConf: can't get spOSPFArea_t	
16	Thu Jan	01:07:05 1970 PP23 ERROR ospfReadConf: can't get spOSPFArea_t	
20	Thu Jan	00:00:04 1970 PPOc -WARN SNMP TRAP 3: link up	
21	Thu Jan	00:00:06 1970 PINI -WARN SNMP TRAP 1: warm start	
22	Thu Jan	00:00:06 1970 PINI -WARN SNMP TRAP 3: link up	
22	Thu Jan	00:00:06 1970 PINI -WARN SNMP TRAP 3: link up	
24	Thu Jan	00:00:07 1970 PP23 ERROR ospfReadConf: can't get spOSPFArea_t	
25	Thu Jan	00:00:11 1970 PP2b INFO adjtime task pause 1 day	
30	Thu Jan	00:00:04 1970 PPOc -WARN SNMP TRAP 3: link up	
31	Thu Jan	00:00:06 1970 PINI -WARN SNMP TRAP 1: warm start	
32	Thu Jan	00:00:06 1970 PINI -WARN SNMP TRAP 3: link up	
Clea	r Error Lo	(y/n):	

Note: If you clear a log (by entering y at the Clear Error Log (y/n):prompt), you cannot view it again.

28.2.4 show interface

Syntax:

```
show interface [port-number]
```

This command displays statistics of a port. The following example shows that port 2 is up and the related information.

Figure 102 show interface Command Example

ras# show inter	face 2	
Port Info	Port NO.	:2
	Link	:100M/F
	Status	:FORWARDING
	LACP	:Disabled
	TxPkts	:1744
	RxPkts	:12
	Errors	:0
	Tx KBs/s	:0.64
	Rx KBs/s	:0.0
	Up Time	:1:00:40
TX Packet	Tx Packets	:1744
	Multicast	:1744
	Broadcast	:0
	Pause	:0
RX Packet	Rx Packets	:12
	Multicast	:12
	Broadcast	:0
	Pause	:0
TX Collison	Single	:0
	Multiple	:0
	Excessive	:0
	Late	:0
Error Packet	RX CRC	:0
	Runt	:0
Distribution	64	:12
	65 to 127	:0
	128 to 255	:0
	256 to 511	:0
	512 to 1023	:0
	1024 to 1518	:0
	Giant	:0
ras#		

28.2.5 show mac address-table

Syntax:

show mac address-table <all <sort>|static>

Where

<sort> = Specifies the sorting criteria (MAC, VID or port).

This command displays the MAC address(es) stored in the switch. The following example shows the MAC address table.

Figure 103 show mac address-table Command Example

ras# show mac address-table all
Port VLAN ID MAC Address Type
2 1 00:85:a0:01:01:04 Dynamic
ras#

28.3 ping

Syntax:

ping <ip> < [vlan <vlan-id>] [size <0-8024>] [-t]>

where

<ip></ip>	=	The IP address of an Ethernet device.
[vlan <vlan-id>]</vlan-id>	=	Specifies the VLAN ID to which the Ethernet device belongs.
[size <0-8024>]	=	Specifies the packet size to send.
[-t]	=	Sends Ping packets to the Ethernet device indefinitely. Click [CTRL] + C to terminate the Ping process.

This command sends Ping packets to an Ethernet device. The following example sends Ping requests to and displays the replies from an Ethernet device with an IP address of 192.168.1.100.

Figure 104 ping Command Example

ras# p	ing 19	2.168.1	L.100					
sent	rcvd	rate	rtt	avg	mdev	max	min	reply from
1	1	100	0	0	0	0	0	192.168.1.100
2	2	100	0	0	0	0	0	192.168.1.100
3	3	100	0	0	0	0	0	192.168.1.100
ras#								

28.4 traceroute

Syntax:

traceroute <ip> [vlan <vlan-id>][ttl <1-255>] [wait <1-60>]
[queries <1-10>]

where

<ip></ip>	=	The IP address of an Ethernet device.
[vlan <vlan-id>]</vlan-id>	=	Specifies the VLAN ID to which the Ethernet device belongs.
[ttl <1-255>]	=	Specifies the Time To Live (TTL) period.
[wait <1-60>]	=	Specifies the time period to wait.
[quesries <1-10>]	=	Specifies how many tries the switch performs the traceroute function.

This command displays information about the route to an Ethernet device. The following example displays route information to an Ethernet device with an IP address of 192.168.1.100.

Figure 105 traceroute Command Example

```
ras> traceroute 192.168.1.100
traceroute to 192.168.1.100, 30 hops max, 40 byte packet
1:192.168.1.100 (10 ms) (10 ms) (0 ms)
traceroute done:
```

28.5 Enabling RSTP

To enable RSTP on a port. Enter spanning-tree followed by the port number and press [ENTER].

The following example enables RSTP on port 10.

Figure 106 Enable RSTP Command Example

```
ras(config)# spanning-tree 10
ras#
```

28.6 Configuration File Maintenance

The following sections shows how to manage the configuration files.

28.6.1 Restarting the Switch

There are two ways in which you can restart the switch: restart the switch (cold reboot) and restart the system (warm reboot).

Use the boot config command to restart the switch. The following figure shows an example.

Figure 107 CLI: boot config Command Example

ras# boot config

Use the reload config command to restart the system. The following figure shows an example.

Figure 108 CLI: reload config Command Example

```
ras# reload config
```

28.6.2 Resetting to the Factory Default

Follow the steps below to reset the switch back to the factory defaults.

- 1 Enter erase running config to reset the current running configuration.
- **2** Enter write memory to save the changes to the configuration file.

The following example resets the configuration file to the factory default settings.

Figure 109 CLI: Reset to the Factory Default Example

```
ras# erase running-config
ras# write memory
```

28.7 no Command Examples

These are the commonly used command examples that belong to the no group of commands.

28.7.1 no mirror-port

Syntax:

no mirror-port

Disables port mirroring on the switch.

An example is shown next.

Figure 110 no mirror-port Command Example

ras(config) # no mirror-port

28.7.2 no https timeout

Syntax:

no https timeout

Resets the https session timeout to default.

An example is shown next. The session timeout is reset to 300 seconds.

Figure 111 no https timeout Command Example

```
ras(config) # no https timeout
Cache timeout 300
```

28.7.3 no trunk

Syntax:

```
no trunk <T1|T2|T3
no trunk <T1|T2|T3> lacp
no trunk <T1|T2|T3> interface <port-list>
```

where

```
<T1|T2|T3> Disables the trunk group.

<T1|T2|T3> lacp Disables LACP in the trunk group.

<T1|T2|T3> interface <port-

list> Removes ports from the trunk group.
```

- An example is shown next.
- Disable trunk one (T1).
- Disable LAPC on trunk three (T3).
- Remove ports one, three, four and five from trunk two (T2).

Figure 112 no trunk Command Example

```
ras(config)# no trunk T1
ras(config)# no trunk T3 lacp
ras(config)# no trunk T2 interface 1,3-5
```

28.7.4 no port-access-authenticator

Syntax:

```
no port-access-authenticator
no port-access-authenticator <port-list> reauthenticate
no port-access-authenticator <port-list>
```

where

	= Disables port authentication on the switch.
<port-list> reauthenticate</port-list>	= Disables the re-authentication mechanism on the listed port(s).
<port-list></port-list>	= Disables authentication on the listed ports.

An example is shown next.

- Disable authentication on the switch.
- Disable re-authentication on ports one, three, four and five.
- Disable authentication on ports one, six and seven.

Figure 113 no port-access-authenticator Command Example

```
ras(config) # no port-access-authenticator
ras(config) # no port-access-authenticator 1,3-5 reauthenticate
ras(config) # no port-access-authenticator 1,6-7
```

28.7.5 no ssh

Syntax:

```
no ssh key <rsal|rsa|dsa>
no ssh known-hosts <host-ip>
no ssh known-hosts <host-ip> [1024|ssh-rsa|ssh-dsa]
```

where

key <rsal rsa dsa></rsal rsa dsa>	Disables the secure shell server encryption key. Your switch
	supports SSH versions 1 and 2 using RSA and DSA
	authentication.

known-hosts <host-ip>Remove specific remote hosts from the list of all known hosts.known-hosts <host-ip>Remove remote known hosts with a specified public key (1024-
bit RSA1, RSA or DSA).

An example is shown next.

- Disable the secure shell RSA1 encryption key.
- Remove the remote host with IP address 172.165.1.8 from the list of known hosts.
- Remove the remote host with IP address 172.165.1.9 and with an SSH-RSA encryption key from the list of known hosts.

Figure 114 no ssh Command Example

```
ras(config)# no ssh key rsal
ras(config)# no ssh known-hosts 172.165.1.8
ras(config)# no ssh known-hosts 172.165.1.9 ssh-rsa
```

28.8 spq

Syntax:

spq

Activates Strict Priority Queuing (SPQ). An example is shown next.

Figure 115 spq Command Example

ras(config)# spq

28.9 wrr

Syntax:

wrr <wt1> <wt2> <wt3><wt4>

where

Enables WRR (Weighted Round Robin) queuing method on the switch.

<wt1> ... <wt4> Sets the interface to use WRR queuing. A weight value of one to eight is
given to each variable from wt1 to wt4.

The following example sets the switch to use WRR queuing and sets the queue weights for Q0 to Q3.

Figure 116 wrr Command Example

```
ras# configure
ras(config)# wrr
ras(config)# wrr 4 3 2 1
```

28.10 interface Commands

These are some commonly used commands that belong to the interface group of commands.

28.10.1 interface port-channel

Syntax:

interface port-channel <port-list>

Use this command to enable the specified ports for configuration. Type multiple ports or port ranges separated by a comma. Ranges of port numbers are typed separated by a dash.

An example is shown next.

- Enter the configuration mode.
- Enable ports one, three, four and five for configuration.
- Begin configuring for those ports.

Figure 117 interface Command Example

```
ras# config
ras(config)# interface port-channel 1,3-5
ras(config-interface)#
```

28.10.2 bmstorm-limit

Syntax:

```
bmstorm-limit <Kbps>
```

where

<

<kbps></kbps>	I invite has a deast as alest traffic the interface receives and
<rups></rups>	Limits broadcast packet traffic the interface receives per second.

Enables broadcast storm control limit on the switch.

An example is shown next.

- Enable port one for configuration.
- Enable broadcast control.
- Set the broadband packet traffic the interface receives per second.

Figure 118 broadcast-limit Command Example

```
ras(config)# interface port-channel 1
ras(config-interface)# bmstorm-limit
ras(config-interface)# bmstorm-limit 21
```

28.10.3 bandwidth-limit

Syntax:

```
bandwidth-limit
bandwidth-limit egress <Kbps>
bandwidth-limit ingress <Kbps>
```

where

Enables bandwidth control on the switch.

<Mbps> Sets the maximum bandwidth allowed for outgoing traffic (egress) or incoming traffic (ingress) on the switch.

An example is shown next.

- Enable port one for configuration.
- Enable bandwidth control.
- Set the outgoing traffic bandwidth limit to 70Kbps.
- Set the incoming traffic bandwidth limit to 90Kbps.

Figure 119 bandwidth-limit Command Example

```
ras(config)# interface port-channel 1
ras(config-interface)# bandwidth-limit
ras(config-interface)# bandwidth-limit egress 70
ras(config-interface)# bandwidth-limit ingress 90
```

28.10.4 mirror

Syntax:

mirror
mirror dir <ingress|egress|both>

where

		Enables port mirroring on the interface.
<ingress egress both></ingress egress both>	=	Enables port mirroring for incoming, outgoing or both incoming and outgoing traffic.
		Port mirroring copies traffic from one or all ports to another or all ports for external analysis.

An example is shown next.

- Enable port mirroring.
- Enable the monitor port three.
- Enable ports one, four, five and six for configuration.
- Enable port mirroring on the ports.
- Enable port mirroring for outgoing traffic. Traffic is copied from ports one, four, five and six to port three in order to examine it in more detail without interfering with the traffic flow on the original port(s).

Figure 120 mirror Command Example

```
ras(config)# mirror-port
ras(config)# mirror-port 3
ras(config)# interface port-channel 1,4-6
ras(config-interface)# mirror
ras(config-interface)# mirror dir egress
```

28.10.5 gvrp

Syntax:

gvrp

GVRP (GARP VLAN Registration Protocol) is a registration protocol that defines a way for switches to register necessary VLAN members on ports across the network. Enable this function to permit VLANs groups beyond the local switch.

An example is shown next.

- Enable the IEEE 802.1Q tagged VLAN command to configure tagged VLAN for the switch.
- Enable ports one, three, four and five for configuration.
- Enable GVRP on the interface.

Figure 121 gvrp Command Example

```
ras(config)# vlan1q gvrp
ras(config)# interface port-channel 1,3-5
ras(config-interface)# gvrp
```

28.10.6 frame-type

Syntax:

frame-type <all|tagged>

where

<all | tagged> Choose to accept both tagged and untagged incoming frames or just tagged incoming frames on a port.

An example is shown next.

- Enable ports one, three, four and five for configuration.
- Enable ingress checking on the ports.
- Enable tagged frame-types on the interface.

Figure 122 frame-type Command Example

```
ras(config)# interface port-channel 1,3-5
ras(config-interface)# ingress-check
ras(config-interface)# frame-type tagged
```

28.10.7 egress set

Syntax:

egress set <port-list>

where

<port-list> Sets the outgoing traffic port list for a port-based VLAN.

An example is shown next.

- Enable port-based VLAN tagging on the switch.
- Enable ports one, three, four and five for configuration.
- Set the outgoing traffic ports as the CPU (0), seven (7), eight (8) and nine (9).

Figure 123 egress set Command Example

```
ras(config)# vlan-type port-based
ras(config)# interface port-channel 1,3-5
ras(config-interface)# egress set 0,7-9
```

28.10.8 qos priority

Syntax:

qos priority <0 .. 7>

where

<0 ... 7> Sets the quality of service priority for a port.

An example is shown next.

- Enable ports one, three, four and five for configuration.
- Set the IEEE 802.1p quality of service priority as four (4).

Figure 124 qos priority Command Example

```
ras(config)# interface port-channel 1,3-5
ras(config-interface)# gos priority 4
```

28.10.9 name

Syntax:

name <port-name-string>

where

<port-name-string> Sets a name for your port interface(s).

An example is shown next.

- Enable ports one, three, four and five for configuration.
- Set a name for the ports.

Figure 125 name Command Example

```
ras(config)# interface port-channel 1,3-5
ras(config-interface)# name Test
```

28.10.10 speed-duplex

Syntax:

```
speed-duplex <auto|10-half|10-full|100-half|100-full|1000-full>
```

where

```
<auto|10-half|10-
full|100-half|100-
full|100-full>
Sets the duplex mode (half or full) and speed (10, 100 or 1000 Mbps)
of the connection on the port. Selecting auto (auto-negotiation)
makes one port able to negotiate with a peer automatically to obtain
the connection speed and duplex mode that both ends support.
```

An example is shown next.

- Enable ports one, three, four and five for configuration.
- Set the speed to 10 Mbps in half duplex mode.

Figure 126 speed-duplex Command Example

```
ras(config)# interface port-channel 1,3-5
ras(config-interface)# speed-duplex 10-half
```

CHAPTER 29 IEEE 802.1Q Tagged VLAN Commands

This chapter describes the IEEE 802.1Q Tagged VLAN and associated commands.

29.1 IEEE 802.1Q Tagged VLAN Overview

See the VLAN chapter for more information on VLANs. There are two kinds of tagging:

1 Explicit Tagging

A VLAN identifier is added to the frame header that identifies the source VLAN.

2 Implicit Tagging

The MAC (Media Access Control) number, the port or other information is used to identify the source of a VLAN frame.

The IEEE 802.1Q Tagged VLAN uses both explicit and implicit tagging.

Whether to tag an outgoing frame depends on the setting of the egress port on a per-LAN, perport basis (recall that a port can belong to multiple VLANs). If the tagging on the egress port is enabled for the VID of a frame, then the frame is transmitted as a tagged frame; otherwise, it is transmitted as an untagged frame.

29.2 VLAN Databases

A VLAN database stores and organizes VLAN registration information useful for switching frames to and from a switch. A VLAN database consists of a static entries (Static VLAN or SVLAN table) and dynamic entries (Dynamic VLAN or DVLAN table).

29.2.1 Static Entries (SVLAN Table)

Static entry registration information is added, modified and removed by administrators only.

29.2.2 Dynamic Entries (DVLAN Table)

Dynamic entries are learned by the switch and cannot be created or updated by administrators. The switch learns this information by observing what port, source address and VLAN ID (or VID) is associated with a frame. Entries are added and deleted using GARP VLAN Registration Protocol (GVRP), where GARP is the Generic Attribute Registration Protocol.

29.3 Configuring Tagged VLAN

The following procedure shows you how to configure tagged VLAN.

- **1** Use the IEEE 802.1Q tagged VLAN commands to configure tagged VLAN for the switch.
- Use the vlan <vlan-id> command to configure or create a VLAN on the switch. The switch automatically enters the config-vlan mode.Use the inactive command to deactivate the VLAN(s).
- Use the interface port-channel <port-list> command to enter the configinterface mode to set the VLAN settings on a port, then use the pvid <vlan-id> command to set the VLAN ID you created for the port-list to that specific port in the PVID table.
- Use the exit command when you are finished configuring the VLAN.

Example:

Figure 127 Tagged VLAN Configuration and Activation Example

```
ras (config) # vlan 2000
ras (config-vlan) # name up1
ras (config-vlan) # fixed 10-12
ras (config-vlan) # no untagged 10-12
ras (config-vlan) # exit
ras (config) # interface port-channel 10-12
ras (config-interface) # pvid 2000
ras (config-interface) # exit
```

2 Configure your management VLAN.

- Use the vlan <vlan-id> command to create a VLAN (VID 3 in this example) for managing the switch, and the switch will activate the new management VLAN.
- Use the inactive command to disable the new management VLAN.

Example:

Figure 128 CPU VLAN Configuration and Activation Example

```
ras (config)# vlan 3
ras (config-vlan)# inactive
```

29.4 Global VLAN1Q Tagged VLAN Configuration Commands

This section shows you how to configure and monitor the IEEE 802.1Q Tagged VLAN.

29.4.1 GARP Status

Syntax:

show garp

This command shows the switch's GARP timer settings, including the join, leave and leave all timers.

An example is shown next.

Figure 129 GARP STATUS Command Example

```
ras # show garp
GARP Timer
Join Timer = 200
Leave Timer = 600
Leave All Timer = 10000
ras#
```

29.4.2 GARP Timer

Syntax:

garp join <msec> leave <msec> leaveall <msec>

where

join <msec> = This sets the duration of the Join Period timer for GVRP in milliseconds. Each port has a Join Period timer. The allowed Join Time range is between 100 and 32767 milliseconds; the default is 200 milliseconds.

leave <msec></msec>	=	This sets the duration of the Leave Period timer for GVRP in milliseconds. Each port has a single Leave Period timer. Leave Time must be two times larger than Join Timer; the default is 600 milliseconds.
leaveall <msec></msec>	=	This sets the duration of the Leave All Period timer for GVRP in milliseconds. Each port has a single Leave All Period timer. Leave All Timer must be larger than Leave Timer; the default is 10000 milliseconds.

This command sets the switch's GARP timer settings, including the join, leave and leave all timers.

Switches join VLANs by making a declaration. A declaration is made by issuing a Join message using GARP. Declarations are withdrawn by issuing a Leave message. A Leave All message terminates all registrations. GARP timers set declaration timeout values.

The following example sets the Join Timer to 300 milliseconds, the Leave Timer to 800 milliseconds and the Leave All Timer to 11000 milliseconds.

Figure 130 GARP Timer Command Example

ras (config)# garp join 300 leave 800 leaveall 11000

29.4.3 GVRP Timer

Syntax:

show vlan1q gvrp

This command shows the switch's GVRP settings.

An example is shown next.

Figure 131 GVRP Status Command Example

```
ras # show vlan1q gvrp
GVRP Support
gvrpEnable = YES
GVRP Support
```

29.4.4 Enable GVRP

Syntax:

vlan1q gvrp

This command turns on GVRP in order to propagate VLAN information beyond the switch.

29.4.5 Disable GVRP

Syntax:

no vlanlq gvrp

This command turns off GVRP so that the switch does not propagate VLAN information to other switches.

29.4.6 Enable Ingress Checking

Syntax:

ingress-check

Enables the device to discard incoming frames for VLANs that are not included in a port member set.

The following example activates ingress checking on the switch.

Figure 132 ingress-check Command Example

ras(config)# vlan1q ingress-check

29.5 Port VLAN Commands

You must configure the switch port VLAN settings in config-interface mode.

29.5.1 Set Port VID

Syntax:

pvid <VID>

where

<VID> = Specifies the VLAN number between 1 and 4094

This command sets the default VLAN ID on the port(s).

The following example sets the default VID to 200 on ports 1 to 5.

Figure 133 vlan1q port default vid Command Example

```
ras (config)# interface port-channel 1-5
ras (config-interface)# pvid 200
```

29.5.2 Set Acceptable Frame Type

Syntax:

frame-type <all|tagged>

where

<all|tagged> = Specifies all Ethernet frames (tagged and untagged) or only tagged
Ethernet frames.

This command sets the specified port to accept all Ethernet frames or only those with an IEEE 802.1Q VLAN tag.

The following example sets ports 1 to 5 to accept only tagged frames.

Figure 134 frame type Command Example

```
ras (config)# interface port-channel 1-5
ras (config-interface)# frame-type tagged
```

29.5.3 Enable or Disable Port GVRP

Use the gvrp command to enable GVRP on the port(s). Use the no gvrp command to disable GVRP.

The following example turns off GVRP for ports 1 to 5.

Figure 135 no gvrp Command Example

```
ras (config)# interface port-channel 1-5
ras (config-interface)# no gvrp
```

29.5.4 Modify Static VLAN

Use the following commands in the config-vlan mode to configure the static VLAN table.

Syntax:

```
vlan <vlan-id>
fixed <port-list>
forbidden <port-list>
name <name-str>
normal <port-list>
untagged <port-list>
no fixed <port-list>
no forbidden <port-list>
no forbidden <port-list>
no untagged <port-list>
```

where

```
<vlan-id> = The VLAN ID [1-4094].
<name-str> = A name to identify the SVLAN entry.
<port-list> = This is the switch port list.
```

- Enter fixed to register the <port-list> to the static VLAN table with <vlan-id>.
- Enter normal to confirm registration of the <port-list> to the static VLAN table with <vlan-id>.
- Enter forbidden to block a <port-list> from joining the static VLAN table with <vlan-id>.
- Enter no fixed or no forbidden to change <port-list> to normal status.
- Enter untagged to send outgoing frames without a tag.
- Enter no untagged to tag outgoing frames.

29.5.4.1 Modify a Static VLAN Table Example

The following example configures ports 1 to 5 as fixed and untagged ports in VLAN 2000.

Figure 136 Modifying Static VLAN Example

```
ras (config)# vlan 2000
ras (config-vlan)# fixed 1-5
ras (config-vlan)# untagged 1-5
```

29.5.4.2 Forwarding Process Example

Tagged Frames

- **1** First the switch checks the VLAN ID (VID) of tagged frames or assigns temporary VIDs to untagged frames.
- **2** The switch then checks the VID in a frame's tag against the SVLAN table.
- **3** The switch notes what the SVLAN table says (that is, the SVLAN tells the switch whether or not to forward a frame and if the forwarded frames should have tags).

4 Then the switch applies the port filter to finish the forwarding decision. This means that frames may be dropped even if the SVLAN says to forward them. Frames might also be dropped if they are sent to a CPE (customer premises equipment) DSL device that does not accept tagged frames.

Untagged Frames

- **1** An untagged frame comes in from the LAN.
- **2** The switch checks the PVID table and assigns a temporary VID of 1.
- **3** The switch ignores the port from which the frame came, because the switch does not send a frame to the port from which it came. The switch also does not forward frames to "forbidden" ports.
- **4** If after looking at the SVLAN, the switch does not have any ports to which it will send the frame, it won't check the port filter.

29.5.5 Delete VLAN ID

Syntax:

no vlan <vlan-id>

where

 $\langle vlan-id \rangle$ = The VLAN ID [1-4094].

This command deletes the specified VLAN ID entry from the static VLAN table. The following example deletes entry 2 in the static VLAN table.

Figure 137 no vlan Command Example

```
ras (config)# no vlan 2
```

29.6 Enable VLAN

Syntax:

vlan <vlan-id>

This command enables the specified VLAN ID in the SVLAN (Static VLAN) table.

29.7 Disable VLAN

Syntax:

vlan <vlan-id>
inactive

This command disables the specified VLAN ID in the SVLAN (Static VLAN) table.

29.8 Show VLAN Setting

Syntax:

show vlan

This command shows the IEEE 802.1Q Tagged SVLAN (Static VLAN) table.

An example is shown next.

- For the AdCtl section of the last column, "-" is a port set to normal, "x" is a forbidden port and "F" is a fixed port.
- For the TagCtl section of the last column, "T" is a tagged port, "U" is an untagged port.

Figure 138 show vlan Command Example

CHAPTER 30 Troubleshooting

This chapter covers potential problems and possible remedies.

30.1 Problems Starting Up the Switch

Table 61	Troubleshooting	the Start-Up	of Your Switch
----------	-----------------	--------------	----------------

PROBLEM	CORRECTIVE ACTION
	Check the power connection and make sure the power source is turned on.
turn on when you turn on the switch.	If the error persists, you may have a hardware problem. In this case, you should contact your vendor.

30.2 Problems Accessing the Switch

PROBLEM	CORRECTIVE ACTION
I cannot access the switch using Telnet.	Make sure the ports are properly connected. You may have exceeded the maximum number of concurrent Telnet sessions. Close other Telnet session(s) or try connecting again later. Check that you have enabled Telnet service access. If you have configured a secured client IP address, your computer's IP address must match it. Refer to the chapter on access control for details.
I cannot access the web configurator.	The administrator username is "admin". The default administrator password is "1234". The username and password are case-sensitive. Make sure that you enter the correct password and username using the proper casing. If you have changed the password and have now forgotten it, you will need to upload the default configuration file. This restores all of the factory defaults including the password.
	Check that you have enabled web service access. If you have configured a secured client IP address, your computer's IP address must match it. Refer to the chapter on access control for details.
	Your computer's and the switch's IP addresses must be on the same subnet. See the following section to check that pop-up windows, JavaScripts and Java permissions are allowed.

 Table 62
 Troubleshooting Accessing the Switch

30.2.1 Pop-up Windows, JavaScripts and Java Permissions

In order to use the web configurator you need to allow:

- Web browser pop-up windows from your device.
- JavaScripts (enabled by default).
- Java permissions (enabled by default).

Note: Internet Explorer 6 screens are used here. Screens for other Internet Explorer versions may vary.


30.2.1.1 Internet Explorer Pop-up Blockers

You may have to disable pop-up blocking to log into your device.

Either disable pop-up blocking (enabled by default in Windows XP SP (Service Pack) 2) or allow pop-up blocking and create an exception for your device's IP address.

- 30.2.1.1.1 Disable pop-up Blockers
 - **1** In Internet Explorer, select **Tools**, **Pop-up Blocker** and then select **Turn Off Pop-up Blocker**.

Figure 139 Pop-up Blocker



You can also check if pop-up blocking is disabled in the **Pop-up Blocker** section in the **Privacy** tab.

- 1 In Internet Explorer, select Tools, Internet Options, Privacy.
- 2 Clear the **Block pop-ups** check box in the **Pop-up Blocker** section of the screen. This disables any web pop-up blockers you may have enabled.

nternet	Options					? 🛽
General	Security	Privacy	Content	Connections	Programs	Advanced
Settin	50	he slider ti	o select a	privacy setting I	for the Interr	net
- [_ Me	dium				
-	- priv -Bla ⊒- info Re	acy policy ocks third- rmation wi estricts first	party cook thout your -party coo	ies that do not ies that use per implicit consent kies that use per cit consent	rsonally iden t	itifiable
0	Sites		nport	Advanced.	Def	ault
Pop-u		it most pop ck pop-up		ws from appea		ngs
			ОК	Ca	ncel	Apply

Figure 140 Internet Options

3 Click **Apply** to save this setting.

30.2.1.1.2 Enable pop-up Blockers with Exceptions

Alternatively, if you only want to allow pop-up windows from your device, see the following steps.

- 1 In Internet Explorer, select Tools, Internet Options and then the Privacy tab.
- 2 Select Settings...to open the Pop-up Blocker Settings screen.

	Options					
General	Security	Privacy	Content	Connections	Programs	Advanced
Settin	58	he slider to	o select a p	privacy setting f	or the Interr	net
- [_ Me	dium				
-	- priv- -Blo ⊒- infor Re	acy policy ocks third-j rmation wil estricts first	party cook thout your -party cool	ies that do not l ies that use per implicit consent kies that use pe cit consent	sonally iden	tifiable
0	Sites		nport	Advanced.	. Def	ault
Pop-u	<u> </u>	it most pop ck pop-up:		ws from appear	ing. Setti	ngs

Figure 141 Internet Options

- **3** Type the IP address of your device (the web page that you do not want to have blocked) with the prefix "http://". For example, http://192.168.1.1.
- 4 Click Add to move the IP address to the list of Allowed sites.

Pop-up Blocker Settings	
Exceptions Pop-ups are currently blocked. You can a Web sites by adding the site to the list belo Address of Web site to allow:	
http://192.168.1.1	Add
Allowed sites:	
	Remove
	Remove All
Notifications and Filter Level	
Play a sound when a pop-up is blocked.	
Show Information Bar when a pop-up is blocked	1.
Filter Level:	
Medium: Block most automatic pop-ups	
Pop-up Blocker FAQ	Close

Figure 142 Pop-up Blocker Settings

- **5** Click **Close** to return to the **Privacy** screen.
- 6 Click Apply to save this setting.

30.2.1.2 JavaScripts

If pages of the web configurator do not display properly in Internet Explorer, check that JavaScripts are allowed.

1 In Internet Explorer, click Tools, Internet Options and then the Security tab.

Figure 143 Internet Options

Internet Options	? ×
General Security Privacy Content Connections Programs A	dvanced
Select a Web content zone to specify its security settings.	
Internet Local intranet Trusted sites Restricted sites	
Internet	
This zone contains all Web sites you Sites.	
Security level for this zone	
Move the slider to set the security level for this zone.	
- Medium	
Safe browsing and still functional	nt
 Unsigned ActiveX controls will not be downloaded 	
Appropriate for most Internet sites	
Custom Level Default Leve	
OK Cancel /	Apply

- 2 Click the Custom Level... button.
- **3** Scroll down to **Scripting**.
- 4 Under Active scripting make sure that Enable is selected (the default).
- **5** Under Scripting of Java applets make sure that Enable is selected (the default).
- 6 Click **OK** to close the window.

ecurity Settings	<u>?</u> ×
Settings:	
Scripting	
Active scripting	
O Disable	
 Enable 	
O Prompt	
Allow paste operations via script	
O Disable	
O Enable	
O Prompt	
📓 Scripting of Java applets	
O Disable	
 Enable 	
O Prompt	-
	•
l	
Reset custom settings	
Reset to: Medium	▼ Reset
Essector Inclidin	
	OK Cancel

Figure 144 Security Settings - Java Scripting

30.2.1.3 Java Permissions

- **1** From Internet Explorer, click **Tools**, **Internet Options** and then the **Security** tab.
- 2 Click the Custom Level... button.
- **3** Scroll down to **Microsoft VM**.
- 4 Under Java permissions make sure that a safety level is selected.
- **5** Click **OK** to close the window.

O Disable ⊙ Enable			<u></u>
Font download			
O Disable			
-			
	y		
all a suc		1	
		1	<u> </u>
ustom settings —			
	 Disable Enable Prompt posoft VM Java permissions Custom Disable Sura High safety Low safety Medium safet 	Font download Disable Fonble Prompt Dava permissions Custom Disable Sura Unitable Sura High safety Low safety Medium safety	Font download Disable Enable Prompt pooft VM Dava permissions Custom Disable Sura High safety Low safety Medium safety

Figure 145 Security Settings - Java

30.2.1.3.1 JAVA (Sun)

- **1** From Internet Explorer, click **Tools**, **Internet Options** and then the **Advanced** tab.
- 2 make sure that Use Java 2 for <applet> under Java (Sun) is selected.
- **3** Click **OK** to close the window.

Figure 146 Java (Sun)

Internet Options	? ×
General Security Privacy Content Connections Programs Advan	ced
<u>S</u> ettings:	
 Use inline AutoComplete Use Passive FTP (for firewall and DSL modem compatibility) Use smooth scrolling HTTP 1.1 settings Use HTTP 1.1 Use HTTP 1.1 through proxy connections Java (Sun) Use Java 2 v1.4.1_07 for <applet> (requires restart)</applet> Microsoft VM Inva console enabled (requires restart) Javalogging enabled Uncompiler for virtual machine enabled (requires restart) Always show Internet Explorer (5.0 or later) Radio toolbar Don't display online media content in the media bar Enable Automatic Image Resizing 	
<u>R</u> estore Defaults	
OK Cancel Apply	,

30.3 Problems with the Password

Table 63	Troubleshooting the Password
----------	------------------------------

PROBLEM	CORRECTIVE ACTION	
Cannot access the switch.	The password field is case sensitive. Make sure that you enter the correct password using the proper casing.	
	The administrator username is "admin". The default administrator password is "1234". The username and password are case-sensitive. Make sure that you enter the correct password and username using the proper casing. If you have changed the password and have now forgotten it, you will need to upload the default configuration file. This restores all of the factory defaults including the password.	

APPENDIX A Product Specifications

These are the switch product specifications.

Table 64	General Product Specifications
----------	--------------------------------

Ethernet	24 10/100 Base-TX interfaces
Interface	Auto-negotiation
	Auto-MDI/MDIX
	Compliant with IEEE 802.3/3u
	Back pressure flow control for half duplex
	Flow control for full duplex (IEEE 802.3x)
	RJ-45 Ethernet cable connector
	Rate limiting at 64Kbps steps
Gigabit Interface	Two Gigabit Ethernet/mini-GBIC ports
Bridging	8K MAC addresses
	Static MAC address filtering (port lock)
	Broadcast storm control
	Limited maximum number of MAC addresses per port
Switching	Switching fabric: 8.8Gbps, non-blocking
	Max. Frame size: 1522 bytes
	Forwarding frame: IEEE 802.3, IEEE 802.1q, Ethernet II, PPPoE
	Prevent the forwarding of corrupted packets
STP	IEEE 802.1d spanning tree protocol
	IEEE 802.1w, rapid reconfiguration to recover network failure
QoS	IEEE 802.1p
	Four priority queues
	Supports RFC 2475 DiffServ, DSCP to IEEE 802.1p priority mapping
Security	IEEE 802.1x port-based authentication
	Static MAC Address Forward (256 rules)
VLAN	Port-based VLAN setting
	Tag-based (IEEE 802.1Q) VLAN
	Number of VLAN: 4K (256 static VLANs)
	Supports GVRP
Link	Supports IEEE 802.3ad; static and dynamic (LACP) port trunking
aggregation	Three groups (two for fast Ethernet and one for Gigabit Ethernet)
Port mirroring	All ports support port mirroring
IGMP	Supports IGMP snooping

Table 65	Management Specifications
	management epeemeatione

System Control	Alarm/Status surveillance		
	LED indication for alarm and system status		
	Performance monitoring		
	Line speed		
	Four RMON groups (history, statistics, alarms, and events)		
	Throughput monitoring		
	CMP packet transmission		
	Port mirroring and aggregation		
	Spanning Tree Protocol		
	IGMP snooping		
	Firmware upgrade and download through FTP/TFTP		
	Login authorization and security levels (read only and read/write)		
	Self diagnostics		
	FLASH memory		
Network Management	CLI through console port and telnet		
	Web-based management		
	Up to 64management IP address in different VLAN		
	Clustering: up to 24 switches can be manage by one IP		
	SNMP		
	RMON groups (history, statistics, alarms and events)		
MIB	RFC1213 MIB II		
	RFC1493 Bridge MIB		
	RFC1643 Ethernet MIB		
	RFC1757 Four groups of RMON		
	RFC 1155 SMI		
	RFC2674 Bridge MIB extension (for IEEE 802.1Q)		
	Private MIBs		

Table 66 Physical and Environmental Specifications

LEDs	Per switch: PWR, SYS, ALM Per Ethernet port: LNK/ACT, FDX/COL
Dimension	438 mm (W) x 173 mm (D) x 44.5 mm (H) Standard 19" rack mountable
Weight	3.1Kg
Temperature	Operating: 0° C ~ 45° C (32° F ~ 113° F) Storage: -25° C ~ 70° C (13° F ~ 158° F)
Humidity	10 ~ 90% (non-condensing)
Power Supply	Overload protection 100-240VAC, 50/60Hz, 0.4A Max.

Safety	UL 60950-1
	CSA 60950-1
	EN 60950-1
	IEC 60950-1
EMC	FCC Part 15 (Class A) CE EMC (Class A)

 Table 66
 Physical and Environmental Specifications (continued)

APPENDIX B IP Subnetting

IP Addressing

Routers "route" based on the network number. The router that delivers the data packet to the correct destination host uses the host ID.

IP Classes

An IP address is made up of four octets (eight bits), written in dotted decimal notation, for example, 192.168.1.1. IP addresses are categorized into different classes. The class of an address depends on the value of its first octet.

- Class "A" addresses have a 0 in the left most bit. In a class "A" address the first octet is the network number and the remaining three octets make up the host ID.
- Class "B" addresses have a 1 in the left most bit and a 0 in the next left most bit. In a class "B" address the first two octets make up the network number and the two remaining octets make up the host ID.
- Class "C" addresses begin (starting from the left) with 1 1 0. In a class "C" address the first three octets make up the network number and the last octet is the host ID.
- Class "D" addresses begin with 1 1 1 0. Class "D" addresses are used for multicasting. (There is also a class "E" address. It is reserved for future use.)

IP ADDRESS:		OCTET 1	OCTET 2	OCTET 3	OCTET 4
Class A	0	Network number	Host ID	Host ID	Host ID
Class B	10	Network number	Network number	Host ID	Host ID
Class C	110	Network number	Network number	Network number	Host ID

Table 67 Classes of IP Addresses

Note: Host IDs of all zeros or all ones are not allowed.

Therefore:

A class "C" network (8 host bits) can have $2^8 - 2$ or 254 hosts.

A class "B" address (16 host bits) can have 2^{16} –2 or 65534 hosts.

A class "A" address (24 host bits) can have 2²⁴ –2 hosts (approximately 16 million hosts).

Since the first octet of a class "A" IP address must contain a "0", the first octet of a class "A" address can have a value of 0 to 127.

Similarly the first octet of a class "B" must begin with "10", therefore the first octet of a class "B" address has a valid range of 128 to 191. The first octet of a class "C" address begins with "110", and therefore has a range of 192 to 223.

CLASS	ALLOWED RANGE OF FIRST OCTET (BINARY)	ALLOWED RANGE OF FIRST OCTET (DECIMAL)
Class A	0 0000000 to 0 1111111	0 to 127
Class B	10 000000 to 10 111111	128 to 191
Class C	110 00000 to 110 11111	192 to 223
Class D	1110 0000 to 1110 1111	224 to 239

Table 68 Allowed IP Address Range By Class

Subnet Masks

A subnet mask is used to determine which bits are part of the network number, and which bits are part of the host ID (using a logical AND operation). A subnet mask has 32 is a "1" then the corresponding bit in the IP address is part of the network number. If a bit in the subnet mask is "0" then the corresponding bit in the IP address is part of the host ID.

Subnet masks are expressed in dotted decimal notation just as IP addresses are. The "natural" masks for class A, B and C IP addresses are as follows.

CLASS	NATURAL MASK	
A	255.0.0.0	
В	255.255.0.0	
С	255.255.255.0	

Table 69 "Natural" Masks

Subnetting

With subnetting, the class arrangement of an IP address is ignored. For example, a class C address no longer has to have 24 bits of network number and 8 bits of host ID. With subnetting, some of the host ID bits are converted into network number bits. By convention, subnet masks always consist of a continuous sequence of ones beginning from the left most bit of the mask, followed by a continuous sequence of zeros, for a total number of 32 bits.

Since the mask is always a continuous number of ones beginning from the left, followed by a continuous number of zeros for the remainder of the 32 bit mask, you can simply specify the number of ones instead of writing the value of each octet. This is usually specified by writing a "/" followed by the number of bits in the mask after the address.

For example, 192.1.1.0 /25 is equivalent to saying 192.1.1.0 with mask 255.255.255.128.

The following table shows all possible subnet masks for a class "C" address using both notations.

SUBNET MASK IP ADDRESS	SUBNET MASK "1" BITS	LAST OCTET BIT VALUE
255.255.255.0	/24	0000 0000
255.255.255.128	/25	1000 0000
255.255.255.192	/26	1100 0000
255.255.255.224	/27	1110 0000
255.255.255.240	/28	1111 0000
255.255.255.248	/29	1111 1000
255.255.255.252	/30	1111 1100

Table 70 Alternative Subnet Mask Notation

The first mask shown is the class "C" natural mask. Normally if no mask is specified it is understood that the natural mask is being used.

Example: Two Subnets

As an example, you have a class "C" address 192.168.1.0 with subnet mask of 255.255.255.0.

Table 71 Two Subnets Example

The first three octets of the address make up the network number (class "C"). You want to have two separate networks.

Divide the network 192.168.1.0 into two separate subnets by converting one of the host ID bits of the IP address to a network number bit. The "borrowed" host ID bit can be either "0" or "1" thus giving two subnets; 192.168.1.0 with mask 255.255.255.128 and 192.168.1.128 with mask 255.255.255.128.

Note: In the following charts, shaded/bolded last octet bit values indicate host ID bits "borrowed" to form network ID bits. The number of "borrowed" host ID bits determines the number of subnets you can have. The remaining number of host ID bits (after "borrowing") determines the number of hosts you can have on each subnet.

	NETWORK NUMBER	LAST OCTET BIT VALUE
IP Address	192.168.1.	0
IP Address (Binary)	11000000.10101000.00000001.	0 0000000
Subnet Mask	255.255.255.	128
Subnet Mask (Binary)	11111111.1111111.11111111.	1000000
Subnet Address: 192.168.1.0	Lowest Host ID: 192.168.1.1	
Broadcast Address: 192.168.1.127	5 · · · · · ·	

Table 72 Subnet 1

Table 73 Subnet 2

	NETWORK NUMBER	LAST OCTET BIT VALUE	
IP Address	192.168.1.	128	
IP Address (Binary)	11000000.10101000.00000001.	1000000	
Subnet Mask	255.255.255.	128	
Subnet Mask (Binary)	1111111.1111111.1111111.	1000000	
Subnet Address: 192.168.1.128	Lowest Host ID: 192.168.1.129		
Broadcast Address: 192.168.1.255	Highest Host ID: 192.168.1.254	Highest Host ID: 192.168.1.254	

The remaining 7 bits determine the number of hosts each subnet can have. Host IDs of all zeros represent the subnet itself and host IDs of all ones are the broadcast address for that subnet, so the actual number of hosts available on each subnet in the example above is $2^7 - 2$ or 126 hosts for each subnet.

192.168.1.0 with mask 255.255.255.128 is the subnet itself, and 192.168.1.127 with mask 255.255.255.128 is the directed broadcast address for the first subnet. Therefore, the lowest IP address that can be assigned to an actual host for the first subnet is 192.168.1.1 and the highest is 192.168.1.126. Similarly the host ID range for the second subnet is 192.168.1.129 to 192.168.1.254.

Example: Four Subnets

Table 74 Subnet 1

	NETWORK NUMBER	LAST OCTET BIT VALUE
IP Address	192.168.1.	0
IP Address (Binary)	11000000.10101000.00000001.	00 000000
Subnet Mask (Binary)	11111111.1111111.1111111.	11 000000
Subnet Address: 192.168.1.0	Lowest Host ID: 192.168.1.1	
Broadcast Address: 192.168.1.63	Highest Host ID: 192.168.1.62	

Table 75 Subnet 2

	NETWORK NUMBER	LAST OCTET BIT VALUE
IP Address	192.168.1.	64
IP Address (Binary)	11000000.10101000.00000001.	01 000000
Subnet Mask (Binary)	11111111.1111111.11111111.	11 000000
Subnet Address: 192.168.1.64	Lowest Host ID: 192.168.1.65	
Broadcast Address: 192.168.1.127	Highest Host ID: 192.168.1.126	

Table 76 Subnet 3

	NETWORK NUMBER	LAST OCTET BIT VALUE
IP Address	192.168.1.	128
IP Address (Binary)	11000000.10101000.00000001.	10 000000
Subnet Mask (Binary)	11111111.1111111.11111111.	11 000000
Subnet Address: 192.168.1.128	Lowest Host ID: 192.168.1.129	
Broadcast Address: 192.168.1.191	Highest Host ID: 192.168.1.190	

Table 77	Subnet 4
----------	----------

	NETWORK NUMBER	LAST OCTET BIT VALUE
IP Address	192.168.1.	192
IP Address (Binary)	11000000.10101000.00000001.	11 000000
Subnet Mask (Binary)	1111111.1111111.11111111.	11 000000
Subnet Address: 192.168.1.192	Lowest Host ID: 192.168.1.193	
Broadcast Address: 192.168.1.255	Highest Host ID: 192.168.1.254	

Example Eight Subnets

Similarly use a 27-bit mask to create 8 subnets (001, 010, 011, 100, 101, 110).

The following table shows class C IP address last octet values for each subnet.

SUBNET	SUBNET ADDRESS	FIRST ADDRESS	LAST ADDRESS	BROADCAST ADDRESS
1	0	1	30	31
2	32	33	62	63
3	64	65	94	95
4	96	97	126	127
5	128	129	158	159
6	160	161	190	191
7	192	193	222	223
8	224	223	254	255

The following table is a summary for class "C" subnet planning.

Table 79 Class C Subnet Planning

NO. "BORROWED" HOST BITS	SUBNET MASK	NO. SUBNETS	NO. HOSTS PER SUBNET
1	255.255.255.128 (/25)	2	126
2	255.255.255.192 (/26)	4	62
3	255.255.255.224 (/27)	8	30
4	255.255.255.240 (/28)	16	14
5	255.255.255.248 (/29)	32	6
6	255.255.255.252 (/30)	64	2
7	255.255.255.254 (/31)	128	1

Subnetting With Class A and Class B Networks.

For class "A" and class "B" addresses the subnet mask also determines which bits are part of the network number and which are part of the host ID.

A class "B" address has two host ID octets available for subnetting and a class "A" address has three host ID octets (see Table 67 on page 207) available for subnetting.

The following table is a summary for class "B" subnet planning.

NO. "BORROWED" HOST BITS	SUBNET MASK	NO. SUBNETS	NO. HOSTS PER SUBNET
1	255.255.128.0 (/17)	2	32766
2	255.255.192.0 (/18)	4	16382
3	255.255.224.0 (/19)	8	8190
4	255.255.240.0 (/20)	16	4094
5	255.255.248.0 (/21)	32	2046
6	255.255.252.0 (/22)	64	1022
7	255.255.254.0 (/23)	128	510
8	255.255.255.0 (/24)	256	254
9	255.255.255.128 (/25)	512	126
10	255.255.255.192 (/26)	1024	62
11	255.255.255.224 (/27)	2048	30
12	255.255.255.240 (/28)	4096	14
13	255.255.255.248 (/29)	8192	6
14	255.255.255.252 (/30)	16384	2
15	255.255.255.254 (/31)	32768	1

Table 80 Class B Subnet Planning

Index

Symbols

"standby" ports 93

Numerics

110V AC 3 230V AC 3 802.1P priority 64

A

AC 3 Access control 119 Access priority 119 Limitation 119 Login account 122 Remote management 131 Service port 131 **SNMP 120** Accessories 3 Address Resolution Protocol (ARP) 143 Administrator password 123 Aggregator ID 95 Aging time 59 Airflow 3 Alternative Subnet Mask Notation 209 American Wire Gauge 3 Application 25 Backbone 25 Bridging 26 IEEE 802.1Q VLAN 27 Switched workgroup 26 ARP 143 How it works 143 View 143 Authority 2 Automatic VLAN registration 66 AWG 3

В

Basement 3 Basic setting 55 BPDUs (Bridge Protocol Data Units) 82 Bridge Protocol Data Units (BPDUs) 82 Broadcast storm control 89

С

Cables, Connecting 3 CFI (Canonical Format Indicator) 65 Change password 43 Changes or Modifications 2 CI Commands 148 Class of Service (CoS) 109 **CLI** Command Configure tagged VLAN example 184 Static VLAN Table example 189 Cluster management 25, 135 Cluster manager 135, 139 Cluster member 135, 139 Cluster member firmware upgrade 137 Network example 135 Setup 138 Specification 135 Status 136 Switch models 135 **VID 139** Web configurator 137 Cluster manager 135 Cluster member 135 Command Forwarding Process Example 189 Summary 151 Syntax conventions 148 **Command Line Interface** Accessing 145 Introduction 145 Configuration file 44 Backup 115 Restore 44, 114 Connecting Cables 3 Console port 25 Settings 33

Copyright 1 Corrosive Liquids 3 Covers 3 CPU management port 72 CRC (Cyclic Redundant Check) 54 Current date 57 Current time 57 Customer Support 5

D

Damage 3 Dampness 3 Danger 3 Denmark, Contact Information 5 DHCP 23 DHCP (Dynamic Host Configuration Protocol) 23 Diagnostic 133 Ethernet port test 133 Ping 133 System log 133 Differentiated Service (DiffServ) 109 DiffServ 109 Activate 110 DS field 109 **DSCP 109** DSCP-to-IEEE802.1p mapping 111 Network example 109 PHB 109 DS (Differentiated Services) 109 DSCP DSCP-to-IEEE802.1p mapping 111 Service level 109 What it does 109 DSCP (DiffServ Code Point) 109 Dust 3 DVLAN Table 183 Dynamic link aggregation 93

Ε

Egress port Electric Shock Electrical Pipes Electrocution Ethernet broadcast address Ethernet port test Ethernet ports Default settings 34 Europe 3 Exposure 3 Extended authentication protocol 99 External authentication server 99

F

FCC Compliance 2 Feature Hardware 25 File Transfer using FTP command example 117 Filename convention 116 Filterina 79 Filtering database 141 Finland, Contact Information 5 Firmware 55 Upgrade 114, 137 Flow control 64 Back pressure 64 IEEE802.3x 64 France, Contact Information 5 Front panel 33 FTP 116 File transfer procedure 117 Restrictions over WAN 118

G

GARP 66, 184 GARP (Generic Attribute Registration Protocol) 66 garp status 185 GARP Status Command 185 GARP timer 59, 66 Gas Pipes 3 General setup 56 Germany, Contact Information 5 Getting help 46 GMT (Greenwich Mean Time) 57 GVRP 66, 71, 72, 184 GVRP (GARP VLAN Registration Protocol) 66, 178 gvrp disable 187 gvrp enable 186 gvrp status 186

Η

Hardware installation 29 Hardware overview 33 High Voltage Points 3 Host IDs 207 How SSH works 124 HTTPS 126 HTTPS Example 127

IEEE 802.1p 60 IEEE 802.1Q Tagged VLAN 183 IEEE 802.1x 99 Activate 100 Note 99 Reauthentication 100 IGMP snooping 58, 59 Ingress port 75 Installation Freestanding 29 Precautions 30 Rack-mounting 30 Introduction 23 IP Addressing 207 IP Classes 207 IP interface 60 IP setup 60 iStacking 25

L

LACP 93 System priority 96 Timeout 97 LEDs 37 Lightning 3 Limit MAC address learning 104 Link Aggregate Control Protocol (LACP) 93 Link aggregation 24, 93 Dynamic 93 ID information 94 Setup 95 Status 94 Liquids, Corrosive 3 Lockout 44 Log 133 Login 39 Password 43 Login account 122 Administrator 122 Non-administrator 122 Number of 122 Login password 123

Μ

MAC (Media Access Control) 55 MAC address 55, 143 Maximum number per port 104 MAC address learning 24, 59, 77, 103, 104 Specify limit 104 MAC table 141 How it works 141 View 142 Maintenance 113 Management Information Base (MIB) 120 Management port 75 MIB 120 Supported MIBs 121 Mini GBIC ports 34 Connection speed 35 Connector type 34 Transceiver installation 35 Transceiver removal 35 Mirror port 91 Modifications 2 Mounting brackets 30 MSA (MultiSource Agreement) 34 MTU (Multi-Tenant Unit) 58

Ν

Network management system (NMS) 120 North America 3 North America Contact Information 5 Norway, Contact Information 5 NTP (RFC-1305) 57

0

Opening 3

Ρ

Password 43, 140 PHB (Per-Hop Behavior) 109 Ping 133 Pipes 3 Pool 3 Port authentication 99 IEEE802.1x 100 RADIUS server 101 Port Based VLAN Type 59 Port details 52 Port isolation 71, 75 Port Mirroring 163, 178 Port mirroring 24, 91 Mirror port 91 Port redundancy 93 Port security 24, 103 Limit MAC address learning 104 Port setup 62 Port speed/duplex 63 Port status 51 Port VID Default for all ports 164 Port VLAN trunking 67 Port-based VLAN 72 All connected 75 Port isolation 75 Setting Wizard 75 Power Adaptor 3 Power Cord 3 Power Outlet 3 Power Supply 3 Power Supply, repair 3 Priority 60 Priority level 60 Priority queue assignment 60 Product specification 203 PVID 65. 72 PVID (Priority Frame) 65

Q

Qualified Service Personnel 3 Quality of Service (QoS) 109 Queue weight 106 Queuing 24, 105 Queuing algorithm 105, 106 Queuing method 105, 106

R

RADIUS 99 RADIUS (Remote Authentication Dial In User Service) 99 RADIUS server 99 Advantages 99 Network example 99 Settings 101 Rear panel 36 Regular Mail 5 Related Documentation 21 Remote management 131 Service 132 Trusted computers 132 Removing 3 Repair 3 Reset 44 Reset to factory default settings 115 Restore configuration 44 Risk 3 Risks 3 Round Robin Scheduling 105 RSTP (Rapid STP) 24 Rubber feet 29

S

Safety Warnings 3 Service 3, 4 Service access control 131 Service port 131 Service Personnel 3 Shock, Electric 3 Simple Network Management Protocol (SNMP) 120 **SNMP 120** Agent 120 Communities 122 Management model 120 Manager 120 MIB 120, 121 Network components 120 Object variables 120 Protocol operations 120 Setup 121 Traps 121 Versions supported 120 Spain, Contact Information 5 Spanning Tree Protocol (STP) 81 SSH 123

SSH Implementation 125 Static MAC address 24, 77, 103 Static MAC forwarding 77 Static VLAN 69 Control 70 Tagging 70 Status 40, 51 LED 37 Link aggregation 94 Port 51 Port details 52 STP 82 VLAN 68 STP 81 Bridge ID 83 Bridge priority 85 Configuration 84 Designated bridge 81 Forwarding Delay 85 Hello BPDU 82 Hello Time 83, 85 How it works 82 Max Age 83, 85 Path cost 81, 85 Port priority 85 Port state 82 Root port 81 Status 82 Terminology 81 STP (Spanning Tree Protocol) 24 Strict Priority Queuing (SPQ) 105 Subnet Masks 208 Subnetting 208 Supply Voltage 3 Support E-mail 5 SVLAN Table 183 Sweden, Contact Information 5 Swimming Pool 3 Switch lockout 44 Switch reset 44 Switch setup 58 Syntax Conventions 21 sys Commands examples 167, 172, 176 sys log disp 168, 172, 176 sys sw mac list 169 System information 55 System log 133 System reboot 116 System up time 52

Т

Tagged VLAN 65 Telecommunication Line Cord. 3 Telephone 5 Thunderstorm 3 Time Current 57 Time zone 57 Timeserver 57 Time (RFC-868) 57 Time service protocol 57 Time format 57 Time zone 57 Timeserver 57 Transceiver Installation 35 Removal 35 Trap Destination 122 Traps 121 Trunk group 93 Trunking 24, 93 Type of Service (ToS) 109

U

UTC (Universal Time Coordinated) 57

V

Vendor 3 Ventilation 29 Ventilation holes 29 Ventilation Slots 3 VID 62, 65, 69 Number of possible VIDs 65 Priority frame 65 VID (VLAN Identifier) 65 VLAN 57, 65 Acceptable frame type 72 Automatic registration 66 Explicit Tagging 183 ID 65 ID (VID) 184 Implicit Tagging 183 Ingress filtering 72 Introduction 57

Number of VLANs 69 Port isolation 71 Port number 69 Port settings 71 Port-based VLAN 72 Registration Information 183 Static VLAN 69 Status 68, 69 Tagged 65 Trunking 67 Type 59, 67 VLAN (Virtual Local Area Network) 23, 57 VLAN Databases 183 VLAN number 62 VLAN trunking 72 vlan1q port accept 188 vlan1q port gvrp 188 vlan1q svlan active 190 vlan1q svlan delentry 190 vlan1q svlan inactive 191 vlan1q svlan list 191 vlan1q svlan setentry 188 Voltage Supply 3 Voltage, High 3

W

Wall Mount 3 Warnings 3 Water 3 Water Pipes 3 Web configuration Screen summary 41 Web configurator Getting help 46 Home 40 Login 39 Logout 45 Navigation panel 40 Web Site 5 Weighted Round Robin Scheduling (WRR) 106 Wet Basement 3 Worldwide Contact Information 5

Ζ

ZyNOS (ZyXEL Network Operating System) 117 ZyXEL Limited Warranty Note 4